** WARNING ** WARNING ** WARNING ** This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, exerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.



STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS AND

SPECIAL PROVISIONS

FOR CONSTRUCTION ON STATE HIGHWAY IN

SHASTA COUNTY NEAR MOUNTAIN GATE FROM 0.8 km NORTH OF BRIDGE BAY OVERCROSSING TO 0.8 km SOUTH OF TURNTABLE BAY OVERCROSSING

	DISTRICT 02, ROUTE 5
For Use in Connection wi	th Standard Specifications Dated JULY 1999, Standard Plans Dated JULY 1999, and Labo Surcharge and Equipment Rental Rates.
-	

CONTRACT NO. 02-364904 02-Sha-5-R45.2/R46.4 Bids Open: December 11, 2001 Dated: November 19, 2001

OSD

IMPORTANT SPECIAL NOTICES

Attention is directed to the Notice to Contractor and Section 1, "Plans and Specifications," of the special provisions
regarding references to the District and District Director's Office. The Office of the District Director for the
Northern Region is located at Marysville.

Payment Bonds

Attention is directed to Section 5 of the Special Provisions, regarding contract bonds. The payment bond shall be in a sum not less than one hundred percent of the total amount payable by the terms of the contract.

TABLE OF CONTENTS

NOTICE TO CONTRACTORS	1
COPY OF ENGINEER'S ESTIMATE	3
SPECIAL PROVISIONS	4
SECTION 1. SPECIFICATIONS AND PLANS	4
SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS	4
2-1.01 GENERAL	
2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)	Δ
2-1.03 DVBE GOAL FOR THIS PROJECT	
2-1.04 SUBMISSION OF DVBE INFORMATION	
2-1.05 SMALL BUSINESS PREFERENCE	
2-1.06 CALIFORNIA COMPANY PREFERENCE	
SECTION 3. AWARD AND EXECUTION OF CONTRACT	
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES	
SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES	
SECTION 5. GENERAL SECTION 5-1. MISCELLANEOUS	c
5-1.01 PLANS AND WORKING DRAWINGS	
5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK	
5-1.012 DIFFERING SITE CONDITIONS	
5-1.015 LABORATORY	
5-1.017 CONTRACT BONDS	
5-1.018 EXCAVATION SAFETY PLANS	
5-1.019 COST REDUCTION INCENTIVE	
5-1.02 LABOR NONDISCRIMINATION	
5-1.03 INTEREST ON PAYMENTS	
5-1.031 FINAL PAYMENT AND CLAIMS	
5-1.04 PUBLIC SAFETY	11
5-1.05 SURFACE MINING AND RECLAMATION ACT	
5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES	12
5-1.07 YEAR 2000 COMPLIANCE	12
5-1.08 SUBCONTRACTOR AND DVBE RECORDS	13
5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS	13
5-1.09 SUBCONTRACTING	13
5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS	
5-1.11 AREAS FOR CONTRACTOR'S USE	14
5-1.12 PAYMENTS	
SECTION 6. (BLANK)	
SECTION 7. (BLANK)	
SECTION 8. MATERIALS	
SECTION 8-1. MISCELLANEOUS	14
8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS	
8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS	
8-1.03 MISCELLANEOUS METAL	
SECTION 8-2. CONCRETE	
8-2.01 PORTLAND CEMENT CONCRETE	
SECTION 8-3. WELDING	
8-3.01 WELDING	
GENERAL	
WELDING QUALITY CONTROL	
PAYMENT	
SECTION 9. DESCRIPTION OF BRIDGE WORK	
SECTION 10. CONSTRUCTION DETAILS	
SECTION 10-1. GENERAL	
10-1.01 ORDER OF WORK	
10-1.02 PREVENTION OF SWALLOW NESTING AND BAT ROOSTING	34

10-1.03 WATER POLLUTION CONTROL	34
WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES	
WPCP IMPLEMENTATION	36
MAINTENANCE	37
PAYMENT	37
10-1.04 COOPERATION	37
10-1.05 PROGRESS SCHEDULE	37
10-1.06 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES	38
10-1.07 CONSTRUCTION AREA SIGNS	38
10-1.08 MAINTAINING TRAFFIC	
10-1.09 CLOSURE REQUIREMENTS AND CONDITIONS	40
CLOSURE SCHEDULE	40
CONTINGENCY PLAN	
LATE REOPENING OF CLOSURES	40
COMPENSATION	40
10-1.10 CONSTRUCTION ZONE ENHANCED ENFORCEMENT	40
10-1.11 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE	
10-1.12 PORTABLE CHANGEABLE MESSAGE SIGN	42
10-1.13 TEMPORARY CRASH CUSHION MODULE	
10-1.14 EXISTING HIGHWAY FACILITIES	
EXISTING PAINT SYSTEMS	
BRIDGE REMOVAL	46
REPLACE STEEL PEDESTAL	
10-1.15 FALSEWORK	48
10-1.16 EPOXY CRACK INJECTION	
MATERIALS	
PREPARATION	
INJECTION	50
MEASUREMENT AND PAYMENT	50
10-1.17 STEEL STRUCTURES	50
GENERAL	50
MATERIALS	51
BOLTED CONNECTIONS	51
ROTATIONAL CAPACITY TESTING PRIOR TO SHIPMENT TO JOB SITE	51
INSTALLATION TENSION TESTING AND ROTATIONAL CAPACITY TESTING AFTER ARRI	
THE JOB SITE	56
SURFACE PREPARATION	
SEALING	
MEASUREMENT AND PAYMENT	56
10-1.18 REPAIR WELD	
10-1.19 CLEAN AND PAINT STRUCTURAL STEEL	
CLEANING	
PAINTING	
MEASUREMENT AND PAYMENT	
SECTION 11. MODIFIED STANDARD SPECIFICATION SECTIONS	
SECTION 11-2. PORTLAND CEMENT CONCRETE	
SECTION 12. (BLANK)	
SECTION 11. MODIFIED STANDARD SPECIFICATION SECTIONS SECTION 11-1. (BLANK)SECTION 11-2. PORTLAND CEMENT CONCRETE	60 60

STANDARD PLANS LIST

The Standard Plan sheets applicable to this contract include, but are not limited to those indicated below. The Revised Standard Plans (RSP) and New Standard Plans (NSP) which apply to this contract are included as individual sheets of the project plans.

A10A	Abbreviations
A10B	Symbols

T10 Traffic Control System for Lane Closure On Freeways and Expressways

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

CONTRACT NO. 02-364904

02-Sha-5-R45.2/R46.4

Sealed proposals for the work shown on the plans entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROJECT PLANS FOR CONSTRUCTION ON STATE HIGHWAY IN SHASTA COUNTY NEAR MOUNTAIN GATE FROM 0.8 km NORTH OF BRIDGE BAY OVERCROSSING TO 0.8 km SOUTH OF TURNTABLE BAY OVERCROSSING

will be received at the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, CA 95814, until 2 o'clock p.m. on December 11, 2001, at which time they will be publicly opened and read in Room 0100 at the same address.

Proposal forms for this work are included in a separate book entitled:

STATE OF CALIFORNIA; DEPARTMENT OF TRANSPORTATION; PROPOSAL AND CONTRACT FOR CONSTRUCTION ON STATE HIGHWAY IN SHASTA COUNTY NEAR MOUNTAIN GATE FROM 0.8 km NORTH OF BRIDGE BAY OVERCROSSING TO 0.8 km SOUTH OF TURNTABLE BAY OVERCROSSING

General work description: Rehabilitate Bridge and Overhead.

This project has a goal of 3 percent disabled veteran business enterprise (DVBE) participation.

No prebid meeting is scheduled for this project.

Bids are required for the entire work described herein.

At the time this contract is awarded, the Contractor shall possess either a Class A license or any combination of the following Class C licenses which constitutes a majority of the work: C-32, C-51.

The Contractor must also be properly licensed at the time the bid is submitted, except that on a joint venture bid a joint venture license may be obtained by a combination of licenses after bid opening but before award in conformance with Business and Professions Code, Section 7029.1.

This contract is subject to state contract nondiscrimination and compliance requirements pursuant to Government Code, Section 12990.

Preference will be granted to bidders properly certified as a "Small Business" as determined by the Department of General Services, Office of Small Business Certification and Resources at the time of bid opening in conformance with the provisions in Section 2-1.05, "Small Business Preference," of the special provisions, and Section 1896 et seq, Title 2, California Code of Regulations. A form for requesting a "Small Business" preference is included with the bid documents. Applications for status as a "Small Business" must be submitted to the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, Telephone No. (916) 322-5060.

A reciprocal preference will be granted to "California company" bidders in conformance with Section 6107 of the Public Contract Code. (See Sections 2 and 3 of the special provisions.) A form for indicating whether bidders are or are not a "California company" is included in the bid documents and is to be filled in and signed by all bidders.

The District in which the work for this project is located has been incorporated into the Department's Northern Region. References in the Standard Specifications or in the special provisions to the district shall be deemed to mean the Northern Region. The office of the District Director for the Northern Region is located at Marysville.

Project plans, special provisions, and proposal forms for bidding this project can only be obtained at the Department of Transportation, Plans and Bid Documents, Room 0200, MS #26, Transportation Building, 1120 N Street, Sacramento, California 95814, FAX No. (916) 654-7028, Telephone No. (916) 654-4490. Use FAX orders to expedite orders for project plans, special provisions and proposal forms. FAX orders must include credit card charge number, card expiration date and authorizing signature. Project plans, special provisions, and proposal forms may be seen at the above Department of Transportation office and at the offices of the District Directors of Transportation at Irvine, Oakland, and the district in which the work is situated. Standard Specifications and Standard Plans are available through the State of California, Department of Transportation, Publications Unit, 1900 Royal Oaks Drive, Sacramento, CA 95815, Telephone No. (916) 445-3520.

Cross sections for this project are not available.

The successful bidder shall furnish a payment bond and a performance bond.

Pursuant to Section 1773 of the Labor Code, the general prevailing wage rates in the county, or counties, in which the work is to be done have been determined by the Director of the California Department of Industrial Relations. These wages are set forth in the General Prevailing Wage Rates for this project, available at the Labor Compliance Office at the offices of the District Director of Transportation for the district in which the work is situated, and available from the California Department of Industrial Relations' Internet Web Site at: http://www.dir.ca.gov. Future effective general prevailing wage rates which have been predetermined and are on file with the Department of Industrial Relations are referenced but not printed in the general prevailing wage rates.

DEPARTMENT OF TRANSPORTATION

Deputy Director Transportation Engineering

Dated November 19, 2001

REG

COPY OF ENGINEER'S ESTIMATE (NOT TO BE USED FOR BIDDING PURPOSES) 02-364904

Item	Item Code	Item	Unit of Measure	Estimated Quantity
1 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM
2 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM
3 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	LS	LUMP SUM
4	157560	BRIDGE REMOVAL (PORTION)	LS	LUMP SUM
5	048836	REPLACE STEEL PEDESTAL	EA	3
6	511130	INJECT CRACK (EPOXY)	M	47
7	048837	REPAIR WELD (FILLET)	M	8
8	048838	REPAIR WELD (FULL PENETRATION)	M	1.2
9 (S-F)	550102	STRUCTURAL STEEL (BRIDGE)	KG	18
10 (S)	590115	CLEAN AND PAINT STRUCTURAL STEEL	LS	LUMP SUM
11 (S)	590135	SPOT BLAST CLEAN AND PAINT UNDERCOAT	M2	9
12 (S)	590301	WORK AREA MONITORING	LS	LUMP SUM
13	999990	MOBILIZATION	LS	LUMP SUM

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISIONS

Annexed to Contract No. 02-364904

SECTION 1. SPECIFICATIONS AND PLANS

The work embraced herein shall conform to the provisions in the Standard Specifications dated July 1999, and the Standard Plans dated July 1999, of the Department of Transportation insofar as the same may apply, and these special provisions.

Amendments to the Standard Specifications set forth in these special provisions shall be considered as part of the Standard Specifications for the purposes set forth in Section 5-1.04, "Coordination and Interpretation of Plans, Standard Specifications and Special Provisions," of the Standard Specifications. Whenever either the term "Standard Specifications is amended" or the term "Standard Specifications are amended" is used in the special provisions, the indented text or table following the term shall be considered an amendment to the Standard Specifications. In case of conflict between such amendments and the Standard Specifications, the amendments shall take precedence over and be used in lieu of the conflicting portions.

The District in which the work for this project is located has been incorporated into the Department's Northern Region. References in the Standard Specifications or in these special provisions to the district shall be deemed to mean the Northern Region. The office of the District Director for the Northern Region is located at Marysville.

In case of conflict between the Standard Specifications and these special provisions, the special provisions shall take precedence over and shall be used in lieu of the conflicting portions.

SECTION 2. PROPOSAL REQUIREMENTS AND CONDITIONS

2-1.01 GENERAL

The bidder's attention is directed to the provisions in Section 2, "Proposal Requirements and Conditions," of the Standard Specifications and these special provisions for the requirements and conditions which the bidder must observe in the preparation of the proposal form and the submission of the bid.

In addition to the subcontractors required to be listed in conformance with Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications, each proposal shall have listed therein the name and address of each DVBE subcontractor to be used for credit in meeting the goal, and to whom the bidder proposes to directly subcontract portions of the work. The list of subcontractors shall also set forth the portion of work that will be performed by each subcontractor listed. A sheet for listing the subcontractors is included in the Proposal.

The Bidder's Bond form mentioned in the last paragraph in Section 2-1.07, "Proposal Guaranty," of the Standard Specifications will be found following the signature page of the Proposal.

In conformance with Public Contract Code Section 7106, a Noncollusion Affidavit is included in the Proposal. Signing the Proposal shall also constitute signature of the Noncollusion Affidavit.

Submit request for substitution of an "or equal" item, and the data substantiating the request to the Department of Transportation, P.O. Box 911, Marysville, CA 95901, Attn: NRCO/Contract Administration Engineer, so that the request is received by the Department by close of business on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening.

2-1.02 DISABLED VETERAN BUSINESS ENTERPRISE (DVBE)

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veteran Business Enterprise (DVBE) in contracts.

It is the policy of the Department that Disabled Veteran Business Enterprise (DVBE) shall have the maximum opportunity to participate in the performance of contracts financed solely with state funds. The Contractor shall ensure that DVBEs have the maximum opportunity to participate in the performance of this contract and shall take all necessary and reasonable steps for this assurance. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the award and performance of subcontracts. Failure to carry out the requirements of this paragraph shall constitute a breach of contract and may result in termination of this contract or other remedy the Department may deem appropriate.

Bidder's attention is directed to the following:

- A. "Disabled Veteran Business Enterprise" (DVBE) means a business concern certified as a DVBE by the Office of Small Business Certification and Resources, Department of General Services.
- B. A DVBE may participate as a prime contractor, subcontractor, joint venture partner with a prime or subcontractor, or vendor of material or supplies.
- C. Credit for DVBE prime contractors will be 100 percent.
- D. A DVBE joint venture partner must be responsible for specific contract items of work, or portions thereof. Responsibility means actually performing, managing and supervising the work with its own forces. The DVBE joint venture partner must share in the ownership, control, management responsibilities, risks and profits of the joint

venture. The DVBE joint venturer must submit the joint venture agreement with the Caltrans Bidder DVBE Information form required in Section 2-1.04, "Submission of DVBE Information," elsewhere in these special provisions.

- E. A DVBE must perform a commercially useful function, i.e., must be responsible for the execution of a distinct element of the work and must carry out its responsibility by actually performing, managing and supervising the work.
- F. Credit for DVBE vendors of materials or supplies is limited to 60 percent of the amount to be paid to the vendor for the material unless the vendor manufactures or substantially alters the goods.
- G. Credit for trucking by DVBEs will be as follows:
 - 1. One hundred percent of the amount to be paid when a DVBE trucker will perform the trucking with his/her own trucks, tractors and employees.
 - 2. Twenty percent of the amount to be paid to DVBE trucking brokers who do not have a "certified roster."
 - 3. One hundred percent of the amount to be paid to DVBE trucking brokers who have signed agreements that all trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that all trucks are owned by DVBEs, and a signed statement on the "certified roster" that indicates that 100 percent of revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."
 - 4. Twenty percent of the amount to be paid to trucking brokers who are not a DVBE but who have signed agreements with DVBE truckers assuring that at least 20 percent of the trucking will be performed by DVBE truckers if credit is toward the DVBE goal, a "certified roster" showing that at least 20 percent of the number of trucks are owned by DVBE truckers, and a signed statement on the "certified roster" that indicates that at least 20 percent of the revenue paid by the broker will be paid to the DVBEs listed on the "certified roster."

The "certified roster" referred to herein shall conform to the requirements in Section 2-1.04, "Submission Of DVBE Information," elsewhere in these special provisions.

- H. DVBEs and DVBE joint venture partners must be certified DVBEs as determined by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814, on the date bids for the project are opened before credit may be allowed toward the DVBE goal. It is the Contractor's responsibility to verify that DVBEs are certified.
- I. Noncompliance by the Contractor with these requirements constitutes a breach of this contract and may result in termination of the contract or other appropriate remedy for a breach of this contract.

2-1.03 DVBE GOAL FOR THIS PROJECT

The Department has established the following goal for Disabled Veteran Business Enterprise (DVBE) participation for this project:

Disabled Veteran Business Enterprise (DVBE): 3 percent.

It is the bidder's responsibility to make a sufficient portion of the work available to subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DVBE subcontractors and suppliers, so as to assure meeting the goal for DVBE participation.

The Office of Small Business Certification and Resources, Department of General Services, may be contacted at (916) 322-5060 or visit their internet web site at http://www.osmb.dgs.ca.gov/ for program information and certification status. The Department's Business Enterprise Program may also be contacted at (916) 227-9599 or the internet web site at http://www.dot.ca.gov/hq/bep/.

2-1.04 SUBMISSION OF DVBE INFORMATION

The required DVBE information shall be submitted on the "CALTRANS BIDDER - DVBE INFORMATION" form included in the Proposal. If this information is not submitted with the bid, the DVBE information forms shall be removed from the documents prior to submitting the bid.

It is the bidder's responsibility to make enough work available to DVBEs and to select those portions of the work or material needs consistent with the available DVBEs to meet the goal for DVBE participation or to provide information to establish that, prior to bidding, the bidder made adequate good faith efforts to do so.

If the DVBE information is not submitted with the bid, the apparent successful bidder (low bidder), the second low bidder and the third low bidder shall submit the DVBE information to the Department of Transportation, 1120 N Street, Room 0200, MS #26, Sacramento, California 95814 so the information is received by the Department no later than 4:00 p.m. on the fourth day, not including Saturdays, Sundays and legal holidays, following bid opening. DVBE information sent by U.S. Postal Service certified mail with return receipt and certificate of mailing and mailed on or before the third day, not

including Saturdays, Sundays and legal holidays, following bid opening will be accepted even if it is received after the fourth day following bid opening. Failure to submit the required DVBE information by the time specified will be grounds for finding the bid or proposal nonresponsive. Other bidders need not submit DVBE information unless requested to do so by the Department.

The bidder's DVBE information shall establish that good faith efforts to meet the DVBE goal have been made. To establish good faith efforts, the bidder shall demonstrate that the goal will be met or that, prior to bidding, adequate good faith efforts to meet the goal were made.

Bidders are cautioned that even though their submittal indicates they will meet the stated DVBE goal, their submittal should also include their adequate good faith efforts information along with their DVBE goal information to protect their eligibility for award of the contract in the event the Department, in its review, finds that the goal has not been met.

The bidder's DVBE information shall include the names of DVBE firms that will participate, with a complete description of work or supplies to be provided by each, the dollar value of each DVBE transaction, and a written confirmation from the DVBE that it is participating in the contract. A copy of the DVBE's quote will serve as written confirmation that the DVBE is participating in the contract. When 100 percent of a contract item of work is not to be performed or furnished by a DVBE, a description of the exact portion of that work to be performed or furnished by that DVBE shall be included in the DVBE information, including the planned location of that work. The work that a DVBE prime contractor has committed to performing with its own forces as well as the work that it has committed to be performed by DVBE subcontractors, suppliers and trucking companies will count toward the goal.

If credit for trucking by a DVBE trucking broker is shown on the bidder's information as 100 percent of the revenue to be paid by the broker is to be paid to DVBE truckers, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that all the trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification numbers. The roster must indicate that all revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

If credit for trucking by a trucking broker who is not a DVBE is shown in the bidder's information, a "certified roster" of the broker's trucks to be used must be included. The "certified roster" must indicate that at least 20 percent of the broker's trucks are owned by certified DVBEs and must show the DVBE truck numbers, owner's name, Public Utilities Commission Cal-T numbers, and the DVBE certification number. The roster must indicate that at least 20 percent of the revenue paid by the broker will be paid to DVBEs listed on the "certified roster".

A bidder shall be deemed to have made good faith efforts upon submittal, within time limits specified by the Department, of documentary evidence that all of the following actions were taken:

- A. Contact was made with the Office of Small Business Certification and Resources (OSBCR), Department of General Services or their web site at http://www.osmb.dgs.ca.gov/ to identify Disabled Veteran Business Enterprises.
- B. Advertising was published in trade media and media focusing on Disabled Veteran Business Enterprises, unless time limits imposed by the Department do not permit that advertising.
- C. Invitations to bid were submitted to potential Disabled Veteran Business Enterprise contractors.
- D. Available Disabled Veteran Business Enterprises were considered.

2-1.05 SMALL BUSINESS PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

Attention is also directed to the Small Business Procurement and Contract Act, Government Code Section 14835, et seq and Title 2, California Code of Regulations, Section 1896, et seq.

Bidders who wish to be classified as a Small Business under the provisions of those laws and regulations, shall be certified as Small Business by the Department of General Services, Office of Small Business Certification and Resources, 1531 "I" Street, Second Floor, Sacramento, CA 95814.

To request Small Business Preference, bidders shall fill out and sign the Request for Small Business Preference form in the Proposal and shall attach a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form. The bidder's signature on the Request for Small Business Preference certifies, under penalty of perjury, that the bidder is certified as Small Business at the time of bid opening and further certifies, under penalty of perjury, that under the following conditions, at least 50 percent of the subcontractors to be utilized on the project are either certified Small Business or have applied for Small Business certification by bid opening date and are subsequently granted Small Business certification.

The conditions requiring the aforementioned 50 percent level of subcontracting by Small Business subcontractors apply if:

- A. The lowest responsible bid for the project exceeds \$100,000; and
- B. The project work to be performed requires a Class A or a Class B contractor's license; and
- C. Two or more subcontractors will be used.

If the above conditions apply and Small Business Preference is granted in the award of the contract, the 50 percent Small Business subcontractor utilization level shall be maintained throughout the life of the contract.

2-1.06 CALIFORNIA COMPANY PREFERENCE

Attention is directed to "Award and Execution of Contract" of these special provisions.

In conformance with the requirements of Section 6107 of the Public Contract Code, a "California company" will be granted a reciprocal preference for bid comparison purposes as against a nonresident contractor from any state that gives or requires a preference to be given contractors from that state on its public entity construction contracts.

A "California company" means a sole proprietorship, partnership, joint venture, corporation, or other business entity that was a licensed California contractor on the date when bids for the public contract were opened and meets one of the following:

- A. Has its principal place of business in California.
- B. Has its principal place of business in a state in which there is no local contractor preference on construction contracts.
- C. Has its principal place of business in a state in which there is a local contractor construction preference and the contractor has paid not less than \$5000 in sales or use taxes to California for construction related activity for each of the five years immediately preceding the submission of the bid.

To carry out the "California company" reciprocal preference requirements of Section 6107 of the Public Contract Code, all bidders shall fill out and sign the California Company Preference form in the Proposal. The bidder's signature on the California Company Preference form certifies, under penalty of perjury, that the bidder is or is not a "California company" and if not, the amount of the preference applied by the state of the nonresident Contractor.

A nonresident Contractor shall disclose any and all bid preferences provided to the nonresident Contractor by the state or country in which the nonresident Contractor has its principal place of business.

Proposals without the California Company Preference form filled out and signed may be rejected.

SECTION 3. AWARD AND EXECUTION OF CONTRACT

The bidder's attention is directed to the provisions in Section 3, "Award and Execution of Contract," of the Standard Specifications and these special provisions for the requirements and conditions concerning award and execution of contract.

The award of the contract, if it be awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed and who has met the goal for DVBE participation or has demonstrated, to the satisfaction of the Department, adequate good faith efforts to do so. Meeting the goal for DVBE participation or demonstrating, to the satisfaction of the Department, adequate good faith efforts to do so is a condition for being eligible for award of contract.

A "Payee Data Record" form will be included in the contract documents to be executed by the successful bidder. The purpose of the form is to facilitate the collection of taxpayer identification data. The form shall be completed and returned to the Department by the successful bidder with the executed contract and contract bonds. For the purposes of the form, payee shall be deemed to mean the successful bidder. The form is not to be completed for subcontractors or suppliers. Failure to complete and return the "Payee Data Record" form to the Department as provided herein will result in the retention of 20 percent of payments due the contractor and penalties of up to \$20,000. This retention of payments for failure to complete the "Payee Data Record" form is in addition to any other retention of payments due the Contractor.

Attention is also directed to "Small Business Preference" of these special provisions. Any bidder who is certified as a Small Business by the Department of General Services, Office of Small Business Certification and Resources will be allowed a preference in the award of this contract, if it be awarded, under the following conditions:

- A. The apparent low bidder is not certified as a Small Business, or has not filled out and signed the Request for Small Business Preference included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form; and
- B. The bidder filled out and signed the Request for Small Business Preference form included with the bid documents and attached a copy of their Office of Small Business Certification and Resources (OSBCR) small business certification letter to the form.

The small business preference will be a reduction in the bid submitted by the small business contractor, for bid comparison purposes, by an amount equal to 5 percent of the amount bid by the apparent low bidder, the amount not to exceed \$50,000. If this reduction results in the small business contractor becoming the low bidder, then the contract will be awarded to the small business contractor on the basis of the actual bid of the small business contractor notwithstanding the reduced bid price used for bid comparison purposes.

Attention is also directed to "California Company Preference" of these special provisions.

The amount of the California company reciprocal preference shall be equal to the amount of the preference applied by the state of the nonresident contractor with the lowest responsive bid, except where the "California company" is eligible for a California Small Business Preference, in which case the preference applied shall be the greater of the two, but not both.

If the bidder submitting the lowest responsive bid is not a "California company" and with the benefit of the reciprocal preference, a "California company's" responsive bid is equal to or less than the original lowest responsive bid, the "California company" will be awarded the contract at its submitted bid price except as provided below.

Small business bidders shall have precedence over nonsmall business bidders in that the application of the "California company" preference for which nonsmall business bidders may be eligible shall not result in the denial of the award to a small business bidder.

SECTION 4. BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES

Attention is directed to the provisions in Section 8-1.03, "Beginning of Work," in Section 8-1.06, "Time of Completion," and in Section 8-1.07, "Liquidated Damages," of the Standard Specifications and these special provisions.

The Contractor shall begin work within 15 calendar days after the contract has been approved by the Attorney General or the attorney appointed and authorized to represent the Department of Transportation.

This work shall be diligently prosecuted to completion before the expiration of **140 WORKING DAYS** beginning on the fifteenth calendar day after approval of the contract.

The Contractor shall pay to the State of California the sum of \$ per day, for each and every calendar day's delay in finishing the work in excess of the number of working days prescribed above.

SECTION 5. GENERAL SECTION 5-1. MISCELLANEOUS

5-1.01 PLANS AND WORKING DRAWINGS

When the specifications require working drawings to be submitted to the Division of Structure Design, the drawings shall be submitted to: Division of Structure Design, Documents Unit, Mail Station 9, 1801 30th Street, Sacramento, CA 95816, Telephone 916 227-8252.

5-1.011 EXAMINATION OF PLANS, SPECIFICATIONS, CONTRACT, AND SITE OF WORK

The second paragraph of Section 2-1.03, "Examination of Plans, Specifications, Contract, and Site of Work," of the Standard Specifications is amended to read:

• Where the Department has made investigations of site conditions, including subsurface conditions in areas where work is to be performed under the contract, or in other areas, some of which may constitute possible local material sources, bidders or Contractors may, upon written request, inspect the records of the Department as to those investigations subject to and upon the conditions hereinafter set forth.

Attention is directed to "Differing Site Conditions" of these special provisions regarding physical conditions at the site which may differ from those indicated in "Materials Information," log of test borings or other geotechnical information obtained by the Department's investigation of site conditions.

5-1.012 DIFFERING SITE CONDITIONS

Attention is directed to Section 5-1.116, "Differing Site Conditions," of the Standard Specifications.

During the progress of the work, if subsurface or latent conditions are encountered at the site differing materially from those indicated in the "Materials Information," log of test borings, other geotechnical data obtained by the Department's investigation of subsurface conditions, or an examination of the conditions above ground at the site, the party discovering those conditions shall promptly notify the other party in writing of the specific differing conditions before they are disturbed and before the affected work is performed.

The Contractor will be allowed 15 days from the notification of the Engineer's determination of whether or not an adjustment of the contract is warranted, in which to file a notice of potential claim in conformance with the provisions of Section 9-1.04, "Notice of Potential Claim," of the Standard Specifications and as specified herein; otherwise the decision of the Engineer shall be deemed to have been accepted by the Contractor as correct. The notice of potential claim shall set forth in what respects the Contractor's position differs from the Engineer's determination and provide any additional information obtained by the Contractor, including but not limited to additional geotechnical data. The notice of potential claim shall be accompanied by the Contractor's certification that the following were made in preparation of the bid: a review of the contract, a review of the "Materials Information," a review of the log of test borings and other records of geotechnical data to the extent they were made available to bidders prior to the opening of bids, and an examination of the conditions above ground at the site. Supplementary information, obtained by the Contractor subsequent to the filing of the notice of potential claim, shall be submitted to the Engineer in an expeditious manner.

5-1.015 LABORATORY

When a reference is made in the specifications to the "Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations of the Department of Transportation, or established laboratories of the various Districts of the Department, or other laboratories authorized by the Department to test materials and work involved in the contract. When a reference is made in the specifications to the "Transportation Laboratory," the reference shall mean the Division of Materials Engineering and Testing Services and the Division of Structural Foundations, located at 5900 Folsom Boulevard, Sacramento, CA 95819, Telephone (916) 227-7000.

5-1.017 CONTRACT BONDS

Attention is directed to Section 3-1.02, "Contract Bonds," of the Standard Specifications and these special provisions.

The payment bond shall be in a sum not less than one hundred percent of the total amount payable by the terms of the contract.

5-1.018 EXCAVATION SAFETY PLANS

Section 5-1.02A, "Trench Excavation Safety Plans," of the Standard Specifications is amended to read:

5-1.02A Excavation Safety Plans

- The Construction Safety Orders of the Division of Occupational Safety and Health shall apply to all excavations. For all excavations 1.5 m or more in depth, the Contractor shall submit to the Engineer a detailed plan showing the design and details of the protective systems to be provided for worker protection from the hazard of caving ground during excavation. The detailed plan shall include any tabulated data and any design calculations used in the preparation of the plan. Excavation shall not begin until the detailed plan has been reviewed and approved by the Engineer.
- Detailed plans of protective systems for which the Construction Safety Orders require design by a registered professional engineer shall be prepared and signed by an engineer who is registered as a Civil Engineer in the State of California, and shall include the soil classification, soil properties, soil design calculations that demonstrate adequate stability of the protective system, and any other design calculations used in the preparation of the plan.
- No plan shall allow the use of a protective system less effective than that required by the Construction Safety Orders.

- If the detailed plan includes designs of protective systems developed only from the allowable configurations and slopes, or Appendices, contained in the Construction Safety Orders, the plan shall be submitted at least 5 days before the Contractor intends to begin excavation. If the detailed plan includes designs of protective systems developed from tabulated data, or designs for which design by a registered professional engineer is required, the plan shall be submitted at least 3 weeks before the Contractor intends to begin excavation.
- Attention is directed to Section 7-1.01E, "Trench Safety."

The third paragraph of Section 19-1.02, "Preservation of Property," of the Standard Specifications is amended to read:

• In addition to the provisions in Sections 5-1.02, "Plans and Working Drawings," and 5-1.02A, "Excavation Safety Plans," detailed plans of the protective systems for excavations on or affecting railroad property will be reviewed for adequacy of protection provided for railroad facilities, property, and traffic. These plans shall be submitted at least 9 weeks before the Contractor intends to begin excavation requiring the protective systems. Approval by the Engineer of the detailed plans for the protective systems will be contingent upon the plans being satisfactory to the railroad company involved.

5-1.019 COST REDUCTION INCENTIVE

Attention is directed to Section 5-1.14, "Cost Reduction Incentive," of the Standard Specifications.

Prior to preparing a cost reduction proposal, the Contractor shall request a meeting with the Engineer to discuss the proposal in concept and to determine the merit of the cost reduction proposal. Items of discussion will also include permit issues, impact on other projects, impact on the project schedule, peer reviews, and review times required by the Department and other agencies.

5-1.02 LABOR NONDISCRIMINATION

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations.

NOTICE OF REQUIREMENT FOR NONDISCRIMINATION PROGRAM

(GOV. CODE, SECTION 12990)

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all nonexempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5000 or more.

5-1.03 INTEREST ON PAYMENTS

Interest shall be payable on progress payments, payments after acceptance, final payments, extra work payments, and claim payments as follows:

- A. Unpaid progress payments, payment after acceptance, and final payments shall begin to accrue interest 30 days after the Engineer prepares the payment estimate.
- B. Unpaid extra work bills shall begin to accrue interest 30 days after preparation of the first pay estimate following receipt of a properly submitted and undisputed extra work bill. To be properly submitted, the bill must be submitted within 7 days of the performance of the extra work and in conformance with the provisions in Section 9-1.03C, "Records," and Section 9-1.06, "Partial Payments," of the Standard Specifications. An undisputed extra work bill not submitted within 7 days of performance of the extra work will begin to accrue interest 30 days after the preparation of the second pay estimate following submittal of the bill.
- C. The rate of interest payable for unpaid progress payments, payments after acceptance, final payments, and extra work payments shall be 10 percent per annum.
- D. The rate of interest payable on a claim, protest or dispute ultimately allowed under this contract shall be 6 percent per annum. Interest shall begin to accrue 61 days after the Contractor submits to the Engineer information in sufficient detail to enable the Engineer to ascertain the basis and amount of said claim, protest or dispute.

The rate of interest payable on any award in arbitration shall be 6 percent per annum if allowed under the provisions of Civil Code Section 3289.

5-1.031 FINAL PAYMENT AND CLAIMS

Attention is directed to Section 9-1.07B, "Final Payment and Claims," of the Standard Specifications.

If the Contractor files a timely written statement of claims in response to the proposed final estimate, the District that administers the contract will submit a claim position letter to the Contractor by hand delivery or deposit in the U.S. mail within 135 days of acceptance of the contract. The claim position letter will delineate the District's position on the Contractor's claims. If the Contractor disagrees with the claim position letter, the Contractor shall submit a written notification of its disagreement to be received by the District not later than 15 days after the Contractor's receipt of the claim position letter. The written notification of disagreement shall set forth the basis for the Contractor's disagreement and be submitted to the office designated in the claim position letter. The Contractor's failure to provide a timely, written notification of disagreement shall constitute the Contractor's acceptance and agreement with the determinations provided in the claim position letter and with final payment pursuant to the claim position letter.

If the Contractor files a timely notification of disagreement with the District claim position letter, the board of review designated by the District Director to review claims that remain in dispute will meet with the Contractor within 45 days after receipt by the District of the notification of disagreement. Attendance by the Contractor at the board of review meeting shall be mandatory.

If the District fails to submit a claim position letter to the Contractor within 135 days after the acceptance of the contract and the Contractor has claims that remain in dispute, the Contractor may request a meeting with the board of review designated by the District Director to review claims that remain in dispute. The Contractor's request for a meeting shall identify the claims that remain in dispute. If the Contractor files a request for a meeting, the board of review will meet with the Contractor within 45 days after the District receives the request for the meeting. Attendance by the Contractor at the District Director's board of review meeting shall be mandatory.

Failure of the Contractor to file a timely written statement of claims in response to the proposed final estimate, or to file a timely notification of disagreement with the District claim position letter, or to attend the District Director's board of review meeting shall constitute a failure to pursue diligently and exhaust the administrative procedures in the contract and shall be a bar to arbitration in conformance with the requirements in Section 10240.2 of the California Public Contract Code.

5-1.04 PUBLIC SAFETY

The Contractor shall provide for the safety of traffic and the public in conformance with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications and these special provisions.

The Contractor shall install temporary railing (Type K) between a lane open to public traffic and an excavation, obstacle or storage area when the following conditions exist:

- A. Excavations.—The near edge of the excavation is 3.6 m or less from the edge of the lane, except:
 - 1. Excavations covered with sheet steel or concrete covers of adequate thickness to prevent accidental entry by traffic or the public.
 - 2. Excavations less than 0.3-m deep.
 - 3. Trenches less than 0.3-m wide for irrigation pipe or electrical conduit, or excavations less than 0.3-m in diameter.
 - 4. Excavations parallel to the lane for the purpose of pavement widening or reconstruction.
 - 5. Excavations in side slopes, where the slope is steeper than 1:4 (vertical:horizontal).
 - 6. Excavations protected by existing barrier or railing.
- B. Temporarily Unprotected Permanent Obstacles.—The work includes the installation of a fixed obstacle together with a protective system, such as a sign structure together with protective railing, and the Contractor elects to install the obstacle prior to installing the protective system; or the Contractor, for the Contractor's convenience and with permission of the Engineer, removes a portion of an existing protective railing at an obstacle and does not replace such railing complete in place during the same day.
- C. Storage Areas.—Material or equipment is stored within 3.6 m of the lane and the storage is not otherwise prohibited by the provisions of the Standard Specifications and these special provisions.

The approach end of temporary railing (Type K), installed in conformance with the provisions in this section "Public Safety" and in Section 7-1.09, "Public Safety," of the Standard Specifications, shall be offset a minimum of 4.6 m from the edge of the traffic lane open to public traffic. The temporary railing shall be installed on a skew toward the edge of the traffic lane of not more than 0.3-m transversely to 3 m longitudinally with respect to the edge of the traffic lane. If the 4.6-m minimum offset cannot be achieved, the temporary railing shall be installed on the 10 to 1 skew to obtain the maximum available offset between the approach end of the railing and the edge of the traffic lane, and an array of temporary crash cushion modules shall be installed at the approach end of the temporary railing.

Temporary railing (Type K) shall conform to the provisions in Section 12-3.08, "Temporary Railing (Type K)," of the Standard Specifications. Temporary railing (Type K), conforming to the details shown on 1999 Standard Plan T3, may be used. Temporary railing (Type K) fabricated prior to January 1, 1993, and conforming to 1988 Standard Plan B11-30 may be used, provided the fabrication date is printed on the required Certificate of Compliance.

Temporary crash cushion modules shall conform to the provisions in "Temporary Crash Cushion Module" of these special provisions.

Except for installing, maintaining and removing traffic control devices, whenever work is performed or equipment is operated in the following work areas, the Contractor shall close the adjacent traffic lane unless otherwise provided in the Standard Specifications and these special provisions:

Approach Speed of Public Traffic (Posted Limit)	Work Areas
(Kilometers Per Hour)	
Over 72 (45 Miles Per Hour)	Within 1.8 m of a traffic lane but not on a traffic lane
56 to 72 (35 to 45 Miles Per Hour)	Within 0.9-m of a traffic lane but not on a traffic lane

The lane closure provisions of this section shall not apply if the work area is protected by permanent or temporary railing or barrier.

When traffic cones or delineators are used to delineate a temporary edge of a traffic lane, the line of cones or delineators shall be considered to be the edge of the traffic lane, however, the Contractor shall not reduce the width of an existing lane to less than 3 m without written approval from the Engineer.

When work is not in progress on a trench or other excavation that required closure of an adjacent lane, the traffic cones or portable delineators used for the lane closure shall be placed off of and adjacent to the edge of the traveled way. The spacing of the cones or delineators shall be not more than the spacing used for the lane closure.

Suspended loads or equipment shall not be moved nor positioned over public traffic or pedestrians.

Full compensation for conforming to the provisions in this section "Public Safety," including furnishing and installing temporary railing (Type K) and temporary crash cushion modules, shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.05 SURFACE MINING AND RECLAMATION ACT

Attention is directed to the Surface Mining and Reclamation Act of 1975, commencing in Public Resources Code, Mining and Geology, Section 2710, which establishes regulations pertinent to surface mining operations, and to California Public Contract Code Section 10295.5.

Material from mining operations furnished for this project shall only come from permitted sites in compliance with California Public Contract Code Section 10295.5.

The requirements of this section shall apply to materials furnished for the project, except for acquisition of materials in conformance with the provisions in Section 4-1.05, "Use of Materials Found on the Work," of the Standard Specifications.

5-1.06 REMOVAL OF ASBESTOS AND HAZARDOUS SUBSTANCES

When the presence of asbestos or hazardous substances are not shown on the plans or indicated in the specifications and the Contractor encounters materials which the Contractor reasonably believes to be asbestos or a hazardous substance as defined in Section 25914.1 of the Health and Safety Code, and the asbestos or hazardous substance has not been rendered harmless, the Contractor may continue work in unaffected areas reasonably believed to be safe. The Contractor shall immediately cease work in the affected area and report the condition to the Engineer in writing.

In conformance with Section 25914.1 of the Health and Safety Code, removal of asbestos or hazardous substances including exploratory work to identify and determine the extent of the asbestos or hazardous substance will be performed by separate contract.

If delay of work in the area delays the current controlling operation, the delay will be considered a right of way delay and the Contractor will be compensated for the delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

5-1.07 YEAR 2000 COMPLIANCE

This contract is subject to Year 2000 Compliance for automated devices in the State of California.

Year 2000 compliance for automated devices in the State of California is achieved when embedded functions have or create no logical or mathematical inconsistencies when dealing with dates prior to and beyond 1999. The year 2000 is recognized and processed as a leap year. The product shall operate accurately in the manner in which the product was intended for date operation without requiring manual intervention.

The Contractor shall provide the Engineer a Certificate of Compliance from the manufacturer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for all automated devices furnished for the project.

5-1.08 SUBCONTRACTOR AND DVBE RECORDS

The Contractor shall maintain records of all subcontracts entered into with certified DVBE subcontractors and records of materials purchased from certified DVBE suppliers. The records shall show the name and business address of each DVBE subcontractor or vendor and the total dollar amount actually paid each DVBE subcontractor or vendor.

Upon completion of the contract, a summary of these records shall be prepared on Form CEM-2402 (S) and certified correct by the Contractor or the Contractor's authorized representative, and shall be furnished to the Engineer.

5-1.086 PERFORMANCE OF DVBE SUBCONTRACTORS AND SUPPLIERS

The DVBEs listed by the Contractor in response to the provisions in Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions, which are determined by the Department to be certified DVBEs, shall perform the work and supply the materials for which they are listed, unless the Contractor has received prior written authorization to perform the work with other forces or to obtain the materials from other sources.

Authorization to utilize other forces or sources of materials may be requested for the following reasons:

- A. The listed DVBE, after having had a reasonable opportunity to do so, fails or refuses to execute a written contract, when the written contract, based upon the general terms, conditions, plans and specifications for the project, or on the terms of the subcontractor's or supplier's written bid, is presented by the Contractor.
- B. The listed DVBE becomes bankrupt or insolvent.
- C. The listed DVBE fails or refuses to perform the subcontract or furnish the listed materials.
- D. The Contractor stipulated that a bond was a condition of executing a subcontract and the listed DVBE subcontractor fails or refuses to meet the bond requirements of the Contractor.
- E. The work performed by the listed subcontractor is substantially unsatisfactory and is not in substantial conformance with the plans and specifications or the subcontractor is substantially delaying or disrupting the progress of the work.
- F. The listed DVBE subcontractor is not licensed pursuant to the Contractor's License Law.
- G. It would be in the best interest of the State.

The Contractor shall not be entitled to payment for the work or material unless it is performed or supplied by the listed DVBE or by other forces (including those of the Contractor) pursuant to prior written authorization of the Engineer.

5-1.09 SUBCONTRACTING

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," of the Standard Specifications, Section 2, "Proposal Requirements and Conditions," Section 2-1.04, "Submission of DVBE Information," and Section 3, "Award and Execution of Contract," of these special provisions and these special provisions.

Pursuant to the provisions in Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. This list of debarred contractors is available from the Department of Industrial Relations web site at:

http://www.dir.ca.gov/DLSE/Debar.html.

The DVBE information furnished under Section 3-1.01A, "DVBE Information," of these special provisions is in addition to the subcontractor information required to be furnished in Section 8-1.01, "Subcontracting," and Section 2-1.054, "Required Listing of Proposed Subcontractors," of the Standard Specifications.

Section 10115 of the Public Contract Code requires the Department to implement provisions to establish a goal for Disabled Veteran Business Enterprise (DVBE) participation in highway contracts that are State funded. As a part of this requirement:

- A. No substitution of a DVBE subcontractor shall be made at any time without the written consent of the Department, and
- B. If a DVBE subcontractor is unable to perform successfully and is to be replaced, the Contractor shall make good faith efforts to replace the original DVBE subcontractor with another DVBE subcontractor.

The provisions in Section 2-1.02, "Disabled Veteran Business Enterprise (DVBE)," of these special provisions that DVBEs shall be certified on the date bids are opened does not apply to DVBE substitutions after award of the contract.

5-1.10 PROMPT PROGRESS PAYMENT TO SUBCONTRACTORS

Attention is directed to the provisions in Sections 10262 and 10262.5 of the Public Contract Code and Section 7108.5 of the Business and Professions Code concerning prompt payment to subcontractors.

5-1.11 AREAS FOR CONTRACTOR'S USE

Attention is directed to the provisions in Section 7-1.19, "Rights in Land and Improvements," of the Standard Specifications and these special provisions.

The highway right of way shall be used only for purposes that are necessary to perform the required work. The Contractor shall not occupy the right of way, or allow others to occupy the right of way, for purposes which are not necessary to perform the required work.

No State-owned parcels adjacent to the right of way are available for the exclusive use of the Contractor within the contract limits. The Contractor shall secure, at the Contractor's own expense, areas required for plant sites, storage of equipment or materials, or for other purposes.

5-1.12 PAYMENTS

Attention is directed to Sections 9-1.06, "Partial Payments," and 9-1.07, "Payment After Acceptance," of the Standard Specifications and these special provisions.

For the purpose of making partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications, the amount set forth for the contract items of work hereinafter listed shall be deemed to be the maximum value of the contract item of work which will be recognized for progress payment purposes:

A. Bridge Removal (Portion) \$12,000.00

After acceptance of the contract pursuant to the provisions in Section 7-1.17, "Acceptance of Contract," of the Standard Specifications, the amount, if any, payable for a contract item of work in excess of the maximum value for progress payment purposes hereinabove listed for the item, will be included for payment in the first estimate made after acceptance of the contract.

In determining the partial payments to be made to the Contractor, only the following listed materials will be considered for inclusion in the payment as materials furnished but not incorporated in the work:

A.	
B.	
C.	
·.	

SECTION 6. (BLANK)
SECTION 7. (BLANK)
SECTION 8. MATERIALS
SECTION 8-1. MISCELLANEOUS

8-1.01 SUBSTITUTION OF NON-METRIC MATERIALS AND PRODUCTS

Only materials and products conforming to the requirements of the specifications shall be incorporated in the work. When metric materials and products are not available, and when approved by the Engineer, and at no cost to the State, materials and products in the United States Standard Measures which are of equal quality and of the required properties and characteristics for the purpose intended, may be substituted for the equivalent metric materials and products, subject to the following provisions:

- A. Materials and products shown on the plans or in the special provisions as being equivalent may be substituted for the metric materials and products specified or detailed on the plans.
- B. Before other non-metric materials and products will be considered for use, the Contractor shall furnish, at the Contractor's expense, evidence satisfactory to the Engineer that the materials and products proposed for use are equal to or better than the materials and products specified or detailed on the plans. The burden of proof as to the quality and suitability of substitutions shall be upon the Contractor and the Contractor shall furnish necessary

- information as required by the Engineer. The Engineer will be the sole judge as to the quality and suitability of the substituted materials and products and the Engineer's decision will be final.
- C. When the Contractor elects to substitute non-metric materials and products, including materials and products shown on the plans or in the special provisions as being equivalent, the list of sources of material specified in Section 6-1.01, "Source of Supply and Quality of Materials," of the Standard Specification shall include a list of substitutions to be made and contract items involved. In addition, for a change in design or details, the Contractor shall submit plans and working drawings in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The plans and working drawings shall be submitted at least 7 days before the Contractor intends to begin the work involved.

Unless otherwise specified, the following substitutions of materials and products will be allowed:

SUBSTITUTION TABLE FOR SIZES OF HIGH STRENGTH STEEL FASTENERS

ASTM Designation: A 325M

METRIC SIZE SHOWN ON THE PLANS	SIZE TO BE SUBSTITUTED
mm x thread pitch	inch
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1-1/8
M30 x 3.5	1-1/4
M36 x 4	1-1/2

SUBSTITUTION TABLE FOR PLAIN WIRE REINFORCEMENT

ASTM Designation: A 82

METRIC SIZE SHOWN ON THE PLANS	SIZE TO BE SUBSTITUTED
mm ²	inch ² x 100
MW9	W1.4
MW10	W1.6
MW13	W2.0
MW15	W2.3
MW19	W2.9
MW20	W3.1
MW22	W3.5
MW25	W3.9, except W3.5 in piles only
MW26	W4.0
MW30	W4.7
MW32	W5.0
MW35	W5.4
MW40	W6.2
MW45	W6.5
MW50	W7.8
MW55	W8.5, except W8.0 in piles only
MW60	W9.3
MW70	W10.9, except W11.0 in piles only
MW80	W12.4
MW90	W14.0
MW100	W15.5

SUBSTITUTION TABLE FOR BAR REINFORCEMENT

METRIC BAR DESIGNATION	BAR DESIGNATION
NUMBER ¹ SHOWN ON THE PLANS	NUMBER ² TO BE SUBSTITUTED
10	3
13	4
16	5
19	6
22	7
25	8
29	9
32	10
36	11
43	14
57	18

¹Bar designation numbers approximate the number of millimeters of the nominal diameter of the

No adjustment will be required in spacing or total number of reinforcing bars due to a difference in minimum yield strength between metric and non-metric bars.

SUBSTITUTION TABLE FOR SIZES OF:

(1) STEEL FASTENERS FOR GENERAL APPLICATIONS (ASTM Designation: A 307 or AASHTO Designation: M 314, Grade 36 or 55), and (2) HIGH STRENGTH STEEL FASTENERS (ASTM Designation: A 325 or A 449)

METRIC SIZE SHOWN ON THE PLANS	SIZE TO BE SUBSTITUTED
mm	inch
6 or 6.35	1/4
8 or 7.94	5/16
10 or 9.52	3/8
11 or 11.11	7/16
13 or 12.70	1/2
14 or 14.29	9/16
16 or 15.88	5/8
19 or 19.05	3/4
22 or 22.22	7/8
24, 25, or 25.40	1
29 or 28.58	1-1/8
32 or 31.75	1-1/4
35 or 34.93	1-3/8
38 or 38.10	1-1/2
44 or 44.45	1-3/4
51 or 50.80	2
57 or 57.15	2-1/4
64 or 63.50	2-1/2
70 or 69.85	2-3/4
76 or 76.20	3
83 or 82.55	3-1/4
89 or 88.90	3-1/2
95 or 95.25	3-3/4
102 or 101.60	4

²Bar numbers are based on the number of eighths of an inch included in the nominal diameter of the bars.

SUBSTITUTION TABLE FOR NOMINAL THICKNESS OF SHEET METAL

SUBSTITUTION TABLE FOR NOMINAL THICKNESS OF SHEET METAL			
UNCOATED HOT AND COLD ROLLED SHEETS		HOT-DIPPED ZINC COATED SHEETS	
1	G + GT TO TT	(GALVANIZED)	
METRIC THICKNESS	GAGE TO BE	METRIC THICKNESS	GAGE TO BE
SHOWN ON THE PLANS	SUBSTITUTED	SHOWN ON THE PLANS	SUBSTITUTED
mm	inch	mm	inch
7.94	0.3125	4.270	0.1681
6.07	0.2391	3.891	0.1532
5.69	0.2242	3.510	0.1382
5.31	0.2092	3.132	0.1233
4.94	0.1943	2.753	0.1084
4.55	0.1793	2.372	0.0934
4.18	0.1644	1.994	0.0785
3.80	0.1495	1.803	0.0710
3.42	0.1345	1.613	0.0635
3.04	0.1196	1.461	0.0575
2.66	0.1046	1.311	0.0516
2.28	0.0897	1.158	0.0456
1.90	0.0747	1.006 or 1.016	0.0396
1.71	0.0673	0.930	0.0366
1.52	0.0598	0.853	0.0336
1.37	0.0538	0.777	0.0306
1.21	0.0478	0.701	0.0276
1.06	0.0418	0.627	0.0247
0.91	0.0359	0.551	0.0217
0.84	0.0329	0.513	0.0202
0.76	0.0299	0.475	0.0187
0.68	0.0269		
0.61	0.0239		
0.53	0.0209		
0.45	0.0179		
0.42	0.0164		
0.38	0.0149		

SUBSTITUTION TABLE FOR WIRE

METRIC THICKNESS	WIRE THICKNESS	
SHOWN ON THE PLANS	TO BE SUBSTITUTED	GAGE NO.
mm	inch	
6.20	0.244	3
5.72	0.225	4
5.26	0.207	5
4.88	0.192	6
4.50	0.177	7
4.11	0.162	8
3.76	0.148	9
3.43	0.135	10
3.05	0.120	11
2.69	0.106	12
2.34	0.092	13
2.03	0.080	14
1.83	0.072	15
1.57	0.062	16
1.37	0.054	17
1.22	0.048	18
1.04	0.041	19
0.89	0.035	20

SUBSTITUTION TABLE FOR PIPE PILES

SUBSTITUTION TABLE FOR PIPE PILES		
METRIC SIZE	SIZE	
SHOWN ON THE PLANS	TO BE SUBSTITUTED	
mm x mm	inch x inch	
PP 360 x 4.55	NPS 14 x 0.179	
PP 360 x 6.35	NPS 14 x 0.250	
PP 360 x 9.53	NPS 14 x 0.375	
PP 360 x 11.12	NPS 14 x 0.438	
PP 406 x 12.70	NPS 16 x 0.500	
PP 460 x T	NPS 18 x T"	
PP 508 x T	NPS 20 x T"	
PP 559 x T	NPS 22 x T"	
PP 610 x T	NPS 24 x T"	
PP 660 x T	NPS 26 x T"	
PP 711 x T	NPS 28 x T"	
PP 762 x T	NPS 30 x T"	
PP 813 x T	NPS 32 x T"	
PP 864 x T	NPS 34 x T"	
PP 914 x T	NPS 36 x T"	
PP 965 x T	NPS 38 x T"	
PP 1016 x T	NPS 40 x T"	
PP 1067 x T	NPS 42 x T"	
PP 1118 x T	NPS 44 x T"	
PP 1219 x T	NPS 48 x T"	
PP 1524 x T	NPS 60 x T"	

The thickness in millimeters (T) represents an exact conversion of the thickness in inches (T").

SUBSTITUTION TABLE FOR STRUCTURAL TIMBER AND LUMBER

METRIC MINIMUM	METRIC MINIMUM	NOMINAL
DRESSED DRY,	DRESSED GREEN,	SIZE
SHOWN ON THE PLANS	SHOWN ON THE PLANS	TO BE SUBSTITUTED
mm x mm	mm x mm	inch x inch
19x89	20x90	1x4
38x89	40x90	2x4
64x89	65x90	3x4
89x89	90x90	4x4
140x140	143x143	6x6
140x184	143x190	6x8
184x184	190x190	8x8
235x235	241x241	10x10
286x286	292x292	12x12

SUBSTITUTION TABLE FOR NAILS AND SPIKES

METRIC COMMON NAIL,	METRIC BOX NAIL,	METRIC SPIKE,	SIZE
SHOWN ON THE PLANS	SHOWN ON THE PLANS	SHOWN ON THE	TO BE
		PLANS	SUBSTITUTED
Length, mm	Length, mm	Length, mm	Penny-weight
Diameter, mm	Diameter, mm	Diameter, mm	, ,
50.80	50.80		6d
2.87	2.51		
63.50	63.50		8d
3.33	2.87		
76.20	76.20	76.20	10d
3.76	3.25	4.88	
82.55	82.55	82.55	12d
3.76	3.25	4.88	
88.90	88.90	88.90	16d
4.11	3.43	5.26	
101.60	101.60	101.60	20d
4.88	3.76	5.72	
114.30	114.30	114.30	30d
5.26	3.76	6.20	
127.00	127.00	127.00	40d
5.72	4.11	6.68	
		139.70	50d
		7.19	
		152.40	60d
		7.19	

SUBSTITUTION TABLE FOR IRRIGATION COMPONENTS

001/11 0	INEINIO
METRIC	NOMINAL
WATER METERS, TRUCK	SIZE
LOADING STANDPIPES,	TO BE SUBSTITUTED
VALVES, BACKFLOW	
PREVENTERS, FLOW	
SENSORS, WYE	
STRAINERS, FILTER	
ASSEMBLY UNITS, PIPE	
SUPPLY LINES, AND PIPE	
IRRIGATION SUPPLY	
LINES	
SHOWN ON THE PLANS	
DIAMETER NOMINAL (DN)	
mm	inch
15	1/2
20	3/4
25	1
32	1-1/4
40	1-1/2
50	2
65	2-1/2
75	3
100	4
150	6
200	8
250	10
300	12
350	14
400	16

Unless otherwise specified, substitutions of United States Standard Measures standard structural shapes corresponding to the metric designations shown on the plans and in conformance with the requirements in ASTM Designation: A 6/A 6M, Annex 2, will be allowed.

8-1.02 PREQUALIFIED AND TESTED SIGNING AND DELINEATION MATERIALS

The Department maintains the following list of Prequalified and Tested Signing and Delineation Materials. The Engineer shall not be precluded from sampling and testing products on the list of Prequalified and Tested Signing and Delineation Materials.

The manufacturer of products on the list of Prequalified and Tested Signing and Delineation Materials shall furnish the Engineer a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each type of traffic product supplied.

For those categories of materials included in the list of Prequalified and Tested Signing and Delineation Materials, only those products shown within the listing may be used in the work. Other categories of products, not included in the list of Prequalified and Tested Signing and Delineation Materials, may be used in the work provided they conform to the requirements of the Standard Specifications.

Materials and products may be added to the list of Prequalified and Tested Signing and Delineation Materials if the manufacturer submits a New Product Information Form to the New Product Coordinator at the Transportation Laboratory. Upon a Departmental request for samples, sufficient samples shall be submitted to permit performance of required tests. Approval of materials or products will depend upon compliance with the specifications and tests the Department may elect to perform.

PAVEMENT MARKERS, PERMANENT TYPE

Retroreflective With Abrasion Resistant Surface (ARS)

- A. Apex, Model 921AR (100 mm x 100 mm)
- B. Ray-O-Lite, Model "AA" ARS (100 mm x 100 mm)
- C. Stimsonite, Models 911 (100 mm x 100 mm) and 953 (70 mm x 114 mm)
- D. 3M Series 290 (89 mm x 100 mm)

Retroreflective With Abrasion Resistant Surface (ARS)

(Used for recessed applications)

- A. Stimsonite, Model 948 (58 mm x 119 mm)
- B. Ray-O-Lite, Model 2002 (58 mm x 117 mm)
- C. Stimsonite, Model 944SB (51 mm x 100 mm)
- D. Ray-O-Lite, Model 2004 ARS (51 mm x 100 mm)*

 *For use only in 114 mm wide (older) recessed slots

Non-Reflective For Use With Epoxy Adhesive, 100 mm Round

- A. Apex Universal (Ceramic)
- B. Highway Ceramics, Inc. (Ceramic)

Non-Reflective For Use With Bitumen Adhesive, 100 mm Round

- A. Alpine Products, "D-Dot" and "ANR" (ABS)
- B. Apex Universal (Ceramic)
- C. Apex Universal, Models 929 (ABS) and 929PP (Polypropylene)
- D. Elgin Molded Plastics, "Empco-Lite" Model 900 (ABS)
- E. Highway Ceramics, Inc. (Ceramic)
- F. Hi-Way Safety, Inc., Models P20-2000W and 2001Y (ABS)
- G. Interstate Sales, "Diamond Back" (ABS) and (Polypropylene)
- H. Novabrite Models Adot-w (White) Adot-y (Yellow), (ABS)
- I. Road Creations, Model RCB4NR (Acrylic)
- J. Zumar Industries, "Titan TM40A" (ABS)

PAVEMENT MARKERS, TEMPORARY TYPE

Temporary Markers For Long Term Day/Night Use (6 months or less)

- A. Apex Universal, Model 924 (100 mm x 100 mm)
- B. Elgin Molded Plastics, "Empco-Lite" Model 901 (100 mm x 100 mm)
- C. Road Creations, Model R41C (100 mm x 100 mm)
- D. Vega Molded Products "Temporary Road Marker" (75 mm x 100 mm)

Temporary Markers For Short Term Day/Night Use (14 days or less)

(For seal coat or chip seal applications, clear protective covers are required)

- A. Apex Universal, Model 932
- B. Bunzl (formerly Davidson Plastics, Models) T.O.M., T.R.P.M., and "HH" (High Heat)
- C. Hi-Way Safety, Inc., Model 1280/1281

STRIPING AND PAVEMENT MARKING MATERIAL

Permanent Traffic Striping and Pavement Marking Tape

- A. Advanced Traffic Marking, Series 300 and 400
- B. Brite-Line, Series 1000
- C. Brite-Line, "DeltaLine XRP"
- D. Swarco Industries, "Director 35" (For transverse application only)
- E. Swarco Industries, "Director 60"
- F. 3M, "Stamark" Series 380 and 5730
- G. 3M, "Stamark" Series 420 (For transverse application only)

Temporary (Removable) Striping and Pavement Marking Tape (6 months or less)

- A. Advanced Traffic Marking, Series 200
- B. Brite-Line, Series 100
- C. P.B. Laminations, Aztec, Grade 102
- D. Swarco Industries, "Director-2"
- Trelleborg Industri, R140 Series
- 3M, Series 620 and Series A750
- 3M, Series A145, Removable Black Line Mask (Black Tape: for use only on Asphalt Concrete Surfaces)
- H. Advanced Traffic Marking Black "Hide-A-Line"

(Black Tape: for use only on Asphalt Concrete Surfaces)

- I. Brite-Line "BTR" Black Removable Tape
 - (Black Tape: for use only on Asphalt Concrete Surfaces)
- J. Trelleborg Industri, RB-140
 - (Black Tape: for use only on Asphalt Concrete Surfaces)

Preformed Thermoplastic (Heated in place)

- A. Flint Trading, "Premark" and "Premark 20/20 Flex"
- B. Avery Dennison, "Hotape"

Removable Traffic Paint

A. Belpro, Series 250/252 and No. 93 Remover

Ceramic Surfacing Laminate, 150 mm x 150 mm

A. Safeline Industries/Highway Ceramics, Inc.

CLASS 1 DELINEATORS

One Piece Driveable Flexible Type, 1700 mm

- A. Carsonite, Curve-Flex CFRM-400
- B. Carsonite, Roadmarker CRM-375
- C. Bunzl (Formerly Davidson Plastics), "Flexi-Guide Models 400 and 566"
- D. FlexStake, Model 654 TM
- E. GreenLine Models HWD1-66 and CGD1-66
- F. J. Miller Industries, Model JMI-375 (with soil anchor)

Special Use Flexible Type, 1700 mm

- A. Carsonite, "Survivor" (with 450 mm U-Channel base)
- B. FlexStake, Model 604
- C. GreenLine Models HWD and CGD (with 450 mm U-Channel base)
- D. Safe-Hit with 200 mm pavement anchor (SH248-GP1)
- E. Safe-Hit with 380 mm soil anchor (SH248-GP2) and with 450 mm soil anchor (SH248-GP3)

Surface Mount Flexible Type, 1200 mm

- A. Bent Manufacturing Company, Masterflex Model MF-180EX-48
- B. Carsonite, "Super Duck II"
- C. FlexStake, Surface Mount, Models 704 and 754 TM

CHANNELIZERS

Surface Mount Type, 900 mm

- A. Bent Manufacturing Company, Masterflex Models MF-360-36 (Round) and MF-180-36 (Flat)
- B. Carsonite, "Super Duck" (Flat SDF-436, Round SDR-336)
- C. Carsonite, "Super Duck II" Model SDCF203601MB "The Channelizer"
- D. Bunzl (Formerly Davidson Plastics), Flex-Guide Models FG300LD and FG300UR
- E. FlexStake, Surface Mount, Models 703 and 753 TM
- F. GreenLine, Model SMD-36
- G. Hi-Way Safety, Inc. "Channel Guide Channelizer" Model CGC36
- H. The Line Connection, "Dura-Post" Model DP36-3 (Permanent)
- I. The Line Connection, "Dura-Post" Model DP36-3C (Temporary)
- J. Repo, Models 300 and 400
- K. Safe-Hit, Guide Post, Model SH236SMA

CONICAL DELINEATORS, 1070 mm

(For 700 mm Traffic Cones, see Standard Specifications)

- A. Bent Manufacturing Company "T-Top"
- B. Plastic Safety Systems "Navigator-42"
- C. Radiator Specialty Company "Enforcer"
- D. Roadmaker Company "Stacker"
- E. TrafFix Devices "Grabber"

OBJECT MARKERS

Type "K", 450 mm

- A. Carsonite, Model SMD 615
- B. FlexStake, Model 701 KM
- C. Repo, Models 300 and 400
- D. Safe-Hit, Model SH718SMA
- E. The Line Connection, Model DP21-4K

Type "K-4" / "Q" Object Markers, 600 mm

- A. Bent Manufacturing "Masterflex" Model MF-360-24
- B. Carsonite, Super Duck II
- C. FlexStake, Model 701KM
- D. Repo, Models 300 and 400
- E. Safe-Hit, Models SH8 24SMA_WA and SH8 24GP3_WA
- F. The Line Connection, Model DP21-4Q

TEMPORARY RAILING (TYPE K) REFLECTORS AND CONCRETE BARRIER MARKERS

Impactable Type

- A. ARTUK, "FB"
- B. Bunzl (Formerly Davidson Plastics), Model PCBM-12
- C. Duraflex Corp., "Flexx 2020" and "Electriflexx"
- D. Hi-Way Safety, Inc., Model GMKRM100

Non-Impactable Type

- A. ARTUK, JD Series
- B. Stimsonite, Model 967 (with 83 mm Acrylic cube corner reflector)
- C. Stimsonite, Model 967LS
- D. Vega Molded Products, Models GBM and JD

THRIE BEAM BARRIER MARKERS

(For use to the left of traffic)

- A. Duraflex Corp., "Railrider"
- B. Bunzl (Formerly Davidson Plastics), "Mini" (75 mm x 254 mm)

CONCRETE BARRIER DELINEATORS, 400 mm

(For use to the right of traffic. When mounted on top of barrier, place top of reflective element at 1200 mm)

- A. Bunzl (Formerly Davidson Plastics), Model PCBM T-16
- B. Safe-Hit, Model SH216RBM
- C. Sun-Lab Technology, "Safety Guide Light, Model TM," 130 mm x 130 mm x 80 mm

CONCRETE BARRIER-MOUNTED MINI-DRUM (260 mm x 360 mm x 570 mm)

A. Stinson Equipment Company "SaddleMarker"

SOUND WALL DELINEATOR

(Applied vertically. Place top of 75 mm x 300 mm reflective element at 1200 mm above roadway)

- A. Bunzl (Formerly Davidson Plastics), PCBM S-36
- B. Sun-Lab Technology, "Safety Guide Light, Model SM12," 130 mm x 130 mm x 80 mm

GUARD RAILING DELINEATOR

(Place top of reflective element at 1200 mm above plane of roadway)

Wood Post Type, 686 mm

- A. Carsonite, Model 427
- B. Bunzl (Formerly Davidson Plastics), FG 427 and FG 527
- C. FlexStake, Model 102 GR
- D. GreenLine GRD 27
- E. J.Miller Model JMI-375G
- F. Safe-Hit, Model SH227GRD

Steel Post Type

A. Carsonite, Model CFGR-327 with CFGRBK300 Mounting Bracket

RETROREFLECTIVE SHEETING

Channelizers, Barrier Markers, and Delineators

- A. 3M, High Intensity
- B. Reflexite, PC-1000 Metalized Polycarbonate
- C. Reflexite, AC-1000 Acrylic
- D. Reflexite, AP-1000 Metalized Polyester
- E. Reflexite, Conformalight, AR-1000 Abrasion Resistant Coating
- F. Avery Dennison T-6500 Series (Formerly Stimsonite, Series 6200) (For rigid substrate devices only)
- G. Nippon Carbide, Flexible Ultralite Grade (ULG) II

Traffic Cones, 330 mm Sleeves

A. Reflexite SB (Polyester), Vinyl or "TR" (Semi-transparent)

Traffic Cones, 100 mm and 150 mm Sleeves

- A. 3M Series 3840
- B. Reflexite Vinyl, "TR" (Semi-transparent) or "Conformalight"
- C. Nippon Carbide, Flexible Ultralite Grade (ULG) II

Barrels and Drums

- A. Reflexite, "Conformalight", "Super High Intensity" or "High Impact Drum Sheeting"
- B. 3M Series 3810
- C. Nippon Carbide, Flexible Ultralite Grade (ULG) II
- D. Avery Dennison W-6100

Barricades: Type I, Engineer Grade

- A. American Decal, Adcolite
- B. Avery Dennison, T-1500 and T-1600 series
- C. 3M, Engineer Grade, Series 3170

Barricades: Type II, Super Engineer Grade

- A. Avery Dennison, T-2500 Series
- B. Kiwalite Type II
- C. Nikkalite 1800 Series

Signs: Type II, Super Engineer Grade

- A. Avery Dennison, T-2500 Series
- B. Kiwalite, Type II
- C. Nikkalite 1800 Series

Signs: Type III, High-Intensity Grade

- A. 3M Series 3800
- B. Nippon Carbide, Nikkalite Brand Ultralite Grade II

Signs: Type IV, High-Intensity Prismatic Grade

A. Avery Dennison T-6500 (Formerly Stimsonite Series 6200)

Signs: Type VII, High-Intensity Prismatic Grade

A. 3M Series 3900

Signs: Type VI, Roll-Up Signs

- A. Reflexite, Vinyl (Orange)
- B. Reflexite "SuperBright" (Fluorescent orange)
- C. Reflexite "Marathon" (Fluorescent orange)
- D. 3M Series RS34 (Orange) and RS20 (Fluorescent orange)

SPECIALTY SIGN (All Plastic)

A. All Sign Products, STOP Sign, 750 mm

SIGN SUBSTRATE FOR CONSTRUCTION AREA SIGNS

Aluminum

Fiberglass Reinforced Plastic (FRP)

- A. Sequentia, "Polyplate"
- B. Fiber-Brite

8-1.03 MISCELLANEOUS METAL

The table in the tenth paragraph of Section 75-1.02, "Miscellaneous Iron and Steel," of the Standard Specifications is amended to read:

Steel bars, plates and shapes ASTM Designation: A 36/A 36M or A 575, A 576 (AISI or M Grades 1016 through 1030 except Grade 1017) Steel fastener components for general applications: Bolts and studs ASTM Designation: A 307, Grade B, including S1 supplementary requirements Nonheaded anchor bolts ASTM Designation: A 307, Grade B, including S1 supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements ASTM Designation: A 449, Type 1 ASTM Designation: A 563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: A 325, Type 1 ASTM Designation: F 1852, Type 1 ASTM Designation: F 1852, Type 1 ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality We Zinc-coated nuts that will be tiehtened bevond snue or wrench tieht shall	Material	Specification	
Shapes			
except Grade 1017) Steel fastener components for general applications: Bolts and studs			
Steel fastener components for general applications: Bolts and studs ASTM Designation: A 307 Headed anchor bolts St supplementary requirements Nonheaded anchor bolts ASTM Designation: A 307, Grade B, including St supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements and studs, threaded rods, and nonheaded anchor bolts Nuts	snapes		
Bolts and studs Headed anchor bolts Nonheaded anchor bolts S1 supplementary requirements ASTM Designation: A 307, Grade C, including S1 supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements ASTM Designation: A 449, Type 1 ASTM Designation: A 563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: F 1852, Type 1 Nuts ASTM Designation: F 1852, Type 1 ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality Commercial quality Commercial quality	Staal factories commonants		
Headed anchor bolts Nonheaded anchor bolts Stapplementary requirements and \$1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including \$1 supplementary requirements High-strength bolts and studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: A 449, Type 1 ASTM Designation: A 563, including Appendix X1* ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 1852, Type 1 ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 1852, Type 1 ASTM Designation: F 1852, Type 1, Circular, including \$1 supplementary requirements ASTM Designation: F 959, Type 325, zinc-coated Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality, welded or extruded Cother parts for general applications	·		
Nonheaded anchor bolts Nonheaded anchor bolts Nonheaded anchor bolts ASTM Designation: A 307, Grade C, including S1 supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements ASTM Designation: A 449, Type 1 ASTM Designation: A 563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: F 1852, Type 1 Nuts ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M Washers ASTM Designation: A 240/A 240M and ANS1 B 18.22M Carbon-steel castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Commercial quality Steel pipe Commercial quality Commercial quality Commercial quality Commercial quality			
Nonheaded anchor bolts Stamplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements and studs, threaded rods, and nonheaded anchor bolts Nuts	Headed anchor bolts		
bolts S1 supplementary requirements and S1.6 of AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements High-strength bolts and studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: A 449, Type 1 Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: F 1852, Type 1 ASTM Designation: F 852, Type 1 ASTM Designation: F 853, including Appendix X1* Hardened washers ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators 2inc-coated Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M Carbon-steel castings ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality, welded or extruded Other parts for general applications	N. 1 1 1 1		
AASHTO Designation: M 314 supplementary requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements High-strength bolts and studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: A 449, Type 1 ASTM Designation: A 563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: A 563, including Appendix X1* ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M Washers ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Commercial quality Commercial quality Commercial quality			
requirements or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements ASTM Designation: A 449, Type 1 ASTM Designation: A 4563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: F 1852, Type 1 ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 1852, Type 1 ASTM Designation: F 1852, Type 1 ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements ASTM Designation: F 959, Type 325, zinc-coated Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Commercial quality Commercial quality Commercial quality Commercial quality Commercial quality	bolts		
or AASHTO Designation: M 314, Grade 36 or 55, including S1 supplementary requirements High-strength bolts and studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: A 563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts Nuts ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 1852, Type 1 Nuts ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality, welded or extruded Other parts for general applications		• 11	
S5, including S1 supplementary requirements		•	
High-strength bolts and studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: A 563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts Nuts ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 1852, Type 1 ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality, welded or extruded Other parts for general applications			
and studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: A 563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: F 1852, Type 1 Nuts ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: F 594 or F 836M ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality, welded or extruded Other parts for general applications			
rods, and nonheaded anchor bolts Nuts ASTM Designation: A 563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: F 1852, Type 1 Nuts ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension and anologicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M Washers ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications		ASTM Designation: A 449, Type 1	
anchor bolts Nuts ASTM Designation: A 563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: F 1852, Type 1 Nuts ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality Steel pipe Commercial quality, welded or extruded Commercial quality	7		
Nuts ASTM Designation: A 563, including Appendix X1* Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: F 1852, Type 1 Nuts ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Zinc-coated Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications			
Appendix X1*	anchor bolts		
Washers ASTM Designation: F 844 Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: F 1852, Type 1 Nuts ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension ASTM Designation: F 959, Type 325, zinc-coated Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications	Nuts	ASTM Designation: A 563, including	
Components of high-strength steel fastener assemblies for use in structural steel joints: Bolts		Appendix X1*	
Steel joints: Bolts	Washers	ASTM Designation: F 844	
Bolts ASTM Designation: A 325, Type 1 Tension control bolts ASTM Designation: F 1852, Type 1 Nuts ASTM Designation: A 563, including Appendix X1* Hardened washers ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Zinc-coated Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M Washers ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications	Components of high-streng	th steel fastener assemblies for use in structural	
Tension control bolts Nuts ASTM Designation: F 1852, Type 1 ASTM Designation: A 563, including Appendix X1* Hardened washers Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M Washers ASTM Designation: F 593 or F 738M ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications			
Tension control bolts Nuts ASTM Designation: F 1852, Type 1 ASTM Designation: A 563, including Appendix X1* Hardened washers Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M Washers ASTM Designation: F 593 or F 738M ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications	Bolts	ASTM Designation: A 325, Type 1	
Nuts ASTM Designation: A 563, including Appendix X1* Hardened washers Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M ASTM Designation: F 594 or F 836M Washers ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications	Tension control bolts		
Appendix X1* Hardened washers ASTM Designation: F 436, Type 1, Circular, including S1 supplementary requirements Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications			
Hardened washers Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M ASTM Designation: F 593 or F 738M ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality Commercial quality Commercial quality			
including S1 supplementary requirements Direct tension indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 593 or F 738M ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications	Hardened washers		
Direct tension indicators zinc-coated Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications			
indicators Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications	Direct tension		
Stainless steel fasteners (Alloys 304 & 316) for general applications: Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications	indicators		
Bolts, screws, studs, threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications		lloys 304 & 316) for general applications:	
threaded rods, and nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications			
nonheaded anchor bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications			
bolts Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications	1		
Nuts ASTM Designation: F 594 or F 836M Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications			
Washers ASTM Designation: A 240/A 240M and ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications		ASTM Designation: F 594 or F 836M	
ANSI B 18.22M Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications			
Carbon-steel castings ASTM Designation: A 27/A 27M, Grade 65-35 [450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications	THE MANAGEMENT OF THE PARTY OF		
[450-240], Class 1 Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications [450-240], Class 1 ASTM Designation: A 47, Grade 32510 or A 47M, Grade 32510 or A 47M, Grade 22010 ASTM Designation: A 48, Class 30B Commercial quality Commercial quality	Carbon-steel castings		
Malleable iron castings ASTM Designation: A 47, Grade 32510 or A 47M, Grade 22010 Gray iron castings Ductile iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications Commercial quality	Caroon steer custings		
Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications ASTM Designation: A 536, Grade 65-45-12 Commercial quality Commercial quality	Malleable iron castings		
Gray iron castings ASTM Designation: A 48, Class 30B Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications Commercial quality	Maneagle from castings		
Ductile iron castings ASTM Designation: A 536, Grade 65-45-12 Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications Commercial quality	Gray iron cactings		
Cast iron pipe Commercial quality Steel pipe Commercial quality, welded or extruded Other parts for general applications Commercial quality applications			
Steel pipe Commercial quality, welded or extruded Other parts for general applications Commercial quality			
Other parts for general applications Commercial quality			
applications			
		Commercial quality	

^{*} Zinc-coated nuts that will be tightened beyond snug or wrench tight shall be furnished with a dyed dry lubricant conforming to Supplementary Requirement S2 in ASTM Designation: A 563.

The table in the eighteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

	Sustained Tension	
Stud Diameter	Test Load	
(millimeters)	(kilonewtons)	
29.01-33.00	137.9	
23.01-29.00	79.6	
21.01-23.00	64.1	
* 18.01-21.00	22.2	
15.01-18.00	18.2	
12.01-15.00	14.2	
9.01-12.00	9.34	
6.00-9.00	4.23	

^{*} Maximum stud diameter permitted for mechanical expansion anchors.

The table in the nineteenth paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

	Ultimate	
Stud Diameter	Tensile Load	
(millimeters)	(kilonewtons)	
30.01-33.00	112.1	
27.01-30.00	88.1	
23.01-27.00	71.2	
20.01-23.00	51.6	
16.01-20.00	32.0	
14.01-16.00	29.4	
12.00-14.00	18.7	

The table in the twenty-second paragraph of Section 75-1.03, "Miscellaneous Bridge Metal," of the Standard Specifications is amended to read:

Installation Torque Values, (newton meters)

	Shell Type	pe Integral Stud Type Resin Capsule		
	Mechanical	Mechanical	Anchors	
Stud Diameter	Expansion	Expansion	and	
(millimeters)	Anchors	Anchors	Cast-in-Place Inserts	
29.01-33.00		_	540	
23.01-29.00	_	_	315	
21.01-23.00	_	_	235	
18.01-21.00	110	235	200	
15.01-18.00	45	120	100	
12.01-15.00	30	65	40	
9.01-12.00	15	35	24	
6.00-9.00	5	10	_	

SECTION 8-2. CONCRETE

8-2.01 PORTLAND CEMENT CONCRETE

Portland cement concrete shall conform to the provisions in Section 90, "Portland Cement Concrete," of the Standard Specifications and these special provisions.

References to Section 90-2.01, "Portland Cement," of the Standard Specifications shall mean Section 90-2.01, "Cement," of the Standard Specifications.

Mineral admixture shall be combined with cement in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures," of the Standard Specifications for the concrete materials specified in Section 56-2, "Roadside Signs," of the Standard Specifications.

The requirements of Section 90-4.08, "Required Use of Mineral Admixture," of the Standard Specifications shall not apply to Section 19-3.025C, "Soil Cement Bedding," of the Standard Specifications.

The Department maintains a list of sources of fine and coarse aggregate that have been approved for use with a reduced amount of mineral admixture in the total amount of cementitious material to be used. A source of aggregate will be considered for addition to the approved list if the producer of the aggregate submits to the Transportation Laboratory certified test results from a qualified testing laboratory that verify the aggregate complies with the requirements. Prior to starting the testing, the aggregate test shall be registered with the Department. A registration number can be obtained by calling (916) 227-7228. The registration number shall be used as the identification for the aggregate sample in correspondence with the Department. Upon request, a split of the tested sample shall be provided to the Department. Approval of aggregate will depend upon compliance with the specifications, based on the certified test results submitted, together with any replicate testing the Department may elect to perform. Approval will expire 3 years from the date the most recent registered and evaluated sample was collected from the aggregate source.

Qualified testing laboratories shall conform to the following requirements:

- A. Laboratories performing ASTM Designation: C 1293 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Concrete Proficiency Sample Program and shall have received a score of 3 or better on all tests of the previous 2 sets of concrete samples.
- B. Laboratories performing ASTM Designation: C 1260 shall participate in the Cement and Concrete Reference Laboratory (CCRL) Pozzolan Proficiency Sample Program and shall have received a score of 3 or better on the shrinkage and soundness tests of the previous 2 sets of pozzolan samples.

Aggregates on the list shall conform to one of the following requirements:

- A. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1293, the average expansion at one year shall be less than or equal to 0.040 percent; or
- B. When the aggregate is tested in conformance with the requirements in California Test 554 and ASTM Designation: C 1260, the average of the expansion at 16 days shall be less than or equal to 0.15 percent.

The amounts of cement and mineral admixture used in cementitious material shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," of the Standard Specifications and shall conform to the following:

- A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content.
- B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:
 - 1. When the calcium oxide content of a mineral admixture is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix.
 - 2. When the calcium oxide content of a mineral admixture is greater than 2 percent by mass, and any of the aggregates used are not listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix.
 - 3. When the calcium oxide content of a mineral admixture is greater than 2 percent by mass and the fine and coarse aggregates are listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix.
 - 4. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," of the Standard Specifications is used, the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix.
 - 5. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," of the Standard Specifications is used and the fine and coarse aggregates are listed on the approved list as specified in these special provisions, then the amount of mineral admixture shall not be less than 7 percent by mass of the total amount of cementitious material to be used in the mix.
- C. The total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," of the Standard Specifications specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

The Contractor will be permitted to use Type III portland cement for concrete used in the manufacture of precast concrete members.

SECTION 8-3. WELDING

8-3.01 WELDING

GENERAL

Flux core welding electrodes conforming to the requirements of AWS A5.20 E6XT-4 or E7XT-4 shall not be used to perform any type of welding for this project.

Wherever reference is made to the following AWS welding codes in the Standard Specifications, on the plans, or in these special provisions, the year of adoption for these codes shall be as listed:

AWS Code	Year of Adoption
D1.1	2000
D1.4	1992
D1.5	1995
D1.5 (metric only)	1996

Requirements of the AWS welding codes shall apply unless specified otherwise in the Standard Specifications, on the plans, or in these special provisions. Wherever the abbreviation AWS is used, it shall be equivalent to the abbreviations ANSI/AWS or ANSI/AASHTO/AWS.

Sections 6.1.2 through 6.1.4.3 of AWS D 1.1, Sections 7.1.1 and 7.1.2 of AWS D 1.4, and Sections 6.1.1.1 through 6.1.3.3 of AWS D 1.5 are replaced with the following:

Quality Control (QC) shall be the responsibility of the Contractor. As a minimum, the Contractor shall perform inspection and testing prior to welding, during welding, and after welding as specified in this section and additionally as necessary to ensure that materials and workmanship conform to the requirements of the contract documents.

The QC Inspector shall be the duly designated person who acts for and on behalf of the Contractor for inspection, testing, and quality related matters for all welding.

Quality Assurance (QA) is the prerogative of the Engineer. The QA Inspector is the duly designated person who acts for and on behalf of the Engineer.

Each QC Inspector shall be responsible for quality control acceptance or rejection of materials and workmanship, and shall be currently certified as an AWS Certified Welding Inspector (CWI) in conformance with the requirements in AWS QC1, "Standard and Guide for Qualification of Welding Inspectors."

The QC Inspector may be assisted by an Assistant QC Inspector provided that this individual is currently certified as an AWS Certified Associate Welding Inspector (CAWI) in conformance with the requirements in AWS QC1, "Standard and Guide for Qualification of Welding Inspectors," or has equivalent qualifications. The QC Inspector shall monitor the Assistant QC Inspector's work, and shall be responsible for signing all reports.

When the term "Inspector" is used without further qualification, it shall refer to the QC Inspector.

Section 6.14.6, "Personnel Qualification," of AWS D 1.1, Section 7.7.6, "Personnel Qualification," of AWS D 1.4, and Section 6.1.3.4, "Personnel Qualification," of AWS D 1.5 are replaced with the following:

Personnel performing nondestructive testing (NDT) shall be qualified in conformance with the requirements of the American Society for Nondestructive Testing (ASNT) Recommended Practice No. SNT-TC-1A and the Written Practice of the NDT firm. The Written Practice of the NDT firm shall meet or exceed the requirements of the ASNT Recommended Practice No. SNT-TC-1A. Only individuals who are 1) qualified for NDT Level II, or 2) Level III technicians who have been directly certified by the ASNT and are authorized to perform the work of Level II technicians, shall perform NDT, review the results, and prepare the written reports.

Section 6.5.4, "Scope of Examination," of AWS D 1.1 and Section 7.5.4 of AWS D 1.4 are replaced with the following:

The QC Inspector shall inspect and approve the joint preparation, assembly practice, welding techniques, and performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved welding procedure specification (WPS) are met.

Section 6.5.4 of AWS D 1.5 is replaced with the following:

The QC Inspector shall inspect and approve the joint preparation, assembly practice, welding techniques, and performance of each welder, welding operator, and tack welder to make certain that the applicable requirements of this code and the approved WPS are met. The QC Inspector shall examine the work to make certain that it meets the requirements of Sections 3 and 9.21. The size and contour of welds shall be measured using suitable gages. Visual inspection for cracks in welds and base metal, and for other discontinuities should be aided by strong light magnifiers, or such other devices as may be helpful. Acceptance criteria different from those specified in this code may be used when approved by the Engineer.

Section 6.6.5, "Nonspecified Nondestructive Testing Other Than Visual," of AWS D 1.1, Section 6.6.5 of AWS D 1.4 and Section 6.6.5 of AWS D 1.5 shall not apply.

For any welding, the Engineer may direct the Contractor to perform NDT that is in addition to the visual inspection or NDT specified in the AWS welding codes, in the Standard Specifications, or in these special provisions. Additional NDT required by the Engineer, will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications. Should any welding deficiencies be discovered by this additional NDT, the cost of the testing will not be paid for as extra work but shall be at the Contractor's expense.

Required repair work to correct welding deficiencies, whether discovered by the required visual inspection or NDT, or by additional NDT directed by the Engineer, and any associated delays or expenses caused to the Contractor by performing these repairs, shall be at the Contractor's expense.

The Engineer shall have the authority to verify the qualifications or certifications of any welder, QC Inspector, or NDT personnel to specified levels by retests or other means.

A sufficient number of QC Inspectors shall be provided to ensure continuous inspection when any welding is being performed. Continuous inspection, as a minimum, shall include (1) having QC Inspectors continually present when any welding operation is being performed, or (2) having a QC Inspector within such close proximity of all welding operations that inspections by the QC Inspector of each operation, at each welding location, shall not lapse for a period exceeding 30 minutes.

Inspection and approval of the joint preparation, assembly practice, welding techniques, and performance of each welder, welding operator, and tack welder shall be documented by the QC Inspector on a daily basis for each day that welding is performed.

When joint details that are not prequalified by the applicable AWS codes are proposed for use in the work, welders using these details shall perform a qualification test plate using the approved WPS variables and the joint detail to be used in production. The test plate shall be the maximum thickness to be used in production. The test plate shall be mechanically or radiographically tested as directed by the Engineer. Mechanical and radiographic testing and acceptance criteria shall be as specified in the applicable AWS codes.

The period of effectiveness for a welder's or welding operator's qualification shall be a maximum of 3 years for the same weld process, welding position, and weld type. A valid qualification at the beginning of work on a contract will be acceptable for the entire period of the contract, as long as the welder's work remains satisfactory.

WELDING QUALITY CONTROL

Welding quality control shall conform to the requirements in the AWS welding codes, the Standard Specifications, and these special provisions.

Unless otherwise specified, welding quality control shall apply when any work is welded in conformance with the provisions in Section 49, "Piling," Section 52, "Reinforcement," Section 55, "Steel Structures," Section 56-1, "Overhead Sign Structures," Section 75-1.035, "Bridge Joint Restrainer Units," or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

The welding of fracture critical members (FCMs) shall conform to the provisions specified in the Fracture Control Plan (FCP) and herein.

The Contractor shall designate in writing a welding Quality Control Manager (QCM). The QCM shall be responsible directly to the Contractor for the quality of welding, including materials and workmanship, performed by the Contractor and subcontractors.

The QCM shall be the sole individual responsible to the Contractor for submitting, receiving, and approving all correspondence, required submittals, and reports to and from the Engineer.

The QCM shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project. The QCM may be an employee of the Contractor.

Welding inspection personnel or NDT firms to be used in the work shall not be employed or compensated by any subcontractor, or by other persons or entities hired by subcontractors, who will provide other services or materials for the project, except for the following conditions:

- A. The welding is performed at a permanent fabrication facility which is certified under the AISC Quality Certification Program, Category Cbr, Major Steel Bridges.
- B. The welding is performed at a permanent fabrication facility which is certified under the AISC Quality Certification Program, Category Sbd, Conventional Steel Building Structures. This condition shall apply only for work welded in conformance with the provisions in Section 56-1, "Overhead Sign Structures" or Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications.

For welding performed at such certified facilities, the inspection personnel or NDT firms may be employed or compensated by the fabrication facility performing the welding.

Prior to submitting the Welding Quality Control Plan (WQCP) required herein, a pre-welding meeting between the Engineer, Contractor, and any entity performing welding for this project, shall be held to discuss the requirements for the WQCP.

Except for work that is welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, prior to performing any welding, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate WQCP for each item of work for which welding is to be performed.

Prior to furnishing materials welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate WQCP for each fabrication facility supplying these materials or proof of previous Engineer approval of a WQCP for such a facility no more than one year prior to the delivery of materials for inspection.

As a minimum, each WQCP shall include the following:

- A. The name of the welding firm and any required NDT firms;
- B. A manual prepared by the NDT firm that shall include equipment, testing procedures, code of safe practices, the Written Practice of the NDT firm, and the names, qualifications, and documentation of certifications for all personnel to be used;
- C. The name of the QCM and the names, qualifications, and documentation of certifications for all QC Inspectors and Assistant QC Inspectors to be used;
- D. An organizational chart showing all QC personnel and their assigned QC responsibilities;
- E. The methods and frequencies for performing all required quality control procedures, including QC inspection forms to be used, as required by the specifications including:
 - 1. all visual inspections;
 - 2. all NDT including radiographic geometry, penetrameter and shim selection, film quality, film processing, radiograph identification and marking system, and film interpretation and reports; and
 - 3. calibration procedures and calibration frequency for all NDT equipment;
- F. A system for the identification and tracking of all welds, NDT, and any required repairs, and a procedure for the reinspection of repaired welds. The system shall have provisions for 1) permanently identifying each weld and the person who performed the weld, 2) placing all identification and tracking information on each radiograph, 3) a method of reporting nonconforming welds to the Engineer, and 4) a method of documentation of repairs and reinspection of nonconforming welds;
- G. Standard procedures for performing noncritical repair welds. Noncritical repair welds are-defined as welds to deposit additional weld beads or layers to compensate for insufficient weld size and to fill limited excavations that were performed to remove unacceptable edge or surface discontinuities, rollover or undercut. The depth of these excavations shall not exceed 65 percent of the specified weld size;
- H. The WPS, including documentation of all supporting Procedure Qualification Record (PQR) tests performed, and the name of the testing laboratory who performed the tests, to verify the acceptability of the WPS. The submitted WPS shall be within the allowable period of effectiveness;
- I. Documentation of all certifications for welders for each weld process and position that will be used. Certifications shall list the electrodes used, test position, base metal and thickness, tests performed, and the witnessing authority. All certifications shall be within the allowable period of effectiveness;
- J. One copy each of all AWS welding codes and the FCP which are applicable to the welding to be performed. These codes and the FCP shall become the permanent property of the Department; and
- K. Forms to be used for Certificates of Compliance, daily production logs, and daily reports.

The Engineer shall have 10 working days to review the WQCP submittal after a complete plan has been received. Except for work that is welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, no welding shall be performed until the WQCP is approved in writing by the Engineer. No materials welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, shall be incorporated into the work until the WQCP is approved in writing by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the WQCP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

An amended WQCP or addendum shall be submitted to, and approved in writing by the Engineer, for proposed revisions to the approved WQCP. An amended WQCP or addendum will be required for revisions to the WQCP, including but not limited to a revised WPS, additional welders, changes in NDT firms or procedures, QC, or NDT personnel, or updated systems for tracking and identifying welds. The Engineer shall have 3 working days to complete the review of the amended WQCP or addendum. Work that is affected by any of the proposed revisions shall not be performed until the amended WQCP or addendum has been approved. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the amended WQCP or addendum, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

After final approval of the WQCP, amended WQCP, or addendum, the Contractor shall submit 7 copies to the Engineer of each of these approved documents.

It is expressly understood that the Engineer's approval of the Contractor's WQCP shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformity with the requirements of the plans and specifications. The Engineer's approval shall not constitute a waiver of any requirement of the plans and specifications nor relieve the Contractor of any obligation thereunder, and defective work, materials, and equipment may be rejected notwithstanding approval of the WQCP.

A daily production log for welding shall be kept by the QCM for each day that welding is performed. The log shall clearly indicate the locations of all welding, except partial penetration longitudinal seam welds performed in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications. The log shall include the welders' names, amount of welding performed, any problems or deficiencies discovered, and any testing or repair work performed, at each location. The daily report from each QC Inspector shall also be included in the log.

The following items shall be included in a Welding Report that is to be submitted to the Engineer within 7 days following the performance of any welding. For work welded in conformance with Section 86-2.04, "Standards, Steel Pedestals and Posts," of the Standard Specifications, the following items shall be included in a Welding Report that is to be submitted to the Engineer 48 hours prior to the Contractor furnishing a Certificate of Compliance for the material:

- A. Reports of all visual weld inspections and NDT;
- B. Radiographs and radiographic reports, and other required NDT reports;
- C. Documentation that the Contractor has evaluated all radiographs and other nondestructive tests and corrected all rejectable deficiencies, and all repaired welds have been reexamined by the required NDT and found acceptable; and
- D. Daily production log.

Radiographic envelopes shall have clearly written on the outside of the envelope the following information: name of the QCM, name of the nondestructive testing firm, name of the radiographer, date, contract number, complete part description, and all included weld numbers or a report number, as detailed in the WQCP. In addition, all innerleaves shall have clearly written on them the part description and all included weld numbers, as detailed in the WQCP.

Reports regarding NDT, including radiographs, shall be signed by both the NDT technician and the person that performed the review, and then submitted directly to the QCM for review and signature prior to submittal to the Engineer. Corresponding names shall be clearly printed or typewritten next to all signatures.

The Engineer will review the Welding Report to determine if the Contractor is in conformance with the WQCP. Unless otherwise specified, the Engineer shall be allowed 7 working days to review the report and respond in writing after a complete Welding Report has been received. Prior to receiving notification from the Engineer of the Contractor's conformance with the WQCP, the Contractor may encase in concrete or cover welds for which a Welding Report has been submitted. However, should the Contractor elect to encase or cover those welds prior to receiving notification from the Engineer, it is expressly understood that the Contractor shall not be relieved of the responsibility for incorporating material in the work that conforms to the requirements of the plans and specifications. Material not conforming to these requirements will be subject to rejection. Should the Contractor elect to wait to encase or cover welds pending notification by the Engineer, and should the Engineer fail to complete the review and provide notification within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in notification, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QC Inspector shall provide reports to the QCM on a daily basis for each day that welding is performed.

Except for noncritical weld repairs, the Engineer shall be notified immediately in writing when welding problems, deficiencies, base metal repairs, or any other type of repairs not submitted in the WQCP are discovered and also of the proposed repair procedures to correct them. The Engineer shall have 5 working days to review these procedures. No remedial work shall begin until the repair procedures are approved in writing by the Engineer. Should the Engineer fail to complete the review within this time allowance, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the proposed repair procedures, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

The QCM shall sign and furnish to the Engineer, a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications for each item of work for which welding was performed. The certificate shall state that all of the materials and workmanship incorporated in the work, and all required tests and inspections of this work, have been performed in conformance with the details shown on the plans and the provisions of the Standard Specifications and these special provisions.

PAYMENT

Full compensation for conforming to the requirements of this section shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

SECTION 9. DESCRIPTION OF BRIDGE WORK

The work shall consist, in general of, replacing steel pedestal plates, replacing threaded studs, repairing welds and epoxy injecting cracks of Pit River BOH, Bridge No. 06-0021.

SECTION 10. CONSTRUCTION DETAILS SECTION 10-1. GENERAL

10-1.01 ORDER OF WORK

Order of work shall conform to the provisions in Section 5-1.05, "Order of Work," of the Standard Specifications and these special provisions.

10-1.02 PREVENTION OF SWALLOW NESTING AND BAT ROOSTING

It is anticipated that swallows may try to nest and bats may try to roost on the Pit River Bridge Overhead, Bridge Number 06-0021, between March 15th and October 1st. The Contractor shall be responsible for prevention of swallow nesting and bat roosting in accordance with these special provisions

Swallows shall be prevented from nesting within 4.6 m of a work area between March 15th and September 1st. Using netting or screening can preclude nesting. Such devices, if implemented, shall be installed prior to March 15th. If netting or screening is not installed, or is ineffective, removing of partially completed nests is permitted to discourage nesting. Removing shall be performed daily, or more often if necessary, between March 15th and September 1st. If new nests within the 4.6 m buffer zone are more than 30 percent completed, as determined by the Engineer, work shall be suspended by the Engineer in accordance with Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications.

Swallows shall be allowed to nest on portions of the bridge where conflicts during construction are not anticipated.

Bats shall be prevented from roosting inside deck expansion joints within 4.6 m of a work area between April 1st and October 1st. Expansion joints shall be, screened or netted prior to April 1st to preclude bat habitation. If bats inhabit the expansion joints within the 4.6 m buffer zone, work shall be suspended by the Engineer in accordance with Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications.

Netting and devices installed to prevent swallow nesting and bat roosting shall be removed when no longer needed, as determined by the Engineer.

Full compensation for conforming to the requirements of this section shall be considered as included in the contract prices paid for the various contract items of work and no additional compensation will be allowed therefor.

10-1.03 WATER POLLUTION CONTROL

Water pollution control work shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications and these special provisions.

Water pollution control work shall conform to the requirements in the "Storm Water Pollution Prevention Plan (SWPPP) and Water Pollution Control Program (WPCP) Preparation Manual" and the "Construction Site Best Management Practices (BMPs) Manual," and addenda thereto issued up to, and including, the date of advertisement of the project, hereafter referred to respectively as the "Preparation Manual" and the "Construction Site BMP Manual" and collectively as the "Manuals." Copies of the Manuals may be obtained from the Department of Transportation, Material Operations Branch, Publication Distribution Unit, 1900 Royal Oaks Drive, Sacramento, California 95815, Telephone: (916) 445-3520. Copies of the Manuals obtained Department's Internet mav also be from the Web http://www.dot.ca.gov/hq/construc/stormwater.html.

Copies of the Manuals are also available for review at the North Region Construction Office at 961 Live Oak Boulevard, Yuba City, California 95991.

The Contractor shall know and fully comply with the applicable provisions of the Manuals and Federal, State, and local regulations that govern the Contractor's operations and storm water discharges from both the project site and areas of disturbance outside the project limits during construction.

Unless arrangements for disturbance of areas outside the project limits are made by the Department and made part of the contract, it is expressly agreed that the Department assumes no responsibility whatsoever to the Contractor or property owner with respect to any arrangements made between the Contractor and property owner to allow disturbance of areas outside the project limits.

The Contractor shall be responsible for the costs and for liabilities imposed by law as a result of the Contractor's failure to comply with the requirements set forth in this section "Water Pollution Control" including, but not limited to, compliance with the applicable provisions of the Manuals and Federal, State, and local regulations. For the purposes of this paragraph,

costs and liabilities include, but are not limited to, fines, penalties, and damages whether assessed against the State or the Contractor, including those levied under the Federal Clean Water Act and the State Porter Cologne Water Quality Act.

In addition to the remedies authorized by law, an amount of the money due the Contractor under the contract, as determined by the Department, may be retained by the State of California until disposition has been made of the costs and liabilities.

The retention of money due the Contractor shall be subject to the following:

- A. The Department will give the Contractor 30 days notice of the Department's intention to retain funds from partial payments which may become due to the Contractor prior to acceptance of the contract. Retention of funds from payments made after acceptance of the contract may be made without prior notice to the Contractor.
- B. No retention of additional amounts out of partial payments will be made if the amount to be retained does not exceed the amount being withheld from partial payments pursuant to Section 9-1.06, "Partial Payments," of the Standard Specifications.
- C. If the Department has retained funds and it is subsequently determined that the State is not subject to the costs and liabilities in connection with the matter for which the retention was made, the Department shall be liable for interest on the amount retained at the legal rate of interest for the period of the retention.

Conformance with the provisions in this section "Water Pollution Control" shall not relieve the Contractor from the Contractor's responsibilities as provided in Section 7, "Legal Relations and Responsibilities," of the Standard Specifications.

WATER POLLUTION CONTROL PROGRAM PREPARATION, APPROVAL AND UPDATES

As part of the water pollution control work, a Water Pollution Control Program, hereafter referred to as the "WPCP," is required for this contract. The WPCP shall conform to the provisions in Section 7-1.01G, "Water Pollution," of the Standard Specifications, the requirements in the Manuals, and these special provisions.

No work having potential to cause water pollution, as determined by the Engineer, shall be performed until the WPCP has been approved by the Engineer.

Within 30 days after the approval of the contract, the Contractor shall submit 3 copies of the WPCP to the Engineer. The Engineer will have 7 days to review the WPCP. If revisions are required, as determined by the Engineer, the Contractor shall revise and resubmit the WPCP within 7 days of receipt of the Engineer's comments. The Engineer will have 7 days to review the revisions. Upon the Engineer's approval of the WPCP, 3 additional copies of the WPCP incorporating the required changes shall be submitted to the Engineer. Minor changes or clarifications to the initial submittal may be made and attached as amendments to the WPCP. In order to allow construction activities to proceed, the Engineer may conditionally approve the WPCP while minor revisions or amendments are being completed.

The WPCP shall identify pollution sources that may adversely affect the quality of storm water discharges associated with the project and shall identify water pollution control measures, hereafter referred to as control measures, to be constructed, implemented, and maintained in order to reduce to the extent feasible pollutants in storm water discharges from the construction site during construction under this contract.

The WPCP shall incorporate control measures in the following categories:

- A. Soil stabilization;
- B. Sediment control;
- C. Tracking control;
- D. Wind erosion control;
- E. Non-storm water control; and
- F. Waste management and material pollution control.

Specific objectives and minimum requirements for each category of control measures are contained in the Manuals.

The Contractor shall consider the objectives and minimum requirements presented in the Manuals for each of the above categories. When minimum requirements are listed for any category, the Contractor shall incorporate into the WPCP and implement on the project, one or more of the listed minimum controls required in order to meet the pollution control objectives for the category. In addition, the Contractor shall consider other control measures presented in the Manuals and shall incorporate into the WPCP and implement on the project the control measures necessary to meet the objectives of the WPCP. The Contractor shall document the selection process in conformance with the procedure specified in the Manuals.

The WPCP shall include, but not be limited to, the following items as described in the Preparation Manual:

- A. Project description and Contractor's certification;
- B. Project information;
- C. Pollution sources, control measures, and water pollution control drawings; and
- D. Amendments, if any.

The Contractor shall amend the WPCP, graphically and in narrative form, whenever there is a change in construction activities or operations which may affect the discharge of significant quantities of pollutants to surface waters, ground waters, municipal storm drain systems or when deemed necessary by the Engineer. The WPCP shall be amended if the WPCP has not achieved the objective of reducing pollutants in storm water discharges. Amendments shall show additional control measures or revised operations, including those in areas not shown in the initially approved WPCP, which are required on the project to control water pollution effectively. Amendments to the WPCP shall be submitted for review and approval by the Engineer in the same manner specified for the initially approved WPCP. Amendments shall be dated and attached to the onsite WPCP document.

The Contractor shall keep a copy of the WPCP, together with updates, revisions and amendments at the project site.

WPCP IMPLEMENTATION

Upon approval of the WPCP, the Contractor shall be responsible throughout the duration of the project for installing, constructing, inspecting, and maintaining the control measures included in the WPCP and any amendments thereto and for removing and disposing of temporary control measures. Unless otherwise directed by the Engineer or specified in these special provisions, the Contractor's responsibility for WPCP implementation shall continue throughout any temporary suspension of work ordered in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. Requirements for installation, construction, inspection, maintenance, removal, and disposal of control measures are specified in the Manuals and these special provisions.

Soil stabilization practices and sediment control measures, including minimum requirements, shall be provided throughout the rainy season, defined as between October 15 and April 15.

Implementation of soil stabilization practices and sediment control measures for soil-disturbed areas on the project site shall be completed, except as provided for below, not later than 20 days prior to the beginning of the rainy season or upon start of applicable construction activities for projects which begin either during or within 20 days of the rainy season.

Throughout the rainy season, the active, soil-disturbed area of the project site shall be not more than 1.9 hectares. The Engineer may approve, on a case-by-case basis, expansions of the active, soil-disturbed area limit. The Contractor shall demonstrate the ability and preparedness to fully deploy soil stabilization practices and sediment control measures to protect soil-disturbed areas on the project site before the onset of precipitation. A quantity of soil stabilization and sediment control materials shall be maintained on site equal to ____ percent of that sufficient to protect unprotected, soil-disturbed areas on the project site. A detailed plan for the mobilization of sufficient labor and equipment shall be maintained to fully deploy control measures required to protect unprotected, soil-disturbed areas on the project site prior to the onset of precipitation. A current inventory of control measure materials and the detailed mobilization plan shall be included as part of the WPCP.

Throughout the rainy season, soil-disturbed areas on the project site shall be considered to be nonactive whenever soil disturbing activities are expected to be discontinued for a period of 20 or more days and the areas are fully protected. Areas that will become nonactive either during the rainy season or within 20 days thereof shall be fully protected with soil stabilization practices and sediment control measures within 10 days of the discontinuance of soil disturbing activities or prior to the onset of precipitation, whichever is first to occur.

Throughout the rainy season, active soil-disturbed areas of the project site shall be fully protected at the end of each day with soil stabilization practices and sediment control measures unless fair weather is predicted through the following work day. The weather forecast shall be monitored by the Contractor on a daily basis. The National Weather Service forecast shall be used. An alternative weather forecast proposed by the Contractor may be used if approved by the Engineer. If precipitation is predicted prior to the end of the following work day, construction scheduling shall be modified, as required, and functioning control measures shall be deployed prior to the onset of the precipitation.

The Contractor shall implement, year-round and throughout the duration of the project, control measures included in the WPCP for tracking control, wind erosion control, non-storm water control, and waste management and material pollution control.

The Engineer may order the suspension of construction operations which create water pollution if the Contractor fails to conform to the provisions in this section "Water Pollution Control" as determined by the Engineer.

MAINTENANCE

To ensure the proper implementation and functioning of control measures, the Contractor shall regularly inspect and maintain the construction site for the control measures identified in the WPCP. The Contractor shall identify corrective actions and time needed to address any deficient measures or reinitiate any measures that have been discontinued.

The construction site inspection checklist provided in the Preparation Manual shall be used to ensure that the necessary measures are being properly implemented, and to ensure that the control measures are functioning adequately. One copy of each site inspection record shall be submitted to the Engineer.

During the rainy season, inspections of the construction site shall be conducted by the Contractor to identify deficient measures, as follows:

- A. Prior to a forecast storm;
- B. After all precipitation which causes runoff capable of carrying sediment from the construction site;
- C. At 24-hour intervals during extended precipitation events; and
- D. Routinely, at a minimum of once every 2 weeks.

If the Contractor or the Engineer identifies a deficiency in the deployment or functioning of an identified control measure, the deficiency shall be corrected immediately. The deficiency may be corrected at a later date and time if requested by the Contractor and approved by the Engineer in writing, but not later than the onset of subsequent precipitation events. The correction of deficiencies shall be at no additional cost to the State.

PAYMENT

Full compensation for conforming to the provisions in this section shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.

Those control measures for which there is a contract item of work will be measured and paid for as that contract item of work.

The Engineer will retain an amount equal to 25 percent of the estimated value of the contract work performed during estimate periods in which the Contractor fails to conform to the provisions in this section "Water Pollution Control" as determined by the Engineer.

Retentions for failure to conform to the provisions in this section "Water Pollution Control" shall be in addition to the other retentions provided for in the contract. The amounts retained for failure of the Contractor to conform to the provisions in this section will be released for payment on the next monthly estimate for partial payment following the date that a WPCP has been implemented and maintained and water pollution is adequately controlled, as determined by the Engineer.

10-1.04 COOPERATION

Attention is directed to Section 7-1.14, "Cooperation," and Section 8-1.10, "Utility and Non-Highway Facilities," of the Standard Specifications and these special provisions.

It is anticipated that work by other contractors may be in progress adjacent to or within the limits of this project during progress of the work on this contract. Concurrent projects adjacent to this project are:

CONTRACT		LOCATION										
No.	Co	Rte	PM	KP								
02-382604	Sha	5	28.9 - 29.3	46.5 - 47.1								
02-388804	Sha	5	R28.9-R59.9	R46.5-R96.4								
02-358204	Sha	5	R34.2-R40.2	R55.0-R64.7								

10-1.05 PROGRESS SCHEDULE

Progress schedules are required for this contract and shall be submitted in conformance with the provisions in Section 8-1.04, "Progress Schedule," of the Standard Specifications and these special provisions, unless otherwise authorized in writing by the Engineer.

The second paragraph of Section 8-1.04, "Progress Schedule," of the Standard Specifications shall not apply.

10-1.06 CONSTRUCTION AREA TRAFFIC CONTROL DEVICES

Flagging, signs, and all other traffic control devices furnished, installed, maintained, and removed when no longer required shall conform to the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Category 1 traffic control devices are defined as those devices that are small and lightweight (less than 45 kg), and have been in common use for many years. The devices shall be known to be crashworthy by crash testing, crash testing of similar devices, or years of demonstrable safe performance. Category 1 traffic control devices include traffic cones, plastic drums, portable delineators, and channelizers.

If requested by the Engineer, the Contractor shall provide written self-certification for crashworthiness of Category 1 traffic control devices. Self-certification shall be provided by the manufacturer or Contractor and shall include the following: date, Federal Aid number (if applicable), expenditure authorization, district, county, route and kilometer post of project limits; company name of certifying vendor, street address, city, state and zip code; printed name, signature and title of certifying person; and an indication of which Category 1 traffic control devices will be used on the project. The Contractor may obtain a standard form for self-certification from the Engineer.

Category 2 traffic control devices are defined as those items that are small and lightweight (less than 45 kg), that are not expected to produce significant vehicular velocity change, but may otherwise be potentially hazardous. Category 2 traffic control devices include: barricades and portable sign supports.

Category 2 devices purchased on or after October 1, 2000 shall be on the Federal Highway Administration (FHWA) Acceptable Crashworthy Category 2 Hardware for Work Zones list. This list is maintained by FHWA and can be located at the following internet address: http://safety.fhwa.dot.gov/fourthlevel/hardware/listing.cfm?code=workzone. The Department maintains a secondary list at the following internet address: http://www.dot.ca.gov/hq/traffops/signtech/signdel/pdffiles.htm.

Category 2 devices that have not received FHWA acceptance, and were purchased before October 1, 2000, may continue to be used until they complete their useful service life or until January 1, 2003, whichever comes first. Category 2 devices in use that have received FHWA acceptance shall be labeled with the FHWA acceptance letter number and the name of the manufacturer by the start of the project. The label shall be readable. After January 1, 2003, all Category 2 devices without a label shall not be used on the project.

Full compensation for providing self-certification for crashworthiness of Category 1 traffic control devices and labeling Category 2 devices as specified shall be considered as included in the prices paid for the various contract items of work requiring the use of the Category 1 or Category 2 traffic control devices and no additional compensation will be allowed therefor.

10-1.07 CONSTRUCTION AREA SIGNS

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Attention is directed to the provisions in "Prequalified and Tested Signing and Delineation Materials" of these special provisions. Type II retroreflective sheeting shall not be used on construction area sign panels.

The Contractor shall notify the appropriate regional notification center for operators of subsurface installations at least 2 working days, but not more than 14 calendar days, prior to commencing excavation for construction area sign posts. The regional notification centers include, but are not limited to, the following:

Notification Center	Telephone Number
Underground Service Alert-Northern California (USA)	1-800-642-2444 1-800-227-2600
Underground Service Alert-Southern California (USA)	1-800-422-4133 1-800-227-2600

Excavations required to install construction area signs shall be performed by hand methods without the use of power equipment, except that power equipment may be used if it is determined there are no utility facilities in the area of the proposed post holes.

Sign substrates for stationary mounted construction area signs may be fabricated from fiberglass reinforced plastic as specified under "Prequalified and Tested Signing and Delineation Materials" of these special provisions.

10-1.08 MAINTAINING TRAFFIC

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," and 12, "Construction Area Traffic Control Devices," of the Standard Specifications and to the provisions in "Public Safety" of these special provisions

and these special provisions. Nothing in these special provisions shall be construed as relieving the Contractor from the responsibilities specified in Section 7-1.09.

Lane closures shall conform to the provisions in section "Traffic Control System for Lane Closure" of these special provisions.

Lane closures will be allowed only for delivery and removal of equipment. A maximum of 10 days of lane closures will be allowed.

For lane closures in the southbound direction, the beginning of the lane reduction shall be located on a flat tangent section of the roadway 2.0 (1.3 mi) north of the bridge, just prior to a curvilinear down hill section. For lane closures in the northbound direction, the beginning of the lane reduction shall be located on a tangent section of the roadway 1.3 km (0.8 mi) south of the bridge, just prior to a curvilinear section.

Reduced speed traffic control shall be used only when welding operations are being performed.

Personal vehicles of the Contractor's employees shall not be parked within the right of way.

Whenever vehicles or equipment are parked on the shoulder within 1.8 m of a traffic lane, the shoulder area shall be closed as shown on the plans.

Lanes shall be closed only during the hours shown on the charts included in this section "Maintaining Traffic." Except work required under Sections 7-1.08 and 7-1.09, work that interferes with public traffic shall be performed only during the hours shown for lane closures.

Designated legal holidays are: January 1st, the third Monday in February, the last Monday in May, July 4th, the first Monday in September, November 11th, Thanksgiving Day and the following Friday, and December 24th and 25th. When a designated legal holiday falls on a Sunday, the following Monday shall be a designated legal holiday. When a designated legal holiday falls on a Saturday, Sunday or Monday, the entire weekend (Saturday and Sunday) shall be considered legal holidays. When November 11th falls on a Saturday, the preceding Friday shall be a designated legal holiday.

Minor deviations from the requirements of this section concerning hours of work which do not significantly change the cost of the work may be permitted upon the written request of the Contractor, if in the opinion of the Engineer, public traffic will be better served and the work expedited. These deviations shall not be adopted by the Contractor until the Engineer has approved the deviations in writing. All other modifications will be made by contract change order.

Chart No. 1 Multilane Lane Requirements																								
Location: Sha-5-KP R46.3/R47.2																								
	a.m. p.m.																							
FROM HOUR TO HOUR	12	1	2	3	4	5	6	7	8	9 1	10 1	1 1	2	1	2 :	3 4	4 5	5 (5 7	7 8	3 9	1	0 1	1 12
Mondays through Thursdays	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Fridays	1	1	1	1	1	1	1	1	1	1											1	1	1	1
Saturdays	1	1	1	1	1	1															1	1	1	1
Sundays	1	1	1	1	1	1															1	1	1	1
Day before designated legal holiday	1	1	1	1	1	1	1	1	1	1														
Designated legal holidays																								
Legend: 1 One lane, not less than 3.7 m wide including a contiguous 0.6 m wide paved shoulder, open in direction of travel																								
No lane closure allowed																								
REMARKS: When construction operations are not actively in progress, the full width of the traveled way and adjacent shoulders shall be open to public traffic.																								

10-1.09 CLOSURE REQUIREMENTS AND CONDITIONS

Lane closures shall conform to the provisions in "Maintaining Traffic" of these special provisions and these special provisions.

The term closure, as used herein, is defined as the closure of a traffic lane or lanes, including ramp or connector lanes, within a single traffic control system.

CLOSURE SCHEDULE

By noon Monday, the Contractor shall submit a written schedule of planned closures for the following week period, defined as Friday noon through the following Friday noon.

The Closure Schedule shall show the locations and times when the proposed closures are to be in effect. The Contractor shall use the Closure Schedule request forms furnished by the Engineer. Closure Schedules submitted to the Engineer with incomplete, unintelligible or inaccurate information will be returned for correction and resubmittal. The Contractor will be notified of disapproved closures or closures that require coordination with other parties as a condition of approval.

CONTINGENCY PLAN

The Contractor shall prepare a contingency plan for reopening closures to public traffic. The Contractor shall submit the contingency plan for a given operation to the Engineer within one working day of the Engineer's request.

LATE REOPENING OF CLOSURES

If a closure is not reopened to public traffic by the specified time, work shall be suspended in conformance with the provisions in Section 8-1.05, "Temporary Suspension of Work," of the Standard Specifications. The Contractor shall not make any further closures until the Engineer has accepted a work plan, submitted by the Contractor, that will insure that future closures will be reopened to public traffic at the specified time. The Engineer will have 2 working days to accept or reject the Contractor's proposed work plan. The Contractor will not be entitled to any compensation for the suspension of work resulting from the late reopening of closures.

COMPENSATION

The Contractor shall notify the Engineer of any delay in the Contractor's operations due to the following conditions, and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of those conditions, and the Contractor's loss due to that delay could not have been avoided by rescheduling the affected closure or by judicious handling of forces, equipment and plant, the delay will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09:

- A. The Contractor's proposed Closure Schedule is denied and his planned closures are within the time frame allowed for closures in "Maintaining Traffic" of these special provisions, except that the Contractor will not be entitled to any compensation for amendments to the Closure Schedule that are not approved.
- B. The Contractor is denied a confirmed closure.

Should the Engineer direct the Contractor to remove a closure prior to the time designated in the approved Closure Schedule, any delay to the Contractor's schedule due to removal of the closure will be considered a right of way delay within the meaning of Section 8-1.09, "Right of Way Delays," and compensation for the delay will be determined in conformance with the provisions in Section 8-1.09.

10-1.10 CONSTRUCTION ZONE ENHANCED ENFORCEMENT

Construction zone enhanced enforcement will be provided by the State as directed by the Engineer and in conformance with these special provisions. Construction zone enhanced enforcement shall consist of the presence of the California Highway Patrol (CHP) within and near the limits of construction during specified stages of work to control the movement of public traffic within the work zone. A total of 1800 hours of California Highway Patrol support is available.

Construction zone enhanced enforcement will be required during the performance of the following stages of work:

1. Reduced speed traffic control.

In addition to stages of work requiring CHP presence, the Engineer will provide additional CHP support as deemed appropriate by the Engineer.

The Contractor shall submit a schedule to the Engineer at least 15 days prior to the performance of work requiring construction zone enhanced enforcement. The schedule shall include all activities requiring construction zone enhanced enforcement and the estimated hours of CHP support required for each activity. The work shall be performed within the number of hours allocated for CHP support.

The Contractor may request additional CHP support for other times and in support of other work activities. The Contractor shall bear the costs and expenses for additional CHP support. The CHP shall be compensated at an agreed rate of \$65.00 per hour per CHP Officer. The agreed rate shall be considered full compensation for each hour, or portion thereof, that a CHP Officer is performing construction area enhanced enforcement. There will be no markup applied to any expenses connected with CHP support. The costs and expenses for requested additional CHP support will be deducted from moneys due to the Contractor.

The Engineer shall make all arrangements with the CHP for scheduled and requested additional construction zone enhanced enforcement.

CHP support shall be scheduled in compliance with the provisions in "Closure Requirements and Conditions" of these special provisions. The Contractor will be notified in writing of assigned CHP support when the Contractor is informed of the approval of requested closures.

Cancellations to previously approved closures scheduled to include construction zone enhancement enforcement shall be submitted in writing to the Engineer at least 36 hours prior to the time when the closure is to be in place. Written notices of cancellation for a closure shall be delivered to the Engineer between the hours of 7:00 a.m. and 3:00 p.m., Monday through Friday, excluding designated legal holidays.

Cancellations with less than the 36-hour written notice may result in charges from the CHP. The Contractor shall bear any costs and expenses resulting from cancellations with less than the 36 hour written notice, except cancellations due to weather or circumstances beyond the control of the Contractor, as determined by the Engineer. The CHP shall be compensated not less than \$50.00 per hour and no greater than 4 hours of overtime pay per CHP Officer scheduled to participate in the construction zone enhancement enforcement that is cancelled. The costs and expenses incurred for late cancellations will be deducted from moneys due or that may become due the Contractor.

The presence of the California Highway Patrol will not relieve the Contractor of responsibility of providing for the safety of the public in conformance with the requirements in Section 7-1.09, "Public Safety," nor relieve the Contractor from the responsibility for damage in conformance with the requirements in Section 7-1.12, "Responsibility for Damage," of the Standard Specifications.

10-1.11 TRAFFIC CONTROL SYSTEM FOR LANE CLOSURE

A traffic control system shall consist of closing traffic lanes in conformance with the details shown on the plans, the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, the provisions under "Maintaining Traffic" and "Construction Area Signs" of these special provisions, and these special provisions.

The provisions in this section will not relieve the Contractor from the responsibility to provide additional devices or take measures as may be necessary to comply with the provisions in Section 7-1.09, "Public Safety," of the Standard Specifications.

Each vehicle used to place, maintain and remove components of a traffic control system on multilane highways shall be equipped with a Type II flashing arrow sign which shall be in operation when the vehicle is being used for placing, maintaining or removing components. Vehicles equipped with Type II flashing arrow sign not involved in placing, maintaining or removing components when operated within a stationary lane closure shall only display the caution display mode. The sign shall be controllable by the operator of the vehicle while the vehicle is in motion. The flashing arrow sign shown on the plans shall not be used on vehicles which are being used to place, maintain and remove components of a traffic control system and shall be in place before a lane closure requiring its use is completed.

If components in the traffic control system are displaced or cease to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair the components to the original condition or replace the components and shall restore the components to the original location.

When lane closures are made for work periods only, at the end of each work period, components of the traffic control system, except portable delineators placed along open trenches or excavation adjacent to the traveled way, shall be removed from the traveled way and shoulder. If the Contractor so elects, the components may be stored at selected central locations designated by the Engineer within the limits of the highway right of way.

The contract lump sum price paid for traffic control system shall include full compensation for furnishing all labor, materials (including signs), tools, equipment, and incidentals, and for doing all the work involved in placing, removing, storing, maintaining, moving to new locations, replacing, and disposing of the components of the traffic control system shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer. The adjustment provisions in Section 4-1.03, "Changes," of the Standard Specifications shall not apply to the item of traffic control system. Adjustments in compensation for traffic control system will be made only for increased or decreased traffic control system required by changes ordered by the Engineer and will be made on the basis of the cost of the increased or decreased traffic control necessary. The adjustment will be made on a force account basis as provided in Section 9-1.03, "Force Account Payment," of the Standard Specifications for increased work and estimated on the same basis in the case of decreased work.

Traffic control system required by work which is classed as extra work, as provided in Section 4-1.03D of the Standard Specifications, will be paid for as a part of the extra work.

10-1.12 PORTABLE CHANGEABLE MESSAGE SIGN

One portable changeable message sign shall be furnished, placed, operated, and maintained for each stationary lane closure, placed in advance of the first advance warning sign where designated by the Engineer in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Two portable changeable message signs shall be furnished, placed, operated, and maintained in each direction of travel for the reduced speed traffic control system at those locations shown on the plans or where designated by the Engineer in conformance with the provisions in Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Portable changeable message signs will be paid for on a lump sum basis.

The contract lump sum price paid for portable changeable message sign shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnishing, placing, operating, maintaining, repairing, replacing, transporting from location to location, and removing the portable changeable message signs, complete in place, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.13 TEMPORARY CRASH CUSHION MODULE

This work shall consist of furnishing, installing, and maintaining sand filled temporary crash cushion modules in groupings or arrays at each location shown on the plans, as specified in these special provisions or where designated by the Engineer. The grouping or array of sand filled modules shall form a complete sand filled temporary crash cushion in conformance with the details shown on the plans and these special provisions.

Attention is directed to "Public Safety" and of these special provisions.

Whenever the work or the Contractor's operations establishes a fixed obstacle, the exposed fixed obstacle shall be protected with a sand filled temporary crash cushion. The sand filled temporary crash cushion shall be in place prior to opening the lanes adjacent to the fixed obstacle to public traffic.

Sand filled temporary crash cushions shall be maintained in place at each location, including times when work is not actively in progress. Sand filled temporary crash cushions may be removed during a work period for access to the work provided that the exposed fixed obstacle is 4.6 m or more from a lane carrying public traffic and the temporary crash cushion is reset to protect the obstacle prior to the end of the work period in which the fixed obstacle was exposed. When no longer required, as determined by the Engineer, sand filled temporary crash cushions shall be removed from the site of the work.

At the Contractor's option, the modules for use in sand filled temporary crash cushions shall be either Energite III Inertial Modules, Fitch Inertial Modules or TrafFix Sand Barrels manufactured after March 31, 1997, or equal:

- A. Energite III and Fitch Inertial Modules, manufactured by Energy Absorption Systems, Inc., One East Wacker Drive, Chicago, IL 60601-2076. Telephone 1-312-467-6750, FAX 1-800-770-6755
 - 1. Distributor (North): Traffic Control Service, Inc., 8585 Thys Court, Sacramento, CA 95828. Telephone 1-800-884-8274, FAX 1-916-387-9734
 - Distributor (South): Traffic Control Service, Inc., 1881 Betmor Lane, Anaheim, CA 92805. Telephone 1-800-222-8274, FAX 1-714-937-1070
- B. TrafFix Sand Barrels, manufactured by TrafFix Devices, Inc., 220 Calle Pintoresco, San Clemente, CA 92672. Telephone 1-949 361-5663, FAX 1-949 361-9205
 - 1. Distributor (North): United Rentals, Inc., 1533 Berger Drive, San Jose, CA 95112. Telephone 1-408 287-4303, FAX 1-408 287-1929
 - 2. Distributor (South): Statewide Safety & Sign, Inc., P.O. Box 1440, Pismo Beach, CA 93448. Telephone 1-800-559-7080, FAX 1-805 929-5786

Modules contained in each temporary crash cushion shall be of the same type at each location. The color of the modules shall be the standard yellow color, as furnished by the vendor, with black lids. The modules shall exhibit good workmanship free from structural flaws and objectionable surface defects. The modules need not be new. Good used undamaged modules conforming to color and quality of the types specified herein may be utilized. If used Fitch modules requiring a seal are

furnished, the top edge of the seal shall be securely fastened to the wall of the module by a continuous strip of heavy duty tape.

Modules shall be filled with sand in conformance with the manufacturer's directions, and to the sand capacity in kilograms for each module shown on the plans. Sand for filling the modules shall be clean washed concrete sand of commercial quality. At the time of placing in the modules, the sand shall contain not more than 7 percent water as determined by California Test 226.

Modules damaged due to the Contractor's operations shall be repaired immediately by the Contractor at the Contractor's expense. Modules damaged beyond repair, as determined by the Engineer, due to the Contractor's operations shall be removed and replaced by the Contractor at the Contractor's expense.

Temporary crash cushion modules shall be placed on movable pallets or frames conforming to the dimensions shown on the plans. The pallets or frames shall provide a full bearing base beneath the modules. The modules and supporting pallets or frames shall not be moved by sliding or skidding along the pavement or bridge deck.

A Type R or P marker panel shall be attached to the front of the crash cushion as shown on the plans, when the closest point of the crash cushion array is within 3.6 m of the traveled way. The marker panel, when required, shall be firmly fastened to the crash cushion with commercial quality hardware or by other methods determined by the Engineer.

At the completion of the project, temporary crash cushion modules, sand filling, pallets or frames, and marker panels shall become the property of the Contractor and shall be removed from the site of the work. Temporary crash cushion modules shall not be installed in the permanent work.

Temporary crash cushion modules placed in conformance with the provisions in "Public Safety" of these special provisions will not be measured nor paid for.

10-1.14 EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Highway Facilities," of the Standard Specifications and these special provisions.

Plans of the existing bridges may be requested by fax from the Office of Structure Maintenance and Investigations, 1801 30th Street, Sacramento, CA, Fax (916) 227-8357.

Plans of the existing bridges available to the Contractor are reproductions of the original contract plans with significant changes noted and working drawings and do not necessarily show normal construction tolerances and variances. Where dimensions of new construction required by this contract are dependent on the dimensions of the existing bridges, the Contractor shall verify the controlling field dimensions and shall be responsible for adjusting dimensions of the work to fit existing conditions.

EXISTING PAINT SYSTEMS

The existing paint systems on Bridge Number 06-0021 consist of red lead. Any work that disturbs the existing paint system will expose workers to health hazards and will (1) produce debris containing heavy metal in amounts that exceed the thresholds established in Titles 8 and 22 of the California Code of Regulations or (2) produce toxic fumes when heated. All debris produced when the existing paint system is disturbed shall be contained.

Debris Containment and Collection Program

Prior to starting work, the Contractor shall submit a debris containment and collection program to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, for debris produced when the existing paint system is disturbed. The program shall identify materials, equipment, and methods to be used when the existing paint system is disturbed and shall include working drawings of containment systems, loads applied to the bridge by containment structures, and provisions for ventilation and air movement for visibility and worker safety.

If the measures being taken by the Contractor are inadequate to provide for the containment and collection of debris produced when the existing paint system is disturbed, the Engineer will direct the Contractor to revise the operations and the debris containment and collection program. The directions will be in writing and will specify the items of work for which the Contractor's debris containment and collection program is inadequate. No further work shall be performed on the items until the debris containment and collection program is adequate and, if required, a revised program has been approved for the containment and collection of debris produced when the existing paint system is disturbed.

The Engineer will notify the Contractor of the approval or rejection of the submitted or revised debris containment and collection program within 2 weeks of submittal of the Contractor's program or revised program.

The State will not be liable to the Contractor for failure to approve all or any portion of an originally submitted or revised debris containment and collection program, nor for delays to the work due to the Contractor's failure to submit an acceptable program.

Full compensation for the debris containment and collection program shall be considered as included in the contract price paid for the item of work causing the existing paint system to be disturbed, and no additional compensation will be allowed therefor.

Safety and Health Provisions

Attention is directed to Section 7-1.06, "Safety and Health Provisions," of the Standard Specifications. Work practices and worker health and safety shall conform to the California Code of Regulations, Title 8, Construction Safety Orders, including Section 1532.1, "Lead."

The Contractor shall furnish the Engineer a written Code of Safe Practices and shall implement an Injury and Illness Prevention Program and a Hazard Communication Program in conformance with the requirements of Construction Safety Orders, Sections 1509 and 1510.

Prior to starting work that disturbs the existing paint system, and when revisions to the program are required by Section 1532.1, "Lead," the Contractor shall submit the compliance programs required in subsection (e)(2), "Compliance Program," of Section 1532.1, "Lead," of the Construction Safety Orders to the Engineer in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications. The compliance programs shall include the data specified in subsections (e)(2)(B) and (e)(2)(C) of Section 1532.1, "Lead." Approval of the compliance programs by the Engineer will not be required. The compliance programs shall be reviewed and signed by a Certified Industrial Hygienist (CIH) who is certified in comprehensive practice by the American Board of Industrial Hygiene (ABIH). Copies of all air monitoring or jobsite inspection reports made by or under the direction of the CIH in conformance with Section 1532.1, "Lead," shall be furnished to the Engineer within 10 days after the date of monitoring or inspection.

Full compensation for furnishing the Engineer with the submittals and for implementing the programs required by this safety and health section shall be considered as included in the contract price paid for the item of work causing the existing paint system to be disturbed, and no additional compensation will be allowed therefor.

Debris Handling

Debris produced when the existing paint system is disturbed shall not be temporarily stored on the ground. Debris accumulated inside the containment system shall be removed before the end of each work shift. Debris shall be stored in approved, leakproof containers and shall be handled in such a manner that no spillage will occur.

Disposal of debris produced when the existing paint system is disturbed shall be performed in conformance with all applicable Federal, State, and Local hazardous waste laws. Laws that govern this work include:

- A. Health and Safety Code, Division 20, Chapter 6.5 (California Hazardous Waste Control Act).
- B. Title 22; California Code of Regulations, Division 4.5, (Environmental Health Standards for the Management of Hazardous Waste).
- C. Title 8, California Code of Regulations.

Except as otherwise provided herein, debris produced when the existing paint system is disturbed shall be disposed of by the Contractor at an approved Class 1 disposal facility in conformance with the requirements of the disposal facility operator. The debris shall be hauled by a transporter currently registered with the California Department of Toxic Substances Control using correct manifesting procedures and vehicles displaying current certification of compliance. The Contractor shall make all arrangements with the operator of the disposal facility and perform any testing of the debris required by the operator.

At the option of the Contractor, the debris produced when the existing paint system is disturbed may be disposed of by the Contractor at a facility equipped to recycle the debris, subject to the following requirements:

- A. Copper slag abrasive blended by the supplier with a calcium silicate compound shall be used for blast cleaning.
- B. The debris produced when the existing paint system is disturbed shall be tested by the Contractor to confirm that the solubility of the heavy metals is below regulatory limits and that the debris may be transported to the recycling facility as a non-hazardous waste.
- C. The Contractor shall make all arrangements with the operator of the recycling facility and perform any testing of the debris produced when the existing paint system is disturbed that is required by the operator.

Full compensation for debris handling and disposal shall be considered as included in the contract price paid for the item of work causing the existing paint system to be disturbed, and no additional compensation will be allowed therefor.

Work Area Monitoring

The Contractor shall perform work area monitoring of the ambient air in and around the work area at the bridge site to verify the effectiveness of the containment system. The work area monitoring shall consist of collecting, analyzing, and reporting air test results and recommending the required corrective action when specified exposure levels are exceeded. The work area monitoring shall be carried out under the direction of a CIH. The samples shall be collected at locations designated by the Engineer.

Air samples shall be collected and analyzed in conformance with National Institute for Occupational Safety and Health (NIOSH) methods. Air samples for lead detection shall be collected and analyzed in conformance with NIOSH Method 7082, with a limit of detection of at least $0.5\,\mu\text{g/m}^3$. Air samples for detection of other metals shall be collected and analyzed in conformance with NIOSH Method 7300, with a limit of detection of at least one percent of the appropriate Permissible Exposure Limits (PELs) specified by the California/Occupational Safety and Health Administration (Cal/OSHA). Alternative methods of sample collection and analysis, with equivalent limits of detection, may be used at the option of the Contractor.

The airborne metals exposure, outside either the containment system or work areas, shall not exceed the lower of either:

- (1) 10 percent of the Action Level specified for lead by Section 1532.1, "Lead," of the Construction Safety Orders, or
- (2) 10 percent of the appropriate PELs specified for other metals by Cal/OSHA.

The air samples shall be collected at least once per week during progress of work that disturbs the existing paint system. All air samples shall be analyzed within 48 hours at a facility accredited by the Environmental Lead Laboratory Accreditation Program of the American Industrial Hygiene Association (AIHA). When corrective action is recommended by the CIH, additional samples may be required by the Engineer to be taken, at the Contractor's expense.

Air sample laboratory analysis results, including results of additional samples taken after corrective action as recommended by the CIH, shall be submitted to the Engineer. The results shall be submitted both verbally within 48 hours after sampling and in writing with a copy to the Contractor, within 5 days after sampling. Sample analysis reports shall be prepared by the CIH as follows:

- A. Forair sample laboratory analysis results, the date and location of sample collection, sample number, contract number, bridge number, full name of the structure as shown on the contract plans, and District-County-Route-Kilometer Post will be required.
- B. For air sample laboratory analysis results, the following will be required:
 - 1. List of emission control measures in place when air samples were taken.
 - 2. Air sample results shall be compared to the appropriate PELs.
 - 3. Chain of custody forms.
 - 4. Corrective action recommended by the CIH to ensure airborne metals exposure, outside either the containment system or work areas, is within specified limits.

Work area monitoring will be paid for on the basis of a lump sum price.

The contract lump sum price paid for work area monitoring shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in collecting and analyzing samples of ambient air for heavy metals, complete in place, including reporting the test results, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Containment System

At the option of the Contractor, the containment system shall consist of either (1) a ventilated containment structure, (2) vacuum shrouded surface preparation equipment and drapes, tarps, or other materials, or (3) an equivalent containment system. The containment system shall contain all water, resulting debris, and visible dust produced when the existing paint system is disturbed.

Falsework or supports for the ventilated containment structure shall not extend below the vertical clearance level nor to the ground line at locations within the roadbed.

The containment system shall provide the minimum clearances as required under "Relations with Railroad Company" of these special provisions for the passage of railroad traffic.

The ventilated containment structure shall conform to the provisions for falsework in Section 51-1.06, "Falsework," of the Standard Specifications.

The minimum total design load of the ventilated containment structure shall consist of the sum of the dead and live vertical loads. Dead load shall consist of the actual load of the ventilated containment structure. Live loads shall consist of a uniform load of not less than 2160 Pa, which includes 960 Pa of sand load, applied over the area supported, and in addition, a moving 4.5 kN concentrated load shall be applied to produce maximum stress in the main supporting elements. Assumed horizontal loads need not be included in the design of the ventilated containment structure.

The ventilated containment structure shall be supported with either rigid or flexible supports. The rigid or flexible containment materials on the containment structure shall retain airborne particles but may allow airflow through the containment materials. Flexible materials shall be supported and fastened to prevent escape of abrasive and blast materials due to whipping from traffic or wind and to maintain clearances.

All mating joints between the ventilated containment structure and the bridge shall be sealed. Sealing may be by overlapping of seams when using flexible materials or by using tape, caulking, or other sealing measures.

Multiple flap overlapping door tarps shall be used at entry ways to the ventilated containment structure to prevent dust or debris from escaping.

Baffles, louvers, flapper seals, or ducts shall be used at make-up air entry points to the ventilated containment structure to prevent escape of abrasives and resulting surface preparation debris.

The ventilated containment structure shall be properly maintained while work is in progress and shall not be changed from the approved working drawings without prior approval of the Engineer.

The ventilation system in the ventilated containment structure shall be of the forced input airflow type with fans or blowers.

Negative air pressure shall be employed within the ventilated containment structure and will be verified by visual methods by observing the concave nature of the containment materials while taking into account wind effects or by using smoke or other visible means to observe airflow. The input airflow shall be properly balanced with the exhaust capacity throughout the range of operations.

The exhaust airflow of the ventilation system in the ventilated containment structure shall be forced into dust collectors (wet or dry) or bag houses.

Full compensation for the containment system shall be considered as included in the contract price paid for the item of work causing the existing paint system to be disturbed, and no additional compensation will be allowed therefor.

Protective Work Clothing and Hygiene Facilities

Wherever there is exposure or possible exposure to heavy metals or silica dust at the bridge site, the Contractor shall, for State personnel: (1) furnish, clean, and replace protective work clothing and (2) provide access to hygiene facilities. The furnishing, cleaning, and replacement of protective work clothing and providing access to hygiene facilities shall conform to the provisions of subsections (g), "Protective work clothing and equipment," and (i), "Hygiene facilities and practices," of Section 1532.1, "Lead," of the Construction Safety Orders, and will be required for no more than 3 people.

The protective work clothing and access to hygiene facilities shall be provided during exposure or possible exposure to heavy metals or silica dust at the bridge site and during the application of the undercoats of paint.

Protective work clothing and hygiene facilities shall be inspected and approved by the Engineer before being used by State personnel.

The protective work clothing shall remain the property of the Contractor at the completion of the contract.

Full compensation for protective work clothing and access to hygiene facilities for State personnel shall be considered as included in the contract price paid for the item of work causing the existing paint system to be disturbed, and no additional compensation will be allowed therefor.

BRIDGE REMOVAL

Removing portions of bridges shall conform to the provisions in Section 15-4, "Bridge Removal," of the Standard Specifications and these special provisions.

Bridge removal (portion) shall consist of removing threaded studs with heavy hex nuts.

All removed materials that are not to be salvaged or used in the reconstruction shall become the property of the Contractor and shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

The following additional requirements apply to the removal of portions of bridges whenever the removal work is to be performed over railroad property:

- A. A protective cover supported by falsework or members of the existing structure shall be constructed before beginning bridge removal work.
- B. The protective cover shall prevent any materials, equipment, or debris from falling onto railroad property. The protective cover shall have a minimum strength equivalent to that provided by good, sound Douglas fir planking having a nominal thickness of 50 mm.
- C. The protective cover shall conform to the provisions for falsework in Section 51-1.06, "Falsework," of the Standard Specifications. At least 9 weeks before starting the work, the Contractor shall submit to the Engineer complete details and working drawings of the methods and equipment he proposes to use in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.
- D. The Contractor shall be responsible for designing and constructing a safe and adequate protective cover, and shoring and falsework needed to support the protective cover, all with sufficient strength and rigidity to support the entire load to be imposed.
- E. Bridge removal methods shall be described in the working drawings and calculations in sufficient detail to substantiate live loads used in the protective cover design. Dead and live load values assumed for designing the protective cover shall be shown on the working drawings.

- F. Before removal, the protective cover shall be cleaned of all debris and fine material.
- G . The protective cover shall provide the minimum clearances as required under "Relations with Railroad Company" of these special provisions for the passage of railroad traffic.
- H. The construction of the protective cover as specified herein shall not relieve the Contractor of responsibilities specified in Section 7-1.12A, "Indemnification," and Section 7-1.12B, "Insurance," of the Standard Specifications.

REPLACE STEEL PEDESTAL

Replace steel pedestal shall consist of temporarily supporting the structure, removing existing steel pedestals, placing new steel pedestals and lowering the structure in accordance with the details shown on the plans and these special provisions.

General

Temporary supports for the existing structure during replacement of steel pedestals shall be designed, furnished, constructed, monitored, maintained and removed in accordance with the requirements of these special provisions.

The Contractor shall be responsible for the temporary methods and equipment used to jack and support the existing structure for replacement of pedestals. The Contractor shall be responsible for the design of the temporary supports.

At least 9 weeks before starting the work, the Contractor shall submit to the Engineer complete details and working drawings of the methods and equipment he proposes to use in accordance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications.

For temporary supports over railroads, approval by the Engineer of the temporary support drawings will be contingent upon the drawings being satisfactory to the railroad company involved.

Jacking assemblies and temporary supports shall be designed and constructed in conformance with the provisions in "Falsework," of these special provisions.

The maximum loading and deflections used on jacks, brackets, columns and other manufactured devices shall not exceed the manufacturer's recommendations. If requested by the Engineer, the Contractor shall furnish engineering data from the manufacturer verifying the manufacturer's recommendations or shall perform tests as necessary to demonstrate the adequacy of any such device proposed for use. Adequate means shall be employed to prevent unplanned lateral and longitudinal movement of the superstructure. The temporary supports, jacks, and the superstructure shall be stable during all phases of the operation.

Temporary supports and jacking assemblies shall remain in place as required to support the structure until the new pedestals have been completed.

Additions or modifications to the structure, in connection with jacking, and the jacking assemblies shall be subject to approval of the Engineer.

Jacking operations shall be carried out in a uniform manner so that no distortion that would cause excessive stress or damage will be jacked into the superstructure. Jacking shall be limited to the minimum necessary to construct the new pedestals, in no case more than 13 mm above the final grade. The bridge deck surface between stringers shall not vary more than 4 mm horizontally from the existing adjacent deck surfaces.

Attachments shall be removed from the existing structure and concrete surfaces restored to original conditions, except where permanent alterations are shown on the plans.

Removal shall conform to the requirements of "Bridge Removal" of these special provisions.

Steel pedestals shall conform to the requirements of "Steel Structures" of these special provisions.

All removed materials that are not to be salvaged or used in the reconstruction shall become the property of the Contractor and shall be disposed of outside the highway right of way in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

Measurement and Payment

Replacing the pedestal will be measured by the unit determined by the actual count of pedestals installed.

The contract unit price paid for replace steel pedestal shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in jacking and temporarily supporting the existing structure, removing existing steel pedestals, furnishing and placing steel pedestals, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Clean and paint structural steel and spot blast clean and paint undercoat will be paid for as separate contract items in these special provisions.

10-1.15 FALSEWORK

Falsework shall conform to the provisions in Section 51, "Concrete Structures," of the Standard Specifications and these special provisions.

Attention is directed to "Railroad Relations and Insurance" of these special provisions for temporary clearing for falsework over railroads.

The first and second paragraph in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications are amended to read:

- The Contractor shall submit to the Engineer working drawings and design calculations for falsework proposed for use at bridges. For bridges where the height of any portion of the falsework, as measured from the ground line to the soffit of the superstructure, exceeds 4.25 m; or where any individual falsework clear span length exceeds 4.85 m; or where provision for vehicular, pedestrian, or railroad traffic through the falsework is made; the drawings shall be signed by an engineer who is registered as a Civil Engineer in the State of California. Six sets of the working drawings and 2 copies of the design calculations shall be furnished. Additional working drawings and design calculations shall be submitted to the Engineer when specified in "Railroad Relations and Insurance" of the special provisions.
- The falsework drawings shall include details of the falsework erection and removal operations showing the methods and sequences of erection and removal and the equipment to be used. The details of the falsework erection and removal operations shall demonstrate the stability of all or any portions of the falsework during all stages of the erection and removal operations.

The seventh paragraph in Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended to read:

• In the event that several falsework plans are submitted simultaneously, or an additional plan is submitted for review before the review of a previously submitted plan has been completed, the Contractor shall designate the sequence in which the plans are to be reviewed. In such event, the time to be provided for the review of any plan in the sequence shall be not less than the review time specified above for that plan, plus 2 weeks for each plan of higher priority which is still under review. A falsework plan submittal shall consist of plans for a single bridge or portion thereof. For multi-frame bridges, each frame shall require a separate falsework plan submittal.

Section 51-1.06A, "Falsework Design and Drawings," of the Standard Specifications is amended by adding the following paragraphs:

- If structural composite lumber is proposed for use, the falsework drawings shall clearly identify the structural composite lumber members by grade (E value), species, and type. The Contractor shall provide technical data from the manufacturer showing the tabulated working stress values of the composite lumber. The Contractor shall furnish a certificate of compliance as specified in Section 6-1.07, "Certificates of Compliance," for each delivery of structural composite lumber to the project site.
- For falsework piles with a calculated loading capacity greater than 900 kN, the falsework piles shall be designed by an engineer who is registered as either a Civil Engineer or a Geotechnical Engineer in the State of California, and the calculations shall be submitted to the Engineer.

The first paragraph in Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

• The design load for falsework shall consist of the sum of dead and live vertical loads, and an assumed horizontal load. The minimum total design load for any falsework, including members that support walkways, shall be not less than 4800 N/m² for the combined live and dead load regardless of slab thickness.

The eighth paragraph in Section 51-1.06A(1), "Design Loads," of the Standard Specifications is amended to read:

• In addition to the minimum requirements specified in this Section 51-1.06A, falsework for box girder structures with internal falsework bracing systems using flexible members capable of withstanding tensile forces only, shall be designed to include the vertical effects caused by the elongation of the flexible member and the design horizontal load combined with the dead and live loads imposed by concrete placement for the girder stems and connected bottom slabs. Falsework comprised of individual steel towers with bracing systems using flexible members capable of withstanding tensile forces only to resist overturning, shall be exempt from these additional requirements.

The third paragraph in Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended to read:

• When falsework is supported on piles, the piles shall be driven and the actual bearing value assessed in conformance with the provisions in Section 49, "Piling."

Section 51-1.06B, "Falsework Construction," of the Standard Specifications is amended by adding the following paragraphs:

- For falsework piles with a calculated loading capacity greater than 900 kN, the Contractor shall conduct dynamic monitoring of pile driving and conduct penetration and bearing analyses based on a wave equation analysis. These analyses shall be signed by an engineer who is registered as a Civil Engineer in the State of California and submitted to the Engineer prior to completion of falsework erection.
- Prior to the placement of falsework members above the stringers, the final bracing system for the falsework shall be installed.

Section 51-1.06C, "Removing Falsework," of the Standard Specifications is amended by adding the following paragraph:

• The falsework removal operation shall be conducted in such a manner that any portion of the falsework not yet removed remains in a stable condition at all times.

Welding and Nondestructive Testing

Welding of steel members, except for when fillet welds are used where load demands are less than or equal to 175 N/mm for each 3 mm of fillet weld, shall conform to AWS D1.1 or other recognized welding standard. The welding standard to be utilized shall be specified by the Contractor on the working drawings.

Splices made by field welding of steel beams at the project site shall undergo nondestructive testing (NDT). At the option of the Contractor, either ultrasonic testing (UT) or radiographic testing (RT) shall be used as the method of NDT for each field weld and any repair made to a previously welded splice in a steel beam. Testing shall be performed at locations selected by the Contractor. The length of a splice weld where NDT is to be performed, shall be a cumulative weld length equal to 25 percent of the original splice weld length. The cover pass shall be ground smooth at the locations to be tested. The acceptance criteria shall conform to the requirements of AWS D1.1, Section 6, for cyclically loaded nontubular connections subject to tensile stress. If repairs are required in a portion of the weld, additional NDT shall be performed on the repaired sections. The NDT method chosen shall be used for an entire splice evaluation including any required repairs.

For all field welded splices and previously welded splices, the Contractor shall furnish to the Engineer a letter of certification which certifies that all welding and NDT, including visual inspection, are in conformance with the specifications and the welding standard shown on the approved working drawings. The letter of certification shall be signed by an engineer who is registered as a Civil Engineer in the State of California and shall be provided prior to placing any concrete for which the falsework is being erected to support.

10-1.16 EPOXY CRACK INJECTION

Certain cracks in the existing concrete structure shall be prepared and filled with epoxy by pressure injection in conformance with the details shown on the plans and these special provisions.

The cracks to be so prepared and filled shall be only those designated by the Engineer and will not include any cracks which are less than 0.2-mm wide.

MATERIALS

The epoxy adhesive to be used for injecting into cracks in concrete shall be furnished in conformance with the provisions in Sections 95-1, "General," and 95-2.11, "Epoxy Resin Adhesive for Injection Grouting of Portland Cement Concrete Pavements (State Specification 8040-01F-02)," of the Standard Specifications and these special provisions.

Where cracks of varying widths are to be filled, it may be necessary to use more than one epoxy formulation on the project.

PREPARATION

Cracks to be filled shall be cleaned free of dust, silt, and any other material that would impair bond of epoxy to concrete. Cleaning shall be done with compressed air jets except that when such jets will not remove material from the cracks, the cracks shall be flushed with water under pressure. When flushing water is used, the water shall be blown out of the cracks with oil-free compressed air before epoxy is injected.

Suitable injection ports shall be inserted in the cracks at intervals not less than the thickness of the concrete being injected. At the end of a crack, the first port shall be about half this distance from the end. The spacing of the ports shall be adjusted so that the epoxy substantially fills the cracks.

The surface of crack between ports shall be sealed with tape or other temporary surface sealant which is capable of retaining the epoxy adhesive in the crack during pressure injection and until the epoxy has hardened.

INJECTION

Epoxy adhesive shall be pumped into the cracks through the injection ports. The pump, hose, injection gun and appurtenances shall properly proportion and mix the epoxy and shall be capable of injecting the epoxy at a sufficient rate and pressure to completely fill all designated cracks. A suitable gasket shall be used on the head of the injection gun to prevent the adhesive from running down the face of the concrete. Pumping pressure shall be kept as low as practicable.

The temperature of the concrete shall be not less than 10°C or greater than 32°C at the time epoxy is injected.

Before starting injection work and at hourly intervals during injection work when requested by the Engineer, a 90 ml sample of mixed epoxy shall be taken from the injection gun. Should these samples show any evidence of improper proportioning or mixing, injection work shall be suspended until the equipment or procedures are corrected.

The epoxy adhesive shall be forced into the first port at one end of a crack until adhesive runs in substantial quantity from the next adjacent port. The first port shall then be sealed and injection started at the next port. Injection shall then continue from port to port in this manner until the crack is fully injected. For slanting or vertical cracks, pumping shall start at the lower end of the crack. Where approximately vertical and horizontal cracks intersect, the vertical crack below the intersection shall be injected first. The ports shall be sealed by removing the fitting, filling the void with epoxy and covering with tape or surface sealant.

Sealing tape and temporary surface sealant shall remain in place until the epoxy has hardened.

On faces of concrete exposed to public view, sealant tape and other temporary surface sealant shall be removed when no longer required and any spillage of epoxy shall also be removed. No cleanup of surfaces not visible to the public will be required.

MEASUREMENT AND PAYMENT

The basis of payment for inject crack (epoxy) shall be a total of the lengths of the cracks which are designated by the Engineer to be injected and which have been filled with epoxy.

Where cracks are designated for injection on opposite sides of a concrete member and the epoxy adhesive injected on one side penetrates through the members to completely fill the crack on the opposite side, payment will be made for cracks on both sides, as though injection has been performed on both sides, except that no payment will be made for such cracks on the opposite side that were not designated by the Engineer for injection.

Where a crack designated for injection extends around a corner of a concrete member, the length of crack on both faces will be measured for payment.

The contract price paid per meter for inject crack (epoxy) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in preparing and injecting the cracks in existing concrete, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

10-1.17 STEEL STRUCTURES

Construction of steel structures shall conform to the provisions in Section 55, "Steel Structures," of the Standard Specifications and these special provisions.

GENERAL

Structural steel (bridge) shall consist of studs, nuts and washer for repairing steel pedestal Type B.

Attention is directed to "Welding" in Section 8, "Materials," of these special provisions.

The following substitutions of high-strength steel fasteners shall be made:

METRIC SIZE SHOWN ON THE PLANS	IMPERIAL SIZE TO BE SUBSTITUTED
ASTM Designation: A 325M (Nominal bolt diameter and thread pitch (mm))	ASTM Designation: A 325 (Nominal bolt diameter (inch))
M16 x 2	5/8
M20 x 2.5	3/4
M22 x 2.5	7/8
M24 x 3	1
M27 x 3	1 1/8
M30 x 3.5	1 1/4
M36 x 4	1 1/2

MATERIALS

High-strength fastener assemblies, and other bolts attached to structural steel with nuts and washers shall be zinc-coated. When direct tension indicators are used in these assemblies, the direct tension indicator and all components of the fastener assembly shall be zinc-coated by the mechanical deposition process.

BOLTED CONNECTIONS

Section 55-3.14, "Bolted Connections," of the Standard Specifications is amended by adding the following after the ninth paragraph:

• If a torque multiplier is used in conjunction with a calibrated wrench as a method for tightening fastener assemblies to the required tension, both the multiplier and the wrench shall be calibrated together as a system. The same length input and output sockets and extensions that will be used in the work shall also be included in the calibration of the system. The manufacturer's torque multiplication ratio shall be adjusted during calibration of the system, such that when this adjusted ratio is multiplied by the actual input calibrated wrench reading, the product is a calculated output torque that is within 2 percent of the true output torque. When this system is used in the work to perform any installation tension testing, rotational capacity testing, fastener tightening, or tension verification, it shall be used, intact as calibrated.

ROTATIONAL CAPACITY TESTING PRIOR TO SHIPMENT TO JOB SITE

Rotational capacity tests shall be performed on all lots of high-strength fastener assemblies prior to shipment of these lots to the project site. Zinc-coated assemblies shall be tested after all fabrication, coating, and lubrication of components has been completed. One hardened washer shall be used under each nut for the tests.

Each combination of bolt production lot, nut lot and washer lot shall be tested as an assembly.

A rotational capacity lot number shall be assigned to each combination of lots tested. Each shipping unit of fastener assemblies shall be plainly marked with the rotational capacity lot number.

Two fastener assemblies from each rotational capacity lot shall be tested.

The following equipment, procedure, and acceptance criteria shall be used to perform rotational capacity tests on, and determine acceptance of long bolts. Fasteners are considered to be long bolts when full nut thread engagement can be achieved when installed in a bolt tension measuring device:

A. Long Bolt Test Equipment:

- 1. Calibrated bolt tension measuring device with adequate tension capacity for the bolts being tested.
- 2. Calibrated dial or digital torque wrench. Other suitable tools will be required for performing Steps 7 and 8 of the Long Bolt Test Procedure. A torque multiplier may be required for large diameter bolts.
- Spacer washers or bushings. When spacer washers or bushings are required, they shall have the same inside
 diameter and equal or larger outside diameter as the appropriate hardened washers conforming to the
 requirements in ASTM Designation: F436.
- 4. Steel beam or member, such as a girder flange or cross frame, to which the bolt tension measuring device will be attached. The device shall be accessible from the ground.

B Long Bolt Test Procedure:

1. Measure the bolt length. The bolt length is defined as the distance from the end of the threaded portion of the shank to the underside of the bolt head.

- 2. Install the nut on the bolt so that 3 to 5 full threads of the bolt are located between the bearing face of the nut and the underside of the bolt head. Measure and record the thread stickout of the bolt. Thread stickout is determined by measuring the distance from the outer face of the nut to the end of the threaded portion of the shank.
- 3. Insert the bolt into the bolt tension measuring device and install the required number of washers, and additional spacers as needed, directly beneath the nut to produce the thread stickout measured in Step 2 of this procedure.
- 4. Tighten the nut using a hand wrench to a snug-tight condition. The snug tension shall not be less than the Table A value but may exceed the Table A value by a maximum of 2 kips.

Table A

14016 71							
High-Strength Fastener Assembly Tension Values							
to Approximate Snug-Tight Condition							
Bolt Diameter	Snug Tension						
(inches)	(kips)						
1/2	1						
5/8	2						
3/4	3						
7/8	4						
1	5						
1 1/8	6						
1 1/4	7						
1 3/8	9						
1 1/2	10						

5. Match-mark the assembly by placing a heavy reference start line on the face plate of the bolt tension measuring device which aligns with 1) a mark placed on one corner of the nut, and 2) a radial line placed across the flat on the end of the bolt, or on the exposed portions of the threads of tension control bolts. Place an additional mark on the outside of the socket that overlays the mark on the nut corner such that this mark will be visible while turning the nut. Make an additional mark on the face plate, either 2/3 of a turn, one turn, or 1 1/3 turn clockwise from the heavy reference start line, depending on the bolt length being tested as shown in Table B.

Table B

Table B							
Required Nut Rotation for Rotational Capacity (a,b) Tests							
Bolt Length (measured in Step 1)	Required Rotation (turn)						
4 bolt diameters or less	2/3						
Greater than 4 bolt	1						
diameters but no more							
than 8 bolt diameters							
Greater than 8 bolt	1 1/3						
diameters, but no more							
than 12 bolt							
diameters (c)							

- (a) Nut rotation is relative to bolt, regardless of the element (nut or bolt) being turned. For bolts installed by 1/2 turn and less, the tolerance shall be plus or minus 30 degrees; for bolts installed by 2/3 turn and more, the tolerance shall be plus or minus 45 degrees.
- (b) Applicable only to connections in which all material within grip of the bolt is steel.
- (c) When bolt length exceeds 12 diameters, the required rotation shall be determined by actual tests in a suitable tension device simulating the actual conditions.
- 6. Turn the nut to achieve the applicable minimum bolt tension value listed in Table C. After reaching this tension, record the moving torque, in foot-pounds, required to turn the nut, and also record the corresponding bolt tension value in pounds. Torque shall be measured with the nut in motion. Calculate the value, T (in ft-lbs), where T=[(the measured tension in pounds) x (the bolt diameter in inches) / 48 in/ft].

Table C

Tuble 6							
Minimum Tension Values for High-Strength							
Fastener Assemblies							
Bolt Diameter	Minimum Tension						
(inches)	(kips)						
1/2	12						
5/8	19						
3/4	28						
7/8	39						
1	51						
1 1/8	56						
1 1/4	71						
1 3/8	85						
1 1/2	103						

- Turn the nut further to increase bolt tension until the rotation listed in Table B is reached. The rotation is
 measured from the heavy reference line made on the face plate after the bolt was snug-tight. Record this bolt
 tension
- 8. Loosen and remove the nut and examine the threads on both the nut and bolt.

C. Long Bolt Acceptance Criteria:

1. An assembly shall pass the following requirements to be acceptable: 1) the measured moving torque (Step 6) shall be less than or equal to the calculated value, T (Step 6), 2) the bolt tension measured in Step 7 shall be greater than or equal to the applicable turn test tension value listed in Table D, 3) the nut shall be able to be removed from the bolt without signs of thread stripping or galling after the required rotation in Step 7 has been achieved, 4) the bolt does not shear from torsion or fail during the test and 5) the assembly does not seize before the final rotation in Step 7 is reached. Elongation of the bolt in the threaded region between the bearing face of the nut and the underside of the bolt head is expected and will not be considered a failure. Both fastener assemblies tested from one rotational capacity lot shall pass for the rotational capacity lot to be acceptable.

Table D

Turn Test Tension Values						
Bolt Diameter	Turn Test Tension					
(inches)	(kips)					
1/2	14					
5/8	22					
3/4	32					
7/8	45					
1	59					
1 1/8	64					
1 1/4	82					
1 3/8	98					
1 1/2	118					

The following equipment, procedure and acceptance criteria shall be used to perform rotational capacity tests on and determine acceptance of short bolts. Fasteners are considered to be short bolts when full nut thread engagement cannot be achieved when installed in a bolt tension measuring device:

A. Short Bolt Test Equipment:

- 1. Calibrated dial or digital torque wrench. Other suitable tools will be required for performing Steps 7 and 8 of the Short Bolt Test Procedure. A torque multiplier may be required for large diameter bolts.
- 2. Spud wrench or equivalent.
- 3. Spacer washers or bushings. When spacer washers or bushings are required, they shall have the same inside diameter and equal or larger outside diameter as the appropriate hardened washers conforming to the requirements in ASTM Designation: F436.
- 4. Steel plate or girder with a hole to install bolt. The hole size shall be 1.6 mm greater than the nominal diameter of the bolt to be tested. The grip length, including any plates, washers, and additional spacers as needed, shall provide the proper number of threads within the grip, as required in Step 2 of the Short Bolt Test Procedure.

B. Short Bolt Test Procedure:

- 1. Measure the bolt length. The bolt length is defined as the distance from the end of the threaded portion of the shank to the underside of the bolt head.
- 2. Install the nut on the bolt so that 3 to 5 full threads of the bolt are located between the bearing face of the nut and the underside of the bolt head. Measure and record the thread stickout of the bolt. Thread stickout is determined by measuring the distance from the outer face of the nut to the end of the threaded portion of the shank.
- 3. Install the bolt into a hole on the plate or girder and install the required number of washers, and additional spacers as needed, between the bearing face of the nut and the underside of the bolt head to produce the thread stickout measured in Step 2 of this procedure.
- 4. Tighten the nut using a hand wrench to a snug-tight condition. The snug condition shall be the full manual effort applied to the end of a 305 mm long wrench. This applied torque shall not exceed 20 percent of the maximum allowable torque in Table E.

Table E

Tuble E						
Maximum Allowable Torque for High-Strength						
Fastener Assemblies						
Bolt Diameter	Torque					
(inches)	(ft-lbs)					
1/2	145					
5/8	285					
3/4	500					
7/8	820					
1	1220					
1 1/8	1500					
1 1/4	2130					
1 3/8	2800					
1 1/2	3700					

- 5. Match-mark the assembly by placing a heavy reference start line on the steel plate or girder which aligns with 1) a mark placed on one corner of the nut, and 2) a radial line placed across the flat on the end of the bolt, or on the exposed portions of the threads of tension control bolts. Place an additional mark on the outside of the socket that overlays the mark on the nut corner such that this mark will be visible while turning the nut. Make 2 additional small marks on the steel plate or girder, one 1/3 of a turn and one 2/3 of a turn clockwise from the heavy reference start line on the steel plate or girder.
- 6. Using the torque wrench, tighten the nut to the rotation value listed in Table F. The rotation is measured from the heavy reference line described in Step 5 made after the bolt was snug-tight. A second wrench shall be used to prevent rotation of the bolt head during tightening. Measure and record the moving torque after this rotation has been reached. The torque shall be measured with the nut in motion.

Table F

Table F						
Nut Rotation Required for Turn-of-Nut (a,b) Installation						
Bolt Length (measured in Step 1)	Required Rotation (turn)					
4 bolt diameters or less 1/3						
(a) Nut rotation is relative to bolt, regardless of the						

- (a) Nut rotation is relative to bolt, regardless of the element (nut or bolt) being turned. For bolts installed by 1/2 turn and less, the tolerance shall be plus or minus 30 degrees.
- (b) Applicable only to connections in which all material within grip of the bolt is steel.
- 7. Tighten the nut further to the 2/3-turn mark as indicated in Table G. The rotation is measured from the heavy reference start line made on the plate or girder when the bolt was snug-tight. Verify that the radial line on the bolt end, or on the exposed portions of the threads of tension control bolts, is still in alignment with the start line.

Table G

Required Nut Rotation for Rotational Capacity Test						
Bolt Length (measured	Required Rotation (turn)					
in Step 1)						
4 bolt diameters or less	2/3					

- 8. Loosen and remove the nut and examine the threads on both the nut and bolt.
- C. Short Bolt Acceptance Criteria:

1. An assembly shall pass the following requirements to be acceptable: 1) the measured moving torque from Step 6 shall be less than or equal to the maximum allowable torque from Table E, 2) the nut shall be able to be removed from the bolt without signs of thread stripping or galling after the required rotation in Step 7 has been achieved, 3) the bolt does not shear from torsion or fail during the test and 4) the assembly shall not seize before the final rotation in Step 7 is reached. Elongation of the bolt in the threaded region between the bearing face of the nut and the underside of the bolt head will not be considered a failure. Both fastener assemblies tested from one rotational capacity lot shall pass for the rotational capacity lot to be acceptable.

INSTALLATION TENSION TESTING AND ROTATIONAL CAPACITY TESTING AFTER ARRIVAL ON THE JOB SITE

Installation tension tests and rotational capacity tests on high-strength fastener assemblies shall be performed by the Contractor prior to acceptance or installation, and after arrival of the fastener assemblies on the project site. Installation tension tests and rotational capacity tests shall be performed at the job-site, in the presence of the Engineer, on each rotational capacity lot of fastener assemblies.

Installation tension tests shall be performed on 3 representative fastener assemblies in conformance with the provisions in Section 8, "Installation and Tightening," of the RCSC Specification. For short bolts, Section 8(d), "Joint Assembly and Tightening of Slip-Critical and Direct Tension Connections," of the RCSC Specification shall be replaced by the "Pre-Installation Testing Procedures," of the "Structural Bolting Handbook," published by the Steel Structures Technology Center, Incorporated.

The rotational capacity tests shall be performed in conformance with the requirements for rotational capacity tests in "Rotational Capacity Testing Prior to Shipment to Job Site" of these special provisions.

At the Contractor's expense, additional installation tension tests, tests required to determine job inspecting torque and rotational capacity tests shall be performed by the Contractor on each rotational capacity lot, in the presence of the Engineer, if 1) any fastener is not used within 3 months after arrival on the jobsite, 2) fasteners are improperly handled, stored, or subjected to inclement weather prior to final tightening, 3) significant changes are noted in original surface condition of threads, washers or nut lubricant or 4) the Contractor's required inspection is not performed within 48 hours after all fasteners in a joint have been tensioned.

Failure of a job-site installation tension test or a rotational capacity test will be cause for rejection of unused fasteners that are part of the rotational capacity lot.

When direct tension indicators are used, installation verification tests shall be performed in conformance with Appendix Section X1.4 of ASTM Designation: F959, except that bolts shall be initially tensioned to a value 5 percent greater than the minimum required bolt tension.

SURFACE PREPARATION

For all bolted connections, the 1) contact surfaces, 2) surfaces of outside existing members within the grip under bolt heads, nuts and washers and 3) inside surfaces of bolt holes shall be cleaned and coated before assembly in conformance with the provisions for cleaning and painting structural steel of these special provisions.

SEALING

The perimeter around all direct tension indicator gaps shall be completely sealed with non-silicone type sealing compound conforming to the provisions in Federal Specification TT-S-230, Type II. The sealant shall be gray in color and have a minimum thickness of 1.3 mm. If painting is required, the sealing compound shall be applied prior to painting.

When zinc-coated tension control bolts are used, the sheared end of each fastener shall be completely sealed with non-silicone type sealing compound conforming to the provisions in Federal Specification TT-S-230, Type II. The sealant shall be gray in color and shall have a minimum thickness of 1.3 mm. The sealant shall be applied to a clean sheared surface on the same day that the splined end is sheared off.

MEASUREMENT AND PAYMENT

The contract price paid per kilogram for structural steel (bridge) shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in furnishing and erecting structural steel, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Additional replacement of studs will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

10-1.18 REPAIR WELD

Repairing welds shall consist of removing existing welds and base metal and welding existing steel surfaces in conformance with the details shown on the plans, and the requirements of "Steel Structures," of these special provisions and these special provisions.

The repairing of welds shall be made at the locations and to the limits shown on the plans.

The Contractor shall notify the Engineer, in writing, a minimum of 5 working days prior to repairing welds.

Blast cleaned surfaces shall be cleaned and painted in accordance with the provisions in "Clean and Paint Structural Steel" of these special provisions.

Weld repair will be measured by the meter along the length of the repaired weld.

The contract price paid per meter for repair weld of the types listed in the Engineer's Estimate shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in repairing welds, complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Clean and paint structural steel and spot blast clean and paint undercoat will be paid for as separate contract items in these special provisions.

Additional weld repair will be paid for as extra work as provided in Section 4-1.03D of the Standard Specifications.

10-1.19 CLEAN AND PAINT STRUCTURAL STEEL

Exposed new metal surfaces and connections to existing steel, except where galvanized, shall be cleaned and painted in conformance with the provisions in Section 59-2, "Painting Structural Steel," and Section 91, "Paint," of the Standard Specifications and these special provisions.

The existing paint systems consist of materials listed in "Existing Highway Facilities" of these special provisions.

Whenever the Standard Specifications refer to "Steel Structures Painting Council," the reference shall be replaced with "SSPC: The Society for Protective Coatings."

Section 59-2.01, "General," of the Standard Specifications is amended by adding the following paragraphs after the first paragraph:

- Unless otherwise specified, no painting Contractors or subcontractors will be permitted to commence work without having the following current "SSPC: The Society for Protective Coatings" (formerly the Steel Structures Painting Council) certifications in good standing:
- A. For cleaning and painting structural steel in the field, certification in conformance with the requirements in Qualification Procedure No. 1, "Standard Procedure For Evaluating Painting Contractors (Field Application to Complex Industrial Structures)" (SSPC-QP 1).
- B. For removing paint from structural steel, certification in conformance with the requirements in Qualification Procedure No. 2, "Standard Procedure For Evaluating Painting Contractors (Field Removal of Hazardous Coatings from Complex Structures)" (SSPC-QP 2).
- C. For cleaning and painting structural steel in a permanent painting facility, certification in conformance with the requirements in Qualification Procedure No. 3, "Standard Procedure For Evaluating Qualifications of Shop Painting Applicators" (SSPC-QP 3). The AISC's Sophisticated Paint Endorsement (SPE) quality program will be considered equivalent to SSPC-OP 3.

Prior to performing any painting or paint removal, the Contractor shall submit to the Engineer, in conformance with the provisions in Section 5-1.02, "Plans and Working Drawings," of the Standard Specifications, 3 copies of a separate Painting Quality Work Plan (PQWP) for each item of work for which painting or paint removal is to be performed. As a minimum, each PQWP shall include the following:

- A. The name of each Contractor or subcontractor to be used.
- B. One copy each of all current "SSPC: The Society for Protective Coatings" specifications or qualification procedures which are applicable to the painting or paint removal to be performed. These documents shall become the permanent property of the Department.
- C. Proposed methods and equipment to be used for any paint application.
- D. Proof of each of any required certifications, SSPC-QP 1, SSPC-QP 2, SSPC-QP 3.
 - In lieu of certification in conformance with the requirements in SSPC-QP 2 for this project, the Contractor may submit written documentation showing conformance with the requirements in Sections 4.2 through 4.6 of SSPC-QP 2.

2. In lieu of certification in conformance with the requirements in SSPC-QP 3 for this project, the Contractor may submit written documentation showing conformance with the requirements in Section 3, " General Qualification Requirements," of SSPC-QP 3.

The Engineer shall have 10 working days to review the PQWP submittal after a complete plan has been received. No painting or paint removal shall be performed until the PQWP for that work is reviewed by the Engineer. Should the Engineer fail to complete the review within this time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the PQWP, the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

It is expressly understood that the Engineer's review of the Contractor's PQWP shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformity with the requirements of the plans and specifications. The Engineer's review shall not constitute a waiver of any of the requirements of the plans and specifications nor relieve the Contractor of any obligation thereunder, and defective work, materials, and equipment may be rejected notwithstanding review of the PQWP.

The existing paint systems consist of materials listed in "Existing Highway Facilities" of these special provisions.

CLEANING

Exposed new metal surfaces and areas of connections to existing steel, except where galvanized, shall be dry blast cleaned and dry spot blast cleaned, respectively, in conformance with the requirements in Surface Preparation Specification No. 10, "Near White Blast Cleaning," of the "SSPC: The Society for Protective Coatings." Blast cleaning shall leave surfaces with a dense, uniform, angular anchor pattern of no less than 40 μ m nor more than 86 μ m as measured in conformance with the requirements in ASTM Designation: D 4417.

The areas of connections to existing steel to be dry spot blast cleaned shall consist of, as a minimum: (1) new and existing contact surfaces and existing member surfaces under bolt heads, nuts or washers of high-strength bolted connections, (2) exposed bare surfaces of existing steel remaining after trimming, cutting, drilling or reaming, and (3) areas of existing steel within a 100-mm radius measured in any direction from the point of application of heat for welding or flame cutting.

Mineral and slag abrasives used for blast cleaning steel shall conform to the requirements in Abrasive Specification No. 1, "Mineral and Slag Abrasives," of the "SSPC: The Society for Protective Coatings" and shall not contain hazardous material. Mineral and slag abrasives shall comply with the requirements for Class A, Grade 2 to 3 as defined therein.

A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications and a Material Safety Data Sheet shall be furnished prior to use for each shipment of blast cleaning material for existing steel.

The inside surfaces of bolt holes shall be cleaned in conformance with the requirements in Surface Preparation Specification No. 1, "Solvent Cleaning," of the "SSPC: The Society for Protective Coatings," and visible rust shall be removed.

PAINTING

Blast cleaned surfaces shall receive a single undercoat consisting of a waterborne inorganic zinc coating conforming to the requirements in AASHTO Designation M 300, Type II, except that: 1) the first 3 sentences of Section 4.7, "Primer Field Performance Requirements," and the entire Section 4.7.1 shall not apply, and 2) zinc dust shall be Type II in conformance with the requirements in ASTM Designation: D 520. The inorganic zinc coating shall be listed on the qualified products list which may be obtained from the Transportation Laboratory.

The inside surfaces of bolt holes shall be painted with one application of a zinc rich primer (organic vehicle type) after the application of the undercoat of inorganic zinc on adjacent steel. The steel surfaces adjacent to the bolt holes shall be kept clean and protected from drippings during the application of the primer.

Inorganic zinc coating shall be used within 12 hours of initial mixing.

Application of inorganic zinc coating shall conform to provisions for applying zinc-rich coating in Section 59-2.13, "Application of Zinc-Rich Primer," of the Standard Specifications.

Inorganic zinc coating shall not be applied when the atmospheric or surface temperature is less than 7°C nor more than 29°C, nor when the relative humidity exceeds 85 percent.

The single undercoat of inorganic zinc coating shall be applied to the required dry film thickness in 2 or more applications within 4 hours after blast cleaning.

The total dry film thickness of all applications of the inorganic zinc undercoat, including the surfaces of outside existing members within the grip under bolt heads, nuts and washers, shall be not less than $100 \, \mu m$ nor more than $200 \, \mu m$, except that the total dry film thickness on each faying (contact) surface of high strength bolted connections shall be between $25 \, \mu m$ and the maximum allowable dry film thickness for Class B coatings as determined by certified testing in conformance with Appendix A of the "Specification for Structural Joints Using ASTM A325 or A490 Bolts" of the Research Council on Structural Connections (RCSC Specification). Unless otherwise stated, all inorganic zinc coatings used on faying surfaces

shall meet the slip coefficient requirements for a Class B coating on blast-cleaned steel, as specified in the RCSC Specification. The Contractor shall provide results of certified testing showing the maximum allowable dry film thickness for the Class B coating from the qualifying tests for the coating he has chosen, and shall maintain the coating thickness on actual faying surfaces of the structure at or below this maximum allowable coating thickness.

Areas where mudcracking occurs in the inorganic zinc coating shall be blast cleaned and repainted with inorganic zinc coating to the specified thickness.

Dry spray, or overspray, as defined in the Steel Structures Painting Manual, Volume 1, "Good Painting Practice," of the "SSPC: The Society for Protective Coatings," shall be removed prior to application of subsequent coats or final acceptance. Removal of dry spray shall be by screening or other methods that minimize polishing of the inorganic zinc surface. The dry film thickness of the coating after removal of dry spray shall be in conformance with the provisions for applying the single undercoat, as specified herein.

The inorganic zinc coating shall be tested for adhesion and cure. The locations of the tests will be determined by the Engineer. The sequence of the testing operations shall be determined by the Contractor. The testing for adhesion and cure will be performed no sooner than 72 hours after application of the single undercoat of inorganic zinc coating. At the Contractor's expense, satisfactory access shall be provided to allow the Engineer to determine the location of the tests and to test the inorganic zinc coating cure. The inorganic zinc coating shall pass the following tests:

Adhesion

• The inorganic zinc coating shall have a minimum adhesion to steel of 4 MPa when measured at no more than 6 locations using a self-aligning adhesion tester in conformance with the requirements in ASTM Designation: D 4541. The Contractor, at the Contractor's expense, shall: (1) verify compliance with the adhesion requirements, (2) furnish test results to the Engineer, and (3) repair the coating after testing.

Cure

- The inorganic zinc coating, when properly cured, shall exhibit a solid, hard, and polished metal surface when firmly scraped with the knurled edge of a quarter. Inorganic zinc coating that is powdery, soft, or does not exhibit a polished metal surface, as determined by the Engineer, shall be repaired by the Contractor, at the Contractor's expense, by blast cleaning and repainting with inorganic zinc coating to the specified thickness.
- The surface pH of the inorganic zinc primer shall be checked in conformance with ASTM Designation: D4262 by wetting the surface with deionized water and applying pH paper with a capability of measuring in increments of 0.5 pH units. Application of finish coats will not be permitted until the surface pH is less than 8.

Except as approved by the Engineer, a minimum curing time of 72 hours shall be allowed between application of inorganic zinc coating and water rinsing.

Exposed areas of inorganic zinc coating shall be thoroughly water rinsed.

Exposed areas of inorganic zinc coating shall receive a minimum of 2 finish coats of an exterior grade latex paint supplied by the manufacturer of the inorganic zinc coating.

The first finish coat shall be applied within 48 hours following the water rinsing.

The finish coat paint shall be formulated for application to inorganic zinc coating and shall conform to the following provisions:

A.

Property	Value	ASTM Designation
Pigment content, percent	24 max.	D 3723
Nonvolatile content, mass percent	49 min.	D 2369
Viscosity, KU	75 min. to 90 max.	D 562
Fineness of dispersion, Hegman	6 min.	D 1210
Drying time at 25°C, 50% RH, 100-µm wet film		D 1640
Set to touch, minutes	30 max.	
Dry through, hours	1 max.	
Adhesion	4A	D 3359, Procedure A

- B. No visible color change in the finish coats shall occur when tested in conformance with the requirements in ASTM Designation: G 53 using FS 40 UV-B bulbs for a minimum of 38 cycles. The cycle shall be 4 hours of ultraviolet (UV) exposure at 60°C and 4 hours of condensate exposure at 40°C.
- C. The vehicle shall be an acrylic or modified acrylic copolymer with a minimum of necessary additives.

The first finish coat shall be applied in 2 applications. The first application shall consist of a spray applied mist application. The second application shall be applied after the mist application has dried to a set to touch condition as determined by the procedure described in Section 7 of ASTM Designation: D1640. The first finish coat color shall match aluminum waterborne acrylic finish paint, Formula PWB-159D, non-leafing. The total dry film thickness of both applications of the first finish coat shall be not less than $50 \, \mu m$.

Except as approved by the Engineer, a minimum drying time of 12 hours shall be allowed between finish coats.

The second finish coat color shall match aluminum waterborne acrylic finish paint, Formula PWB-160D, leafing. The total dry film thickness of all applications of the second finish coat shall be not less than 50 µm.

The 2 finish coats shall be applied in 3 or more applications to a total dry film thickness of not less than 100 μ m nor more than 200 μ m.

The total dry film thickness of all applications of inorganic zinc coating and finish coat paint shall be not less than $200 \, \mu m$ nor more than $350 \, \mu m$.

Cleaning and painting of existing contact surfaces of high strength bolted connections that contain rust, loose paint or other foreign substances, except loose dirt and dust, will be considered as extra work as specified in Section 4-1.03D, of the Standard Specifications. Cost of repair of damage to existing paint caused by the Contractor's operations shall be borne by the Contractor.

MEASUREMENT AND PAYMENT

Dry spot blast cleaning and undercoat painting of blast cleaned areas of existing surfaces will be measured by the square meter of spot blast cleaned areas, and will be paid for as spot blast clean and paint undercoat.

The contract price paid per square meter for spot blast clean and paint undercoat shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in dry spot blast cleaning and painting undercoat on the existing surfaces complete in place, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract lump sum price paid for clean and paint structural steel shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in cleaning and painting the exposed surfaces of the new structural steel and finish coat on undercoated areas of existing metal, complete in place, including water rinsing, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

SECTION 11. MODIFIED STANDARD SPECIFICATION SECTIONS SECTION 11-1. (BLANK) SECTION 11-2. PORTLAND CEMENT CONCRETE

11-2.01 GENERAL

Portland cement concrete shall conform to the provisions in this Section 11-2, "Portland Cement Concrete," and the section entitled "Portland Cement Concrete" in Section 8, "Materials," of these special provisions. Section 90, "Portland Cement Concrete," of the Standard Specifications is deleted. Section 90, "Portland Cement Concrete," of the Standard Specifications is amended to read as follows.

SECTION 90: PORTLAND CEMENT CONCRETE 90-1 GENERAL

90-1.01 DESCRIPTION

- Portland cement concrete shall be composed of cementitious material, fine aggregate, coarse aggregate, admixtures if used, and water, proportioned and mixed as specified in these specifications.
- The Contractor shall determine the mix proportions for all concrete except pavement concrete. The Engineer will determine the mix proportions for pavement concrete. Concrete for which the mix proportions are determined either by the Contractor or the Engineer shall conform to the requirements of this Section 90.
- Unless otherwise specified, cementitious material shall be a combination of cement and mineral admixture. Cementitious material shall be either:
 - 1. "Type IP (MS) Modified" cement; or
 - 2. A combination of "Type II Modified" portland cement and mineral admixture; or
 - 3. A combination of Type V portland cement and mineral admixture.

- Type III portland cement shall be used only as allowed in the special provisions or with the approval of the Engineer.
 - Class 1 concrete shall contain not less than 400 kg of cementitious material per cubic meter.
 - Class 2 concrete shall contain not less than 350 kg of cementitious material per cubic meter.
 - Class 3 concrete shall contain not less than 300 kg of cementitious material per cubic meter.
 - Class 4 concrete shall contain not less than 250 kg of cementitious material per cubic meter.
- Minor concrete shall contain not less than 325 kg of cementitious material per cubic meter unless otherwise specified in these specifications or the special provisions.
- Unless otherwise designated on the plans or specified in these specifications or the special provisions, the amount of cementitious material used per cubic meter of concrete in structures or portions of structures shall conform to the following:

Use	Cementitious Material Content (kg/m3)	
Concrete designated by compressive strength:		
Deck slabs and slab spans of bridges	400 min., 475 max.	
Roof sections of exposed top box culverts	400 min., 475 max.	
Other portions of structures	350 min., 475 max.	
Concrete not designated by compressive strength:		
Deck slabs and slab spans of bridges	400 min.	
Roof sections of exposed top box culverts	400 min.	
Prestressed members	400 min.	
Seal courses	400 min.	
Other portions of structures	350 min.	
Concrete for precast members	350 min., 550 max.	

- Whenever the 28-day compressive strength shown on the plans is greater than 25 MPa, the concrete shall be designated by compressive strength. If the plans show a 28-day compressive strength that is 28 MPa or greater, an additional 14 days will be allowed to obtain the specified strength. The 28-day compressive strengths shown on the plans that are 25 MPa or less are shown for design information only and are not a requirement for acceptance of the concrete.
- Concrete designated by compressive strength shall be proportioned such that the concrete will attain the strength shown on the plans or specified in the special provisions.
- Before using concrete for which the mix proportions have been determined by the Contractor, or in advance of revising those mix proportions, the Contractor shall submit in writing to the Engineer a copy of the mix design.
- Compliance with cementitious material content requirements will be verified in conformance with procedures described in California Test 518 for cement content. For testing purposes, mineral admixture shall be considered to be cement. Batch proportions shall be adjusted as necessary to produce concrete having the specified cementitious material content.
- If any concrete has a cementitious material, portland cement, or mineral admixture content that is less than the minimum required, the concrete shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place and the Contractor shall pay to the State \$0.55 for each kilogram of cementitious material, portland cement, or mineral admixture that is less than the minimum required. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract. The deductions will not be made unless the difference between the contents required and those actually provided exceeds the batching tolerances permitted by Section 90-5, "Proportioning." No deductions will be made based on the results of California Test 518.
 - The requirements of the preceding paragraph shall not apply to minor concrete or commercial quality concrete.

90-2 MATERIALS

90-2.01 CEMENT

- Unless otherwise specified, cement shall be either "Type IP (MS) Modified" cement, "Type II Modified" portland cement or Type V portland cement.
- "Type IP (MS) Modified" cement shall conform to the requirements for Type IP (MS) cement in ASTM Designation: C 595, and shall be comprised of an intimate and uniform blend of Type II cement and not more than 35 percent by mass of mineral admixture. The type and minimum amount of mineral admixture used in the manufacture of "Type IP (MS) Modified" cement shall be in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."

- "Type II Modified" portland cement shall conform to the requirements for Type II portland cement in ASTM Designation: C 150.
- In addition, "Type IP (MS) Modified" cement and "Type II Modified" portland cement shall conform to the following requirements:
 - A. The cement shall not contain more than 0.60 percent by mass of alkalies, calculated as the percentage of Na₂O plus 0.658 times the percentage of K₂O, when determined by either direct intensity flame photometry or by the atomic absorption method. The instrument and procedure used shall be qualified as to precision and accuracy in conformance with the requirements in ASTM Designation: C 114;
 - B. The autoclave expansion shall not exceed 0.50 percent; and
 - C. Mortar, containing the cement to be used and Ottawa sand, when tested in conformance with California Test 527, shall not expand in water more than 0.010 percent and shall not contract in air more than 0.048 percent, except that when cement is to be used for precast prestressed concrete piling, precast prestressed concrete members, or steam cured concrete products, the mortar shall not contract in air more than 0.053 percent.
- Type III and Type V portland cements shall conform to the requirements in ASTM Designation: C 150 and the additional requirements listed above for "Type II Modified" portland cement, except that when tested in conformance with California Test 527, mortar containing Type III portland cement shall not contract in air more than 0.075 percent.
- Cement used in the manufacture of cast-in-place concrete for exposed surfaces of like elements of a structure shall be from the same cement mill.
- Cement shall be protected from exposure to moisture until used. Sacked cement shall be piled to permit access for tally, inspection, and identification of each shipment.
- Adequate facilities shall be provided to assure that cement meeting the provisions specified in this Section 90-2.01 shall be kept separate from other cement in order to prevent any but the specified cement from entering the work. Safe and suitable facilities for sampling cement shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper, in conformance with California Test 125.
- If cement is used prior to sampling and testing as provided in Section 6-1.07, "Certificates of Compliance," and the cement is delivered directly to the site of the work, the Certificate of Compliance shall be signed by the cement manufacturer or supplier of the cement. If the cement is used in ready-mixed concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.
- Cement furnished without a Certificate of Compliance shall not be used in the work until the Engineer has had sufficient time to make appropriate tests and has approved the cement for use.

90-2.02 AGGREGATES

- Aggregates shall be free from deleterious coatings, clay balls, roots, bark, sticks, rags, and other extraneous material.
- Natural aggregates shall be thoroughly and uniformly washed before use.
- The Contractor, at the Contractor's expense, shall provide safe and suitable facilities, including necessary splitting devices for obtaining samples of aggregates, in conformance with California Test 125.
- Aggregates shall be of such character that it will be possible to produce workable concrete within the limits of water content provided in Section 90-6.06, "Amount of Water and Penetration."
- Aggregates shall have not more than 10 percent loss when tested for soundness in conformance with the requirements in California Test 214. The soundness requirement for fine aggregate will be waived, provided that the durability index, D_f , of the fine aggregate is 60, or greater, when tested for durability in conformance with California Test 229.
- If the results of any one or more of the Cleanness Value, Sand Equivalent, or aggregate grading tests do not meet the requirements specified for "Operating Range" but all meet the "Contract Compliance" requirements, the placement of concrete shall be suspended at the completion of the current pour until tests or other information indicate that the next material to be used in the work will comply with the requirements specified for "Operating Range."
- If the results of either or both the Cleanness Value and coarse aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete that is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$4.60 per cubic meter for paving concrete and \$7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

•

If the results of either or both the Sand Equivalent and fine aggregate grading tests do not meet the requirements specified for "Contract Compliance," the concrete which is represented by the tests shall be removed. However, if the Engineer determines that the concrete is structurally adequate, the concrete may remain in place, and the Contractor shall pay to the State \$4.60 per cubic meter for paving concrete and \$7.20 per cubic meter for all other concrete for the concrete represented by these tests and left in place. The Department may deduct the amount from any moneys due, or that may become due, the Contractor under the contract.

- The 2 preceding paragraphs apply individually to the "Contract Compliance" requirements for coarse aggregate and fine aggregate. When both coarse aggregate and fine aggregate do not conform to the "Contract Compliance" requirements, both paragraphs shall apply. The payments specified in those paragraphs shall be in addition to any payments made in conformance with the provisions in Section 90-1.01, "Description."
- No single Cleanness Value, Sand Equivalent or aggregate grading test shall represent more than 250 m³ of concrete or one day's pour, whichever is smaller.
 - Aggregates specified for freeze-thaw resistance shall pass the freezing and thawing test, California Test 528.
- The Contractor shall notify the Engineer of the proposed source of freeze-thaw resistant concrete aggregates at least 4 months before intended use. Should the Contractor later propose a different source of concrete aggregates, the Contractor shall again notify the Engineer at least 4 months before intended use. Blending of fine or coarse aggregates from untested sources with acceptable aggregates will not be permitted. Provisions for the time of submission of samples as provided in Section 40-1.015, "Cement Content," are superseded by the foregoing.
- Concurrently with notification of proposed sources of freeze-thaw resistant concrete aggregates, the Contractor shall furnish samples in the quantity ordered by the Engineer. The samples shall be secured under the direct supervision of the Engineer. Samples from existing stockpiles of processed aggregate shall be taken from washed materials and shall be visibly damp. Samples from materials in place in a material source shall be taken at depths from the existing surface that will ensure the presence of the full quantity of ground water. Excavations for the purpose of securing samples shall be made to the full depth of intended source operations. Samples shall be protected against loss of contained water until they are delivered to the Engineer.
- The Engineer will waive the above freeze-thaw test and the 4-month advance notice, required in this Section, provided aggregates are to be obtained from sources that have previously passed this test and test results are currently applicable.
 - No extension of contract time will be allowed for the time required to perform the freezing and thawing test.
- When the source of an aggregate is changed, except for pavement concrete, the Contractor shall adjust the mix proportions and submit in writing to the Engineer a copy of the mix design before using the aggregates. When the source of an aggregate is changed for pavement concrete, the Engineer shall be allowed sufficient time to adjust the mix, and the aggregates shall not be used until necessary adjustments are made.

90-2.02A Coarse Aggregate

- Coarse aggregate shall consist of gravel, crushed gravel, crushed rock, crushed air-cooled iron blast furnace slag or combinations thereof. Crushed air-cooled blast furnace slag shall not be used in reinforced or prestressed concrete.
 - Coarse aggregate shall conform to the following quality requirements:

	California	
Tests	Test	Requirements
Loss in Los Angeles Rattler (after 500	211	45% max.
revolutions)		
Cleanness Value		
Operating Range	227	75 min.
Contract Compliance	227	71 min.

- In lieu of the above Cleanness Value requirements, a Cleanness Value "Operating Range" limit of 71, minimum, and a Cleanness Value "Contract Compliance" limit of 68, minimum, will be used to determine the acceptability of the coarse aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:
 - 1. coarse aggregate sampled at the completion of processing at the aggregate production plant had a Cleanness Value of not less than 82 when tested by California Test 227; and
 - 2. prequalification tests performed in conformance with the requirements in California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.02B Fine Aggregate

- Fine aggregate shall consist of natural sand, manufactured sand produced from larger aggregate or a combination thereof. Manufactured sand shall be well graded.
 - Fine aggregate shall conform to the following quality requirements:

	California	
Test	Test	Requirements
Organic Impurities	213	Satisfactory ^a
Mortar Strengths Relative to Ottawa Sand	515	95%, min.
Sand Equivalent:		
Operating Range	217	75, min.
Contract Compliance	217	71, min.

a Fine aggregate developing a color darker than the reference standard color solution may be accepted if it is determined by the Engineer, from mortar strength tests, that a darker color is acceptable.

- In lieu of the above Sand Equivalent requirements, a Sand Equivalent "Operating Range" limit of 71 minimum and a Sand Equivalent "Contract Compliance" limit of 68 minimum will be used to determine the acceptability of the fine aggregate if the Contractor furnishes a Certificate of Compliance, as provided in Section 6-1.07, "Certificates of Compliance," certifying that:
 - 1. fine aggregate sampled at the completion of processing at the aggregate production plant had a Sand Equivalent value of not less than 82 when tested by California Test 217; and
 - prequalification tests performed in conformance with California Test 549 indicated that the aggregate would develop a relative strength of not less than 95 percent and would have a relative shrinkage not greater than 105 percent, based on concrete.

90-2.03 WATER

- In conventionally reinforced concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 1000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO₄, when tested in conformance with California Test 417. In prestressed concrete work, the water for curing, for washing aggregates, and for mixing shall be free from oil and shall not contain more than 650 parts per million of chlorides as Cl, when tested in conformance with California Test 422, nor more than 1300 parts per million of sulfates as SO₄, when tested in conformance with California Test 417. In no case shall the water contain an amount of impurities that will cause either: 1) a change in the setting time of cement of more than 25 percent when tested in conformance with the requirements in ASTM Designation: C 191 or ASTM Designation: C 266 or 2) a reduction in the compressive strength of mortar at 14 days of more than 5 percent, when tested in conformance with the requirements in ASTM Designation: C 109, when compared to the results obtained with distilled water or deionized water, tested in conformance with the requirements in ASTM Designation: C 109.
- In non-reinforced concrete work, the water for curing, for washing aggregates and for mixing shall be free from oil and shall not contain more than 2000 parts per million of chlorides as Cl, when tested in conformance with California Test 422, or more than 1500 parts per million of sulfates as SO₄, when tested in conformance with California Test 417.
- In addition to the above provisions, water for curing concrete shall not contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.
- Water reclaimed from mixer wash-out operations may be used in mixing concrete. The water shall not contain coloring agents or more than 300 parts per million of alkalis ($Na_2O + 0.658 K_2O$) as determined on the filtrate. The specific gravity of the water shall not exceed 1.03 and shall not vary more than ± 0.010 during a day's operations.

90-2.04 ADMIXTURE MATERIALS

- Admixture materials shall conform to the requirements in the following ASTM Designations:
- A. Chemical Admixtures—ASTM Designation: C 494.
- B. Air-entraining Admixtures—ASTM Designation: C 260.
- C. Calcium Chloride—ASTM Designation: D 98.

- D. Mineral Admixtures—Coal fly ash; raw or calcined natural pozzolan as specified in ASTM Designation: C618; silica fume conforming to the requirements in ASTM Designation: C1240, with reduction of mortar expansion of 80 percent, minimum, using the cement from the proposed mix design.
- Unless otherwise specified in the special provisions, mineral admixtures shall be used in conformance with the provisions in Section 90-4.08, "Required Use of Mineral Admixtures."

90-3 AGGREGATE GRADINGS

90-3.01 **GENERAL**

- Before beginning concrete work, the Contractor shall submit in writing to the Engineer the gradation of the primary aggregate nominal sizes that the Contractor proposes to furnish. If a primary coarse aggregate or the fine aggregate is separated into 2 or more sizes, the proposed gradation shall consist of the gradation for each individual size, and the proposed proportions of each individual size, combined mathematically to indicate one proposed gradation. The proposed gradation shall meet the grading requirements shown in the table in this section, and shall show the percentage passing each of the sieve sizes used in determining the end result.
- The Engineer may waive, in writing, the gradation requirements in this Section 90-3.01 and in Sections 90-3.02, "Coarse Aggregate Grading," 90-3.03, "Fine Aggregate Grading," and 90-3.04, "Combined Aggregate Gradings," if, in the Engineer's opinion, furnishing the gradation is not necessary for the type or amount of concrete work to be constructed.
 - Gradations proposed by the Contractor shall be within the following percentage passing limits:

Primary Aggregate Nominal Size	Sieve Size	Limits of Proposed Gradation
37.5-mm x 19-mm	25-mm	19 - 41
25-mm x 4.75-mm	19-mm	52 - 85
25-mm x 4.75-mm	9.5-mm	15 - 38
12.5-mm x 4.75-mm	9.5-mm	40 - 78
9.5-mm x 2.36-mm	9.5-mm	50 - 85
Fine Aggregate	1.18-mm	55 - 75
Fine Aggregate	600-µm	34 - 46
Fine Aggregate	300-µm	16 - 29

• Should the Contractor change the source of supply, the Contractor shall submit in writing to the Engineer the new gradations before their intended use.

90-3.02 COARSE AGGREGATE GRADING

• The grading requirements for coarse aggregates are shown in the following table for each size of coarse aggregate:

		P	ercentage P	assing Primar	y Aggregate	Nominal Size	es	
	37.5-mn	n x 19-mm	25-mm	x 4.75-mm	12.5-mm	x 4.75-mm	9.5-mm	x 2.36-mm
	Operating	Contract	Operating	Contract	Operating	Contract	Operating	Contract
Sieve Sizes	Range	Compliance	Range	Compliance	Range	Compliance	Range	Compliance
50-mm	100	100	_	_	_	_	_	_
37.5-mm	88-100	85-100	100	100	_	_	_	_
25-mm	x ± 18	X ± 25	88-100	86-100	1		_	_
19-mm	0-17	0-20	$X \pm 15$	$X \pm 22$	100	100	_	
12.5-mm					82-100	80-100	100	100
9.5-mm	0-7	0-9	$X \pm 15$	$X \pm 22$	$X \pm 15$	$X \pm 22$	$X \pm 15$	$X \pm 20$
4.75-mm			0-16	0-18	0-15	0-18	0-25	0-28
2.36-mm		_	0-6	0-7	0-6	0-7	0-6	0-7

• In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."

- Coarse aggregate for the 37.5-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," shall be furnished in 2 or more primary aggregate nominal sizes. Each primary aggregate nominal size may be separated into 2 sizes and stored separately, provided that the combined material conforms to the grading requirements for that particular primary aggregate nominal size.
- When the 25-mm, maximum, combined aggregate grading as provided in Section 90-3.04, "Combined Aggregate Gradings," is to be used, the coarse aggregate may be separated into 2 sizes and stored separately, provided that the combined material shall conform to the grading requirements for the 25-mm x 4.75-mm primary aggregate nominal size.

90-3.03 FINE AGGREGATE GRADING

• Fine aggregate shall be graded within the following limits:

	Percentag	ge Passing
Sieve Sizes	Operating Range	Contract Compliance
9.5-mm	100	100
4.75-mm	95-100	93-100
2.36-mm	65-95	61-99
1.18-mm	X ± 10	X ± 13
600-µm	X ± 9	X ± 12
300-μm	X ± 6	X ± 9
150-μm	2-12	1-15
75-µm	0-8	0-10

- In the above table, the symbol X is the gradation that the Contractor proposes to furnish for the specific sieve size as provided in Section 90-3.01, "General."
- In addition to the above required grading analysis, the distribution of the fine aggregate sizes shall be such that the difference between the total percentage passing the 1.18-mm sieve and the total percentage passing the 600- μ m sieves shall be between 10 and 40, and the difference between the percentage passing the 600- μ m and 300- μ m sieves shall be between 10 and 40.
- Fine aggregate may be separated into 2 or more sizes and stored separately, provided that the combined material conforms to the grading requirements specified in this Section 90-3.03.

90-3.04 COMBINED AGGREGATE GRADINGS

- Combined aggregate grading limits shall be used only for the design of concrete mixes. Concrete mixes shall be designed so that aggregates are combined in proportions that shall produce a mixture within the grading limits for combined aggregates as specified herein. Within these limitations, the relative proportions shall be as ordered by the Engineer, except as otherwise provided in Section 90-1.01, "Description."
- The combined aggregate grading used in portland cement concrete pavement shall be the 37.5-mm, maximum grading.
- The combined aggregate grading used in concrete for structures and other concrete items, except when specified otherwise in these specifications or the special provisions, shall be either the 37.5-mm, maximum grading, or the 25-mm, maximum grading, at the option of the Contractor.

Grading Limits of Combined Aggregates

		Percenta	ge Passing	
Sieve Sizes	37.5-mm Max.	25-mm Max.	12.5-mm Max.	9.5-mm Max.
50-mm	100	_	_	_
37.5-mm	90-100	100	_	_
25-mm	50-86	90-100	_	_
19-mm	45-75	55-100	100	_
12.5-mm	_	_	90-100	100
9.5-mm	38-55	45-75	55-86	50 - 100
4.75-mm	30-45	35-60	45-63	45 - 63
2.36-mm	23-38	27-45	35-49	35 - 49
1.18-mm	17-33	20-35	25-37	25 - 37
600-µm	10-22	12-25	15-25	15 - 25
300-µm	4-10	5-15	5-15	5 - 15
150-µm	1-6	1-8	1-8	1 - 8
75-μm	0-3	0-4	0-4	0 - 4

• Changes from one grading to another shall not be made during the progress of the work unless permitted by the Engineer.

90-4 ADMIXTURES

90-4.01 GENERAL

- Admixtures used in portland cement concrete shall conform to and be used in conformance with the provisions in this Section 90-4 and the special provisions. Admixtures shall be used when specified or ordered by the Engineer and may be used at the Contractor's option as provided herein.
- Chemical admixtures and air-entraining admixtures containing chlorides as Cl in excess of one percent by mass of admixture, as determined by California Test 415, shall not be used in prestressed or reinforced concrete.
 - Calcium chloride shall not be used in concrete containing steel reinforcement or other embedded metals.
- Mineral admixture used in concrete for exposed surfaces of like elements of a structure shall be from the same source and of the same percentage.
- Admixtures shall be uniform in properties throughout their use in the work. Should it be found that an admixture as furnished is not uniform in properties, its use shall be discontinued.
- If more than one admixture is used, the admixtures shall be compatible with each other so that the desirable effects of all admixtures used will be realized.

90-4.02 MATERIALS

Admixture materials shall conform to the provisions in Section 90–2.04, "Admixture Materials."

90-4.03 ADMIXTURE APPROVAL

- No admixture brand shall be used in the work unless it is on the Department's current list of approved brands for the type of admixture involved.
- Admixture brands will be considered for addition to the approved list if the manufacturer of the admixture submits to the Transportation Laboratory a sample of the admixture accompanied by certified test results demonstrating that the admixture complies with the requirements in the appropriate ASTM Designation and these specifications. The sample shall be sufficient to permit performance of all required tests. Approval of admixture brands will be dependent upon a determination as to compliance with the requirements, based on the certified test results submitted, together with tests the Department may elect to perform.
- When the Contractor proposes to use an admixture of a brand and type on the current list of approved admixture brands, the Contractor shall furnish a Certificate of Compliance from the manufacturer, as provided in Section 6-1.07, "Certificates of Compliance," certifying that the admixture furnished is the same as that previously approved. If a previously approved admixture is not accompanied by a Certificate of Compliance, the admixture shall not be used in the work until the Engineer has had sufficient time to make the appropriate tests and has approved the admixture for use. The Engineer may take samples for testing at any time, whether or not the admixture has been accompanied by a Certificate of Compliance.

.

If a mineral admixture is delivered directly to the site of the work, the Certificate of Compliance shall be signed by the manufacturer or supplier of the mineral admixture. If the mineral admixture is used in ready-mix concrete or in precast concrete products purchased as such by the Contractor, the Certificate of Compliance shall be signed by the manufacturer of the concrete or product.

90-4.04 REQUIRED USE OF CHEMICAL ADMIXTURES AND CALCIUM CHLORIDE

- When the use of a chemical admixture or calcium chloride is specified or ordered by the Engineer, the admixture shall be used at the dosage specified or ordered, except that if no dosage is specified or ordered, the admixture shall be used at the dosage normally recommended by the manufacturer of the admixture.
- Calcium chloride shall be dispensed in liquid, flake, or pellet form. Calcium chloride dispensed in liquid form shall conform to the provisions for dispensing liquid admixtures in Section 90-4.10, "Proportioning and Dispensing Liquid Admixtures."

90-4.05 OPTIONAL USE OF CHEMICAL ADMIXTURES

- The Contractor will be permitted to use Type A or F, water-reducing; Type B, retarding; or Type D or G, water-reducing and retarding admixtures as described in ASTM Designation: C 494 to conserve cementitious material or to facilitate any concrete construction application subject to the following conditions:
 - A. When a water-reducing admixture or a water-reducing and retarding admixture is used, the cementitious material content specified or ordered may be reduced by a maximum of 5 percent by mass, except that the resultant cementitious material content shall be not less than 300 kilograms per cubic meter; and
 - B. When a reduction in cementitious material content is made, the dosage of admixture used shall be the dosage used in determining approval of the admixture.
- Unless otherwise specified, a Type C accelerating chemical admixture conforming to the requirements in ASTM Designation: C 494, may be used in portland cement concrete. Inclusion in the mix design submitted for approval will not be required provided that the admixture is added to counteract changing conditions that contribute to delayed setting of the portland cement concrete, and the use or change in dosage of the admixture is approved in writing by the Engineer.

90-4.06 REQUIRED USE OF AIR-ENTRAINING ADMIXTURES

• When air-entrainment is specified or ordered by the Engineer, the air-entraining admixture shall be used in amounts to produce a concrete having the specified air content as determined by California Test 504.

90-4.07 OPTIONAL USE OF AIR-ENTRAINING ADMIXTURES

• When air-entrainment has not been specified or ordered by the Engineer, the Contractor will be permitted to use an air-entraining admixture to facilitate the use of any construction procedure or equipment provided that the average air content, as determined by California Test 504, of 3 successive tests does not exceed 4 percent, and no single test value exceeds 5.5 percent. If the Contractor elects to use an air-entraining admixture in concrete for pavement, the Contractor shall so indicate at the time the Contractor designates the source of aggregate as provided in Section 40-1.015, "Cement Content."

90-4.08 REOUIRED USE OF MINERAL ADMIXTURES

- Unless otherwise specified, mineral admixture shall be combined with cement to make cementitious material.
- The calcium oxide content of mineral admixtures shall not exceed 10 percent and the available alkali, as sodium oxide equivalent, shall not exceed 1.5 percent when determined in conformance with the requirements in ASTM Designation: C 618.
- The amounts of cement and mineral admixture used in cementitious material shall be sufficient to satisfy the minimum cementitious material content requirements specified in Section 90-1.01, "Description," or Section 90-4.05, "Optional Use of Chemical Admixtures," and shall conform to the following:
 - A. The minimum amount of cement shall not be less than 75 percent by mass of the specified minimum cementitious material content:
 - B. The minimum amount of mineral admixture to be combined with cement shall be determined using one of the following criteria:
 - 1. When the calcium oxide content of a mineral admixture is equal to or less than 2 percent by mass, the amount of mineral admixture shall not be less than 15 percent by mass of the total amount of cementitious material to be used in the mix;

- 2. When the calcium oxide content of a mineral admixture is greater than 2 percent, the amount of mineral admixture shall not be less than 25 percent by mass of the total amount of cementitious material to be used in the mix;
- 3. When a mineral admixture that conforms to the provisions for silica fume in Section 90-2.04, "Admixture Materials," is used, the amount of mineral admixture shall not be less than 10 percent by mass of the total amount of cementitious material to be used in the mix
- C. The total amount of mineral admixture shall not exceed 35 percent by mass of the total amount of cementitious material to be used in the mix. Where Section 90-1.01, "Description," specifies a maximum cementitious content in kilograms per cubic meter, the total mass of cement and mineral admixture per cubic meter shall not exceed the specified maximum cementitious material content.

90-4.09 BLANK

90-4.10 PROPORTIONING AND DISPENSING LIQUID ADMIXTURES

- Chemical admixtures and air-entraining admixtures shall be dispensed in liquid form. Dispensers for liquid admixtures shall have sufficient capacity to measure at one time the prescribed quantity required for each batch of concrete. Each dispenser shall include a graduated measuring unit into which liquid admixtures are measured to within ±5 percent of the prescribed quantity for each batch. Dispensers shall be located and maintained so that the graduations can be accurately read from the point at which proportioning operations are controlled to permit a visual check of batching accuracy prior to discharge. Each measuring unit shall be clearly marked for the type and quantity of admixture.
- Each liquid admixture dispensing system shall be equipped with a sampling device consisting of a valve located in a safe and readily accessible position such that a sample of the admixture may be withdrawn slowly by the Engineer.
- If more than one liquid admixture is used in the concrete mix, each liquid admixture shall have a separate measuring unit and shall be dispensed by injecting equipment located in such a manner that the admixtures are not mixed at high concentrations and do not interfere with the effectiveness of each other. When air-entraining admixtures are used in conjunction with other liquid admixtures, the air-entraining admixture shall be the first to be incorporated into the mix.
- When automatic proportioning devices are required for concrete pavement, dispensers for liquid admixtures shall operate automatically with the batching control equipment. The dispensers shall be equipped with an automatic warning system in good operating condition that will provide a visible or audible signal at the point at which proportioning operations are controlled when the quantity of admixture measured for each batch of concrete varies from the preselected dosage by more than 5 percent, or when the entire contents of the measuring unit are not emptied from the dispenser into each batch of concrete.
- Unless liquid admixtures are added to premeasured water for the batch, their discharge into the batch shall be arranged to flow into the stream of water so that the admixtures are well dispersed throughout the batch, except that air-entraining admixtures may be dispensed directly into moist sand in the batching bins provided that adequate control of the air content of the concrete can be maintained.
- Liquid admixtures requiring dosages greater than 2.5 L/m³ shall be considered to be water when determining the total amount of free water as specified in Section 90-6.06, "Amount of Water and Penetration."
- Special admixtures, such as "high range" water reducers that may contribute to a high rate of slump loss, shall be measured and dispensed as recommended by the admixture manufacturer and as approved by the Engineer.

90-4.11 STORAGE, PROPORTIONING, AND DISPENSING OF MINERAL ADMIXTURES

- Mineral admixtures shall be protected from exposure to moisture until used. Sacked material shall be piled to permit access for tally, inspection and identification for each shipment.
- Adequate facilities shall be provided to assure that mineral admixtures meeting the specified requirements are kept separate from other mineral admixtures in order to prevent any but the specified mineral admixtures from entering the work. Safe and suitable facilities for sampling mineral admixtures shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper.
- Mineral admixtures shall be incorporated into concrete using equipment conforming to the requirements for cement weigh hoppers, and charging and discharging mechanisms in ASTM Designation: C 94, in Section 90-5.03, "Proportioning," and in this Section 90-4.11.
- When concrete is completely mixed in stationary paving mixers, the mineral admixture shall be weighed in a separate weigh hopper conforming to the provisions for cement weigh hoppers and charging and discharging mechanisms in Section 90-5.03A, "Proportioning for Pavement," and the mineral admixture and cement shall be introduced simultaneously into the mixer proportionately with the aggregate. If the mineral admixture is not weighed in a separate weigh hopper, the

Contractor shall provide certification that the stationary mixer is capable of mixing the cement, admixture, aggregates and water uniformly prior to discharge. Certification shall contain the following:

- A. Test results for 2 compressive strength test cylinders of concrete taken within the first one-third and 2 compressive strength test cylinders of concrete taken within the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;"
- B. Calculations demonstrating that the difference in the averages of 2 compressive strengths taken in the first one-third is no greater than 7.5 percent different than the averages of 2 compressive strengths taken in the last one-third of the concrete discharged from a single batch from the stationary paving mixer. Strength tests and cylinder preparation will be in conformance with the provisions of Section 90-9, "Compressive Strength;" and
- C. The mixer rotation speed and time of mixing prior to discharge that are required to produce a mix that meets the requirements above.

90-5 PROPORTIONING

90-5.01 STORAGE OF AGGREGATES

- Aggregates shall be stored or stockpiled in such a manner that separation of coarse and fine particles of each size shall be avoided and also that the various sizes shall not become intermixed before proportioning.
- Aggregates shall be stored or stockpiled and handled in a manner that shall prevent contamination by foreign materials. In addition, storage of aggregates at batching or mixing facilities that are erected subsequent to the award of the contract and that furnish concrete to the project shall conform to the following:
 - A. Intermingling of the different sizes of aggregates shall be positively prevented. The Contractor shall take the necessary measures to prevent intermingling. The preventive measures may include, but are not necessarily limited to, physical separation of stockpiles or construction of bulkheads of adequate length and height; and
 - B. Contamination of aggregates by contact with the ground shall be positively prevented. The Contractor shall take the necessary measures to prevent contamination. The preventive measures shall include, but are not necessarily limited to, placing aggregates on wooden platforms or on hardened surfaces consisting of portland cement concrete, asphalt concrete, or cement treated material.
- In placing aggregates in storage or in moving the aggregates from storage to the weigh hopper of the batching plant, any method that may cause segregation, degradation, or the combining of materials of different gradings that will result in any size of aggregate at the weigh hopper failing to meet the grading requirements, shall be discontinued. Any method of handling aggregates that results in excessive breakage of particles shall be discontinued. The use of suitable devices to reduce impact of falling aggregates may be required by the Engineer.

90-5.02 PROPORTIONING DEVICES

- Weighing, measuring, or metering devices used for proportioning materials shall conform to the requirements in Section 9-1.01, "Measurement of Quantities," and this Section 90-5.02. In addition, automatic weighing systems shall comply with the requirements for automatic proportioning devices in Section 90-5.03A, "Proportioning for Pavement." Automatic devices shall be automatic to the extent that the only manual operation required for proportioning the aggregates, cement, and mineral admixture for one batch of concrete is a single operation of a switch or starter.
- Proportioning devices shall be tested at the expense of the Contractor as frequently as the Engineer may deem necessary to ensure their accuracy.
- Weighing equipment shall be insulated against vibration or movement of other operating equipment in the plant. When the plant is in operation, the mass of each batch of material shall not vary from the mass designated by the Engineer by more than the tolerances specified herein.
- Equipment for cumulative weighing of aggregate shall have a zero tolerance of ± 0.5 percent of the designated total batch mass of the aggregate. For systems with individual weigh hoppers for the various sizes of aggregate, the zero tolerance shall be ± 0.5 percent of the individual batch mass designated for each size of aggregate. Equipment for cumulative weighing of cement and mineral admixtures shall have a zero tolerance of ± 0.5 percent of the designated total batch mass of the cement and mineral admixture. Equipment for weighing cement or mineral admixture separately shall have a zero tolerance of ± 0.5 percent of their designated individual batch masses. Equipment for measuring water shall have a zero tolerance of ± 0.5 percent of its designated mass or volume.
- The mass indicated for any batch of material shall not vary from the preselected scale setting by more than the following:

- A. Aggregate weighed cumulatively shall be within 1.0 percent of the designated total batch mass of the aggregate. Aggregates weighed individually shall be within 1.5 percent of their respective designated batch masses; and
- B. Cement shall be within 1.0 percent of its designated batch mass. When weighed individually, mineral admixture shall be within 1.0 percent of its designated batch mass. When mineral admixture and cement are permitted to be weighed cumulatively, cement shall be weighed first to within 1.0 percent of its designated batch mass, and the total for cement and mineral admixture shall be within 1.0 percent of the sum of their designated batch masses; and
- C. Water shall be within 1.5 percent of its designated mass or volume.
- Each scale graduation shall be approximately 0.001 of the total capacity of the scale. The capacity of scales for weighing cement, mineral admixture, or cement plus mineral admixture and aggregates shall not exceed that of commercially available scales having single graduations indicating a mass not exceeding the maximum permissible mass variation above, except that no scale shall be required having a capacity of less than 500 kg, with 0.5-kg graduations.

90-5.03 PROPORTIONING

- Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cement, mineral admixture, and water as provided in these specifications. Aggregates shall be proportioned by mass.
- At the time of batching, aggregates shall have been dried or drained sufficiently to result in a stable moisture content such that no visible separation of water from aggregate will take place during transportation from the proportioning plant to the point of mixing. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.
- Should separate supplies of aggregate material of the same size group, but of different moisture content or specific gravity or surface characteristics affecting workability, be available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another.
- Bulk "Type IP (MS) Modified" cement shall be weighed in an individual hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer.
- Bulk cement and mineral admixture may be weighed in separate, individual weigh hoppers or may be weighed in the same weigh hopper and shall be kept separate from the aggregates until the ingredients are released for discharge into the mixer. If the cement and mineral admixture are weighed cumulatively, the cement shall be weighed first.
- When cement and mineral admixtures are weighed in separate weigh hoppers, the weigh systems for the proportioning of the aggregate, the cement, and the mineral admixture shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and independent material weighing device. The cement and the mineral admixture shall be discharged into the mixer simultaneously with the aggregate.
- The scales and weigh hoppers for bulk weighing cement, mineral admixture, or cement plus mineral admixture shall be separate and distinct from the aggregate weighing equipment.
- For batches with a volume of one cubic meter or more, the batching equipment shall conform to one of the following combinations:
 - A. Separate boxes and separate scale and indicator for weighing each size of aggregate.
 - B. Single box and scale indicator for all aggregates.
 - C. Single box or separate boxes and automatic weighing mechanism for all aggregates.
- In order to check the accuracy of batch masses, the gross mass and tare mass of batch trucks, truck mixers, truck agitators, and non-agitating hauling equipment shall be determined when ordered by the Engineer. The equipment shall be weighed at the Contractor's expense on scales designated by the Engineer.

90-5.03A Proportioning for Pavement

- Aggregates and bulk cement, mineral admixture, and cement plus mineral admixture for use in pavement shall be proportioned by mass by means of automatic proportioning devices of approved type conforming to these specifications.
- The Contractor shall install and maintain in operating condition an electronically actuated moisture meter that will indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched within a sensitivity of 0.5 percent by mass of the fine aggregate.
- The batching of cement, mineral admixture, or cement plus mineral admixture and aggregate shall be interlocked so that a new batch cannot be started until all weigh hoppers are empty, the proportioning devices are within zero tolerance, and the discharge gates are closed. The interlock shall permit no part of the batch to be discharged until all aggregate hoppers and

the cement and mineral admixture hoppers or the cement plus mineral admixture hopper are charged with masses that are within the tolerances specified in Section 90-5.02, "Proportioning Devices."

- When interlocks are required for cement and mineral admixture charging mechanisms and cement and mineral admixtures are weighed cumulatively, their charging mechanisms shall be interlocked to prevent the introduction of mineral admixture until the mass of cement in the cement weigh hopper is within the tolerances specified in Section 90-5.02, "Proportioning Devices."
- The discharge gate on the cement and mineral admixture hoppers or the cement plus mineral admixture hopper shall be designed to permit regulating the flow of cement, mineral admixture, or cement plus mineral admixture into the aggregate as directed by the Engineer.
- When separate weigh boxes are used for each size of aggregate, the discharge gates shall permit regulating the flow of each size of aggregate as directed by the Engineer.
- Material discharged from the several bins shall be controlled by gates or by mechanical conveyors. The means of withdrawal from the several bins, and of discharge from the weigh box, shall be interlocked so that not more than one bin can discharge at a time, and so that the weigh box cannot be tripped until the required quantity from each of the several bins has been deposited therein. Should a separate weigh box be used for each size of aggregate, all may be operated and discharged simultaneously.
- When the discharge from the several bins is controlled by gates, each gate shall be actuated automatically so that the required mass is discharged into the weigh box, after which the gate shall automatically close and lock.
- The automatic weighing system shall be designed so that all proportions required may be set on the weighing controller at the same time.

90-6 MIXING AND TRANSPORTING

90-6.01 GENERAL

- Concrete shall be mixed in mechanically operated mixers, except that when permitted by the Engineer, batches not exceeding 0.25 m³ may be mixed by hand methods in conformance with the provisions in Section 90-6.05, "Hand-Mixing."
- Equipment having components made of aluminum or magnesium alloys that would have contact with plastic concrete during mixing, transporting, or pumping of portland cement concrete shall not be used.
- Concrete shall be homogeneous and thoroughly mixed, and there shall be no lumps or evidence of undispersed cement, mineral admixture, or cement plus mineral admixture.
- Uniformity of concrete mixtures will be determined by differences in penetration as determined by California Test 533, or slump as determined by ASTM Designation: C 143, and by variations in the proportion of coarse aggregate as determined by California Test 529.
- When the mix design specifies a penetration value, the difference in penetration, determined by comparing penetration tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed 10 mm. When the mix design specifies a slump value, the difference in slump, determined by comparing slump tests on 2 samples of mixed concrete from the same batch or truck mixer load, shall not exceed the values given in the table below. Variation in the proportion of coarse aggregate will be determined by comparing the results of tests of 2 samples of mixed concrete from the same batch or truck mixer load and the difference between the 2 results shall not exceed 100 kg per cubic meter of concrete.

Average Slump	Maximum Permissible Difference
Less than 100-mm	25-mm
100-mm to 150-mm	38-mm
Greater than 150-mm to 225-mm	50-mm

• The Contractor, at the Contractor's expense, shall furnish samples of the freshly mixed concrete and provide satisfactory facilities for obtaining the samples.

90-6.02 MACHINE MIXING

- Concrete mixers may be of the revolving drum or the revolving blade type, and the mixing drum or blades shall be operated uniformly at the mixing speed recommended by the manufacturer. Mixers and agitators that have an accumulation of hard concrete or mortar shall not be used.
- The temperature of mixed concrete, immediately before placing, shall be not less than 10°C or more than 32°C. Aggregates and water shall be heated or cooled as necessary to produce concrete within these temperature limits. Neither aggregates nor mixing water shall be heated to exceed 65°C. If ice is used to cool the concrete, discharge of the mixer will not be permitted until all ice is melted.

- The batch shall be so charged into the mixer that some water will enter in advance of cementitious materials and aggregates. All water shall be in the drum by the end of the first one fourth of the specified mixing time.
- Cementitious materials shall be batched and charged into the mixer by means that will not result either in loss of cementitious materials due to the effect of wind, in accumulation of cementitious materials on surfaces of conveyors or hoppers, or in other conditions that reduce or vary the required quantity of cementitious material in the concrete mixture.
- Paving and stationary mixers shall be operated with an automatic timing device. The timing device and discharge mechanism shall be interlocked so that during normal operation no part of the batch will be discharged until the specified mixing time has elapsed.
- The total elapsed time between the intermingling of damp aggregates and all cementitious materials and the start of mixing shall not exceed 30 minutes.
 - The size of batch shall not exceed the manufacturer's guaranteed capacity.
- When producing concrete for pavement or base, suitable batch counters shall be installed and maintained in good operating condition at jobsite batching plants and stationary mixers. The batch counters shall indicate the exact number of batches proportioned and mixed.
 - Concrete shall be mixed and delivered to the jobsite by means of one of the following combinations of operations:
 - A. Mixed completely in a stationary mixer and the mixed concrete transported to the point of delivery in truck agitators or in non-agitating hauling equipment (central-mixed concrete).
 - B. Mixed partially in a stationary mixer, and the mixing completed in a truck mixer (shrink-mixed concrete).
 - C. Mixed completely in a truck mixer (transit-mixed concrete).
 - D. Mixed completely in a paving mixer.
- Agitators may be truck mixers operating at agitating speed or truck agitators. Each mixer and agitator shall have attached thereto in a prominent place a metal plate or plates on which is plainly marked the various uses for which the equipment is designed, the manufacturer's guaranteed capacity of the drum or container in terms of the volume of mixed concrete and the speed of rotation of the mixing drum or blades.
- Truck mixers shall be equipped with electrically or mechanically actuated revolution counters by which the number of revolutions of the drum or blades may readily be verified.
- When shrink-mixed concrete is furnished, concrete that has been partially mixed at a central plant shall be transferred to a truck mixer and all requirements for transit-mixed concrete shall apply. No credit in the number of revolutions at mixing speed shall be allowed for partial mixing in a central plant.

90-6.03 TRANSPORTING MIXED CONCRETE

- Mixed concrete may be transported to the delivery point in truck agitators or truck mixers operating at the speed designated by the manufacturer of the equipment as agitating speed, or in non-agitating hauling equipment, provided the consistency and workability of the mixed concrete upon discharge at the delivery point is suitable for adequate placement and consolidation in place, and provided the mixed concrete after hauling to the delivery point conforms to the provisions in Section 90-6.01, "General."
- Truck agitators shall be loaded not to exceed the manufacturer's guaranteed capacity and shall maintain the mixed concrete in a thoroughly mixed and uniform mass during hauling.
- Bodies of non-agitating hauling equipment shall be constructed so that leakage of the concrete mix, or any part thereof, will not occur at any time.
- Concrete hauled in open-top vehicles shall be protected during hauling against rain or against exposure to the sun for more than 20 minutes when the ambient temperature exceeds 24°C.
- No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced.
- The rate of discharge of mixed concrete from truck mixer-agitators shall be controlled by the speed of rotation of the drum in the discharge direction with the discharge gate fully open.
- When a truck mixer or agitator is used for transporting concrete to the delivery point, discharge shall be completed within 1.5 hours or before 250 revolutions of the drum or blades, whichever occurs first, after the introduction of the cement to the aggregates. Under conditions contributing to quick stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time allowed may be less than 1.5 hours.
- When non-agitating hauling equipment is used for transporting concrete to the delivery point, discharge shall be completed within one hour after the addition of the cement to the aggregates. Under conditions contributing to quick

stiffening of the concrete, or when the temperature of the concrete is 30°C or above, the time between the introduction of cement to the aggregates and discharge shall not exceed 45 minutes.

- Each load of concrete delivered at the jobsite shall be accompanied by a weighmaster certificate showing the mix identification number, non-repeating load number, date and time at which the materials were batched, the total amount of water added to the load, and for transit-mixed concrete, the reading of the revolution counter at the time the truck mixer is charged with cement. This weighmaster certificate shall also show the actual scale masses (kilograms) for the ingredients batched. Theoretical or target batch masses shall not be used as a substitute for actual scale masses.
- Weighmaster certificates shall be provided in printed form, or if approved by the Engineer, the data may be submitted in electronic media. Electronic media shall be presented in a tab-delimited format on a 90 mm diskette with a capacity of at least 1.4 megabytes. Captured data, for the ingredients represented by each batch shall be "line feed, carriage return" (LFCR) and "one line, separate record" with allowances for sufficient fields to satisfy the amount of data required by these specifications.
- The Contractor may furnish a weighmaster certificate accompanied by a separate certificate that lists the actual batch masses or measurements for a load of concrete provided that both certificates are imprinted with the same non-repeating load number that is unique to the contract and delivered to the jobsite with the load.
- Weighmaster certificates furnished by the Contractor shall conform to the provisions in Section 9-1.01, "Measurement of Quantities."

90-6.04 TIME OR AMOUNT OF MIXING

- Mixing of concrete in paving or stationary mixers shall continue for the required mixing time after all ingredients, except water and admixture, if added with the water, are in the mixing compartment of the mixer before any part of the batch is released. Transfer time in multiple drum mixers shall not be counted as part of the required mixing time.
- The required mixing time, in paving or stationary mixers, of concrete used for concrete structures, except minor structures, shall be not less than 90 seconds or more than 5 minutes, except that when directed by the Engineer in writing, the requirements of the following paragraph shall apply.
- The required mixing time, in paving or stationary mixers, except as provided in the preceding paragraph, shall be not less than 50 seconds or more than 5 minutes.
- The minimum required revolutions at the mixing speed for transit-mixed concrete shall not be less than that recommended by the mixer manufacturer, but in no case shall the number of revolutions be less than that required to consistently produce concrete conforming to the provisions for uniformity in Section 90-6.01, "General."

90-6.05 HAND-MIXING

• Hand-mixed concrete shall be made in batches of not more than 0.25 m³ and shall be mixed on a watertight, level platform. The proper amount of coarse aggregate shall be measured in measuring boxes and spread on the platform and the fine aggregate shall be spread on this layer, the 2 layers being not more than 0.3 meters in total depth. On this mixture shall be spread the dry cement and mineral admixture and the whole mass turned no fewer than 2 times dry; then sufficient clean water shall be added, evenly distributed, and the whole mass again turned no fewer than 3 times, not including placing in the carriers or forms.

90-6.06 AMOUNT OF WATER AND PENETRATION

• The amount of water used in concrete mixes shall be regulated so that the penetration of the concrete as determined by California Test 533 or the slump of the concrete as determined by ASTM Designation: C 143 is within the "Nominal" values shown in the following table. When the penetration or slump of the concrete is found to exceed the nominal values listed, the mixture of subsequent batches shall be adjusted to reduce the penetration or slump to a value within the nominal range shown. Batches of concrete with a penetration or slump exceeding the maximum values listed shall not be used in the work. When Type F or Type G chemical admixtures are added to the mix, the penetration requirements shall not apply and the slump shall not exceed 225 mm after the chemical admixtures are added.

Type of Work	Non	ninal	Maxi	mum
	Penetration	Slump	Penetration	Slump
	(mm)	(mm)	(mm)	(mm)
Concrete Pavement	0-25		40	_
Non-reinforced concrete facilities	0-35		50	
Reinforced concrete structures				
Sections over 300-mm thick	0-35	_	65	_
Sections 300-mm thick or less	0-50		75	
Concrete placed under water	_	150-200		225
Cast-in-place concrete piles	65-90	130-180	100	200

- The amount of free water used in concrete shall not exceed 183 kg/m³, plus 20 kg for each required 100 kg of cementitious material in excess of 325 kg/m³.• The term free water is defined as the total water in the mixture minus the water absorbed by the aggregates in reaching a saturated surface-dry condition.
- Where there are adverse or difficult conditions that affect the placing of concrete, the above specified penetration and free water content limitations may be exceeded providing the Contractor is granted permission by the Engineer in writing to increase the cementitious material content per cubic meter of concrete. The increase in water and cementitious material shall be at a ratio not to exceed 30 kg of water per added 100 kg of cementitious material per cubic meter. The cost of additional cementitious material and water added under these conditions shall be at the Contractor's expense and no additional compensation will be allowed therefor.
- The equipment for supplying water to the mixer shall be constructed and arranged so that the amount of water added can be measured accurately. Any method of discharging water into the mixer for a batch shall be accurate within 1.5 percent of the quantity of water required to be added to the mix for any position of the mixer. Tanks used to measure water shall be designed so that water cannot enter while water is being discharged into the mixer and discharge into the mixer shall be made rapidly in one operation without dribbling. All equipment shall be arranged so as to permit checking the amount of water delivered by discharging into measured containers.

90-7 CURING CONCRETE

90-7.01 METHODS OF CURING

Newly placed concrete shall be cured by the methods specified in this Section 90-7.01 and the special provisions.

90-7.01A Water Method

- The concrete shall be kept continuously wet by the application of water for a minimum curing period of 7 days after the concrete has been placed.
- When a curing medium consisting of cotton mats, rugs, carpets, or earth or sand blankets is to be used to retain the moisture, the entire surface of the concrete shall be kept damp by applying water with a nozzle that so atomizes the flow that a mist and not a spray is formed, until the surface of the concrete is covered with the curing medium. The moisture from the nozzle shall not be applied under pressure directly upon the concrete and shall not be allowed to accumulate on the concrete in a quantity sufficient to cause a flow or wash the surface. At the expiration of the curing period, the concrete surfaces shall be cleared of all curing mediums.
- When concrete bridge decks and flat slabs are to be cured without the use of a curing medium, the entire surface of the bridge deck or slab shall be kept damp by the application of water with an atomizing nozzle as specified in the preceding paragraph, until the concrete has set, after which the entire surface of the concrete shall be sprinkled continuously with water for a period of not less than 7 days.

90-7.01B Curing Compound Method

- Surfaces of the concrete that are exposed to the air shall be sprayed uniformly with a curing compound.
- Curing compounds to be used shall be as follows:
- 1. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B, except the resin type shall be poly-alpha-methylstyrene.
- 2. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class B.
- 3. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A.
- 4. Non-pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class B.
- 5. Non-pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 1, Class A.

- 6. Non-pigmented curing compound with fugitive dye conforming to the requirements in ASTM Designation: C 309, Type 1-D, Class A.
- The infrared scan for the dried vehicle from curing compound (1) shall match the infrared scan on file at the Transportation Laboratory.
- The loss of water for each type of curing compound, when tested in conformance with the requirements in California Test 534, shall not be more than 0.15-kg/m² in 24 hours or more than 0.45-kg/m² in 72 hours.
 - The curing compound to be used will be specified elsewhere in these specifications or in the special provisions.
- When the use of curing compound is required or permitted elsewhere in these specifications or in the special provisions and no specific kind is specified, any of the curing compounds listed above may be used.
 - Curing compound shall be applied at a nominal rate of 3.7 m²/L, unless otherwise specified.
- At any point, the application rate shall be within $\pm 1.2 \text{ m}^2/\text{L}$ of the nominal rate specified, and the average application rate shall be within $\pm 0.5 \text{ m}^2/\text{L}$ of the nominal rate specified when tested in conformance with the requirements in California Test 535. Runs, sags, thin areas, skips, or holidays in the applied curing compound shall be evidence that the application is not satisfactory.
- Curing compounds shall be applied using power operated spray equipment. The power operated spraying equipment shall be equipped with an operational pressure gage and a means of controlling the pressure. Hand spraying of small and irregular areas that are not reasonably accessible to mechanical spraying equipment, in the opinion of the Engineer, may be permitted.
- The curing compound shall be applied to the concrete following the surface finishing operation, immediately before the moisture sheen disappears from the surface, but before any drying shrinkage or craze cracks begin to appear. In the event of any drying or cracking of the surface, application of water with an atomizing nozzle as specified in Section 90-7.01A, "Water Method," shall be started immediately and shall be continued until application of the compound is resumed or started; however, the compound shall not be applied over any resulting freestanding water. Should the film of compound be damaged from any cause before the expiration of 7 days after the concrete is placed in the case of structures and 72 hours in the case of pavement, the damaged portion shall be repaired immediately with additional compound.
- At the time of use, compounds containing pigments shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. A paddle shall be used to loosen all settled pigment from the bottom of the container, and a power driven agitator shall be used to disperse the pigment uniformly throughout the vehicle.
 - Agitation shall not introduce air or other foreign substance into the curing compound.
- The manufacturer shall include in the curing compound the necessary additives for control of sagging, pigment settling, leveling, de-emulsification, or other requisite qualities of a satisfactory working material. Pigmented curing compounds shall be manufactured so that the pigment does not settle badly, does not cake or thicken in the container, and does not become granular or curdled. Settlement of pigment shall be a thoroughly wetted, soft, mushy mass permitting the complete and easy vertical penetration of a paddle. Settled pigment shall be easily redispersed, with minimum resistance to the sideways manual motion of the paddle across the bottom of the container, to form a smooth uniform product of the proper consistency.
- Curing compounds shall remain sprayable at temperatures above 4°C and shall not be diluted or altered after manufacture.
- The curing compound shall be packaged in clean 210-L barrels or round 19-L containers or shall be supplied from a suitable storage tank located at the jobsite. The containers shall comply with "Title 49, Code of Federal Regulations, Hazardous Materials Regulations." The 210-L barrels shall have removable lids and airtight fasteners. The 19-L containers shall be round and have standard full open head and bail. Lids with bungholes shall not be permitted. On-site storage tanks shall be kept clean and free of contaminants. Each tank shall have a permanent system designed to completely redisperse settled material without introducing air or other foreign substances.
- Steel containers and lids shall be lined with a coating that will prevent destructive action by the compound or chemical agents in the air space above the compound. The coating shall not come off the container or lid as skins. Containers shall be filled in a manner that will prevent skinning. Plastic containers shall not react with the compound.
- Each container shall be labeled with the manufacturer's name, kind of curing compound, batch number, volume, date of manufacture, and volatile organic compound (VOC) content. The label shall also warn that the curing compound containing pigment shall be well stirred before use. Precautions concerning the handling and the application of curing compound shall be shown on the label of the curing compound containers in conformance with the Construction Safety Orders and General Industry Safety Orders of the State of California.
- Containers of curing compound shall be labeled to indicate that the contents fully comply with the rules and regulations concerning air pollution control in the State of California.
- When the curing compound is shipped in tanks or tank trucks, a shipping invoice shall accompany each load. The invoice shall contain the same information as that required herein for container labels.

- Curing compound will be sampled by the Engineer at the source of supply or at the jobsite or at both locations.
- Curing compound shall be formulated so as to maintain the specified properties for a minimum of one year. The Engineer may require additional testing before use to determine compliance with these specifications if the compound has not been used within one year or whenever the Engineer has reason to believe the compound is no longer satisfactory.
- Tests will be conducted in conformance with the latest ASTM test methods and methods in use by the Transportation Laboratory.

90-7.01C Waterproof Membrane Method

- The exposed finished surfaces of concrete shall be sprayed with water, using a nozzle that so atomizes the flow that a mist and not a spray is formed, until the concrete has set, after which the curing membrane shall be placed. The curing membrane shall remain in place for a period of not less than 72 hours.
- Sheeting material for curing concrete shall conform to the requirements in AASHTO Designation: M 171 for white reflective materials.
- The sheeting material shall be fabricated into sheets of such width as to provide a complete cover for the entire concrete surface. Joints in the sheets shall be securely cemented together in such a manner as to provide a waterproof joint. The joint seams shall have a minimum lap of 100 mm.
- The sheets shall be securely weighted down by placing a bank of earth on the edges of the sheets or by other means satisfactory to the Engineer.
- Should any portion of the sheets be broken or damaged before the expiration of 72 hours after being placed, the broken or damaged portions shall be immediately repaired with new sheets properly cemented into place.
- Sections of membrane that have lost their waterproof qualities or have been damaged to such an extent as to render them unfit for curing the concrete shall not be used.

90-7.01D Forms-In-Place Method

- Formed surfaces of concrete may be cured by retaining the forms in place. The forms shall remain in place for a minimum period of 7 days after the concrete has been placed, except that for members over 0.5-m in least dimension the forms shall remain in place for a minimum period of 5 days.
- Joints in the forms and the joints between the end of forms and concrete shall be kept moisture tight during the curing period. Cracks in the forms and cracks between the forms and the concrete shall be resealed by methods subject to the approval of the Engineer.

90-7.02 CURING PAVEMENT

- The entire exposed area of the pavement, including edges, shall be cured by the waterproof membrane method, or curing compound method using curing compound (1) or (2) as the Contractor may elect. Should the side forms be removed before the expiration of 72 hours following the start of curing, the exposed pavement edges shall also be cured. If the pavement is cured by means of the curing compound method, the sawcut and all portions of the curing compound that have been disturbed by sawing operations shall be restored by spraying with additional curing compound.
- Curing shall commence as soon as the finishing process provided in Section 40-1.10, "Final Finishing," has been completed. The method selected shall conform to the provisions in Section 90-7.01, "Methods of Curing."
- When the curing compound method is used, the compound shall be applied to the entire pavement surface by mechanical sprayers. Spraying equipment shall be of the fully atomizing type equipped with a tank agitator that provides for continual agitation of the curing compound during the time of application. The spray shall be adequately protected against wind, and the nozzles shall be so oriented or moved mechanically transversely as to result in the minimum specified rate of coverage being applied uniformly on exposed faces. Hand spraying of small and irregular areas, and areas inaccessible to mechanical spraying equipment, in the opinion of the Engineer, will be permitted. When the ambient air temperature is above 15°C, the Contractor shall fog the surface of the concrete with a fine spray of water as specified in Section 90-7.01A, "Water Method." The surface of the pavement shall be kept moist between the hours of 10:00 a.m. and 4:30 p.m. on the day the concrete is placed. However, the fogging done after the curing compound has been applied shall not begin until the compound has set sufficiently to prevent displacement. Fogging shall be discontinued if ordered in writing by the Engineer.

90-7.03 CURING STRUCTURES

- Newly placed concrete for cast-in-place structures, other than highway bridge decks, shall be cured by the water method, the forms-in-place method, or, as permitted herein, by the curing compound method, in conformance with the provisions in Section 90-7.01, "Methods of Curing."
- The curing compound method using a pigmented curing compound may be used on concrete surfaces of construction joints, surfaces that are to be buried underground, and surfaces where only Ordinary Surface Finish is to be

applied and on which a uniform color is not required and that will not be visible from a public traveled way. If the Contractor elects to use the curing compound method on the bottom slab of box girder spans, the curing compound shall be curing compound (1).

- The top surface of highway bridge decks shall be cured by both the curing compound method and the water method. The curing compound shall be curing compound (1). The curing compound shall be applied progressively during the deck finishing operations immediately after finishing operations are completed on each individual portion of the deck. The water cure shall be applied not later than 4 hours after completion of deck finishing or, for portions of the decks on which finishing is completed after normal working hours, the water cure shall be applied not later than the following morning.
- Concrete surfaces of minor structures, as defined in Section 51-1.02, "Minor Structures," shall be cured by the water method, the forms-in-place method or the curing compound method.
- When deemed necessary by the Engineer during periods of hot weather, water shall be applied to concrete surfaces being cured by the curing compound method or by the forms-in-place method, until the Engineer determines that a cooling effect is no longer required. Application of water for this purpose will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."

90-7.04 CURING PRECAST CONCRETE MEMBERS

- Precast concrete members shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing." Curing shall be provided for the minimum time specified for each method or until the concrete reaches its design strength, whichever is less. Steam curing may also be used for precast members and shall conform to the following provisions:
 - A. After placement of the concrete, members shall be held for a minimum 4-hour presteaming period. If the ambient air temperature is below 10°C, steam shall be applied during the presteaming period to hold the air surrounding the member at a temperature between 10°C and 32°C.
 - B. To prevent moisture loss on exposed surfaces during the presteaming period, members shall be covered as soon as possible after casting or the exposed surfaces shall be kept wet by fog spray or wet blankets.
 - C. Enclosures for steam curing shall allow free circulation of steam about the member and shall be constructed to contain the live steam with a minimum moisture loss. The use of tarpaulins or similar flexible covers will be permitted, provided they are kept in good repair and secured in such a manner as to prevent the loss of steam and moisture.
 - D. Steam at the jets shall be at low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 22°C per hour. The curing temperature throughout the enclosure shall not exceed 65°C and shall be maintained at a constant level for a sufficient time necessary to develop the required transfer strength. Control cylinders shall be covered to prevent moisture loss and shall be placed in a location where temperature is representative of the average temperature of the enclosure.
 - E. Temperature recording devices that will provide an accurate, continuous, permanent record of the curing temperature shall be provided. A minimum of one temperature recording device per 60 m of continuous bed length will be required for checking temperature.
 - F. Members in pretension beds shall be detensioned immediately after the termination of steam curing while the concrete and forms are still warm, or the temperature under the enclosure shall be maintained above 15°C until the stress is transferred to the concrete.
 - G. Curing of precast concrete will be considered completed after termination of the steam curing cycle.

90-7.05 CURING PRECAST PRESTRESSED CONCRETE PILES

- Newly placed concrete for precast prestressed concrete piles shall be cured in conformance with the provisions in Section 90-7.04, "Curing Precast Concrete Members," except that piles with a class designation ending in C (corrosion resistant) shall be cured as follows:
 - A. Piles shall be either steam cured or water cured. If water curing is used, the piles shall be kept continuously wet by the application of water in conformance with the provisions in Section 90-7.01A, "Water Method."
 - B. If steam curing is used, the steam curing provisions in Section 90-7.04, "Curing Precast Concrete Members," shall apply except that the piles shall be kept continuously wet for their entire length for a period of not less than 3 days, including the holding and steam curing periods.

90-7.06 CURING SLOPE PROTECTION

- Concrete slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."
- Concreted-rock slope protection shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing," or with a blanket of earth kept wet for 72 hours, or by sprinkling with a fine spray of water every 2 hours during the daytime for a period of 3 days.

90-7.07 CURING MISCELLANEOUS CONCRETE WORK

- Exposed surfaces of curbs shall be cured by pigmented curing compounds as specified in Section 90-7.01B, "Curing Compound Method."
- Concrete sidewalks, gutter depressions, island paving, curb ramps, driveways, and other miscellaneous concrete areas shall be cured in conformance with any of the methods specified in Section 90-7.01, "Methods of Curing."
- Shotcrete shall be cured for at least 72 hours by spraying with water, or by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."
 - Mortar and grout shall be cured by keeping the surface damp for 3 days.
- After placing, the exposed surfaces of sign structure foundations, including pedestal portions, if constructed, shall be cured for at least 72 hours by spraying with water, or by a moist earth blanket, or by any of the methods provided in Section 90-7.01, "Methods of Curing."

90-8 PROTECTING CONCRETE

90-8.01 **GENERAL**

- In addition to the provisions in Section 7-1.16, "Contractor's Responsibility for the Work and Materials," the Contractor shall protect concrete as provided in this Section 90-8.
- Concrete shall not be placed on frozen or ice-coated ground or subgrade nor on ice-coated forms, reinforcing steel, structural steel, conduits, precast members, or construction joints.
- Under rainy conditions, placing of concrete shall be stopped before the quantity of surface water is sufficient to damage surface mortar or cause a flow or wash of the concrete surface, unless the Contractor provides adequate protection against damage.
- Concrete that has been frozen or damaged by other causes, as determined by the Engineer, shall be removed and replaced by the Contractor at the Contractor's expense.

90-8.02 PROTECTING CONCRETE STRUCTURES

• Structure concrete and shotcrete used as structure concrete shall be maintained at a temperature of not less than 7°C for 72 hours after placing and at not less than 4°C for an additional 4 days. When required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.

90-8.03 PROTECTING CONCRETE PAVEMENT

- Pavement concrete shall be maintained at a temperature of not less than 4°C for 72 hours. When required by the Engineer, the Contractor shall submit a written outline of the proposed methods for protecting the concrete.
- Except as provided in Section 7-1.08, "Public Convenience," the Contractor shall protect concrete pavement against construction and other activities that abrade, scar, discolor, reduce texture depth, lower coefficient of friction, or otherwise damage the surface. Stockpiling, drifting, or excessive spillage of soil, gravel, petroleum products, and concrete or asphalt mixes on the surface of concrete pavement is prohibited unless otherwise specified in these specifications, the special provisions or permitted by the Engineer.
- When ordered by the Engineer or shown on the plans or specified in the special provisions, pavement crossings shall be constructed for the convenience of public traffic. The material and work necessary for the construction of the crossings, and their subsequent removal and disposal, will be paid for at the contract unit prices for the items of work involved and if there are no contract items for the work involved, payment for pavement crossings will be made by extra work as provided in Section 4-1.03D, "Extra Work.". Where public traffic will be required to cross over the new pavement, Type III portland cement may be used in concrete, if permitted in writing by the Engineer. The pavement may be opened to traffic as soon as the concrete has developed a modulus of rupture of 3.8 MPa. The modulus of rupture will be determined by California Test 523.
- No traffic or Contractor's equipment, except as hereinafter provided, will be permitted on the pavement before a period of 10 days has elapsed after the concrete has been placed, nor before the concrete has developed a modulus of rupture

of at least 3.8 MPa. Concrete that fails to attain a modulus of rupture of 3.8 MPa within 10 days shall not be opened to traffic until directed by the Engineer.

- Equipment for sawing weakened plane joints will be permitted on the pavement as specified in Section 40-1.08B, "Weakened Plane Joints."
- When requested in writing by the Contractor, the tracks on one side of paving equipment will be permitted on the pavement after a modulus of rupture of 2.4 MPa has been attained, provided that:
 - A. Unit pressure exerted on the pavement by the paver shall not exceed 135 kPa;
 - B. Tracks with cleats, grousers, or similar protuberances shall be modified or shall travel on planks or equivalent protective material, so that the pavement is not damaged; and
 - C. No part of the track shall be closer than 0.3-m from the edge of pavement.
- In case of visible cracking of, or other damage to the pavement, operation of the paving equipment on the pavement shall be immediately discontinued.
- Damage to the pavement resulting from early use of pavement by the Contractor's equipment as provided above shall be repaired by the Contractor at the Contractor's expense.
- The State will furnish the molds and machines for testing the concrete for modulus of rupture, and the Contractor, at the Contractor's expense, shall furnish the material and whatever labor the Engineer may require.

90-9 COMPRESSIVE STRENGTH

90-9.01 **GENERAL**

- Concrete compressive strength requirements consist of a minimum strength that shall be attained before various loads or stresses are applied to the concrete and, for concrete designated by strength, a minimum strength at the age of 28 days or at the age otherwise allowed in Section 90-1.01, "Description." The various strengths required are specified in these specifications or the special provisions or are shown on the plans.
- The compressive strength of concrete will be determined from test cylinders that have been fabricated from concrete sampled in conformance with the requirements of ASTM Designation: C 172. Test cylinders will be molded and initially field cured in conformance with California Test 540. Test cylinders will be cured and tested after receipt at the testing laboratory in conformance with the requirements of ASTM Designation: C 39. A strength test shall consist of the average strength of 2 cylinders fabricated from material taken from a single load of concrete, except that, if any cylinder should show evidence of improper sampling, molding, or testing, that cylinder shall be discarded and the strength test shall consist of the strength of the remaining cylinder.
- When concrete compressive strength is specified as a prerequisite to applying loads or stresses to a concrete structure or member, test cylinders for other than steam cured concrete will be cured in conformance with Method 1 of California Test 540. The compressive strength of concrete determined for these purposes will be evaluated on the basis of individual tests.
- When concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete strength to be used as a basis for acceptance of other than steam cured concrete will be determined from cylinders cured in conformance with Method 1 of California Test 540. If the result of a single compressive strength test at the maximum age specified or allowed is below the specified strength but is 95 percent or more of the specified strength, the Contractor shall, at the Contractor's expense, make corrective changes, subject to approval of the Engineer, in the mix proportions or in the concrete fabrication procedures, before placing additional concrete, and shall pay to the State \$14 for each in-place cubic meter of concrete represented by the deficient test. If the result of a single compressive strength test at the maximum age specified or allowed is below 95 percent of the specified strength, but is 85 percent or more of the specified strength, the Contractor shall make the corrective changes specified above, and shall pay to the State \$20 for each in place cubic meter of concrete represented by the deficient test. In addition, such corrective changes shall be made when the compressive strength of concrete tested at 7 days indicates, in the judgment of the Engineer, that the concrete will not attain the required compressive strength at the maximum age specified or allowed. Concrete represented by a single test that indicates a compressive strength of less than 85 percent of the specified 28-day compressive strength will be rejected in conformance with the provisions in Section 6-1.04, "Defective Materials."
- If the test result indicates that the compressive strength at the maximum curing age specified or allowed is below the specified strength, but is 85 percent or more of the specified strength, payments to the State as required above shall be made, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer that the strength of the concrete placed in the work meets or exceeds the specified 28-day compressive strength. If the test result indicates a compressive strength at the maximum curing age specified or allowed below 85 percent, the concrete represented by that test will be rejected, unless the Contractor, at the Contractor's expense, obtains and submits evidence acceptable to the Engineer

that the strength and quality of the concrete placed in the work are acceptable. If the evidence consists of tests made on cores taken from the work, the cores shall be obtained and tested in conformance with the requirements in ASTM Designation: C 42.

- No single compressive strength test shall represent more than 250 m³.
- When a precast concrete member is steam cured, the compressive strength of the concrete will be determined from test cylinders that have been handled and stored in conformance with Method 3 of California Test 540. The compressive strength of steam cured concrete will be evaluated on the basis of individual tests representing specific portions of production. When the concrete is designated by 28-day compressive strength rather than by cementitious material content, the concrete shall be considered to be acceptable whenever its compressive strength reaches the specified 28-day compressive strength provided that strength is reached in not more than the maximum number of days specified or allowed after the member is cast.
- When concrete is specified by compressive strength, prequalification of materials, mix proportions, mixing equipment, and procedures proposed for use will be required prior to placement of the concrete. Prequalification shall be accomplished by the submission of acceptable certified test data or trial batch reports by the Contractor. Prequalification data shall be based on the use of materials, mix proportions, mixing equipment, procedures, and size of batch proposed for use in the work.
- Certified test data, in order to be acceptable, shall indicate that not less than 90 percent of at least 20 consecutive tests exceed the specified strength at the maximum number of cure days specified or allowed, and none of those tests are less than 95 percent of specified strength. Strength tests included in the data shall be the most recent tests made on concrete of the proposed mix design and all shall have been made within one year of the proposed use of the concrete.
- Trial batch test reports, in order to be acceptable, shall indicate that the average compressive strength of 5 consecutive concrete cylinders, taken from a single batch, at not more than 28 days (or the maximum age allowed) after molding shall be at least 4 MPa greater than the specified 28-day compressive strength, and no individual cylinder shall have a strength less than the specified strength at the maximum age specified or allowed. Data contained in the report shall be from trial batches that were produced within one year of the proposed use of specified strength concrete in the project. Whenever air-entrainment is required, the air content of trial batches shall be equal to or greater than the air content specified for the concrete without reduction due to tolerances.
- Tests shall be performed in conformance with either the appropriate California Test methods or the comparable ASTM test methods. Equipment employed in testing shall be in good condition and shall be properly calibrated. If the tests are performed during the life of the contract, the Engineer shall be notified sufficiently in advance of performing the tests in order to witness the test procedures.
 - The certified test data and trial batch test reports shall include the following information:
 - A. Date of mixing.
 - B. Mixing equipment and procedures used.
 - C. The size of batch in cubic meters and the mass, type, and source of all ingredients used.
 - D. Penetration of the concrete.
 - E. The air content of the concrete if an air-entraining admixture is used.
 - F. The age at time of testing and strength of all concrete cylinders tested.
 - Certified test data and trial batch test reports shall be signed by an official of the firm that performed the tests.
- When approved by the Engineer, concrete from trial batches may be used in the work at locations where concrete of a lower quality is required and the concrete will be paid for as the type or class of concrete required at that location.
- After materials, mix proportions, mixing equipment, and procedures for concrete have been prequalified for use, additional prequalification by testing of trial batches will be required prior to making changes that, in the judgment of the Engineer, could result in a strength of concrete below that specified.
- The Contractor's attention is directed to the time required to test trial batches and the Contractor shall be responsible for production of trial batches at a sufficiently early date so that the progress of the work is not delayed.
- When precast concrete members are manufactured at the plant of an established manufacturer of precast concrete members, the mix proportions of the concrete shall be determined by the Contractor, and a trial batch and prequalification of the materials, mix proportions, mixing equipment, and procedures will not be required.

90-10 MINOR CONCRETE

90-10.01 GENERAL

• Concrete for minor structures, slope paving, curbs, sidewalks and other concrete work, when designated as minor concrete on the plans, in the specifications, or in the contract item, shall conform to the provisions specified herein.

• The Engineer, at the Engineer's discretion, will inspect and test the facilities, materials and methods for producing the concrete to ensure that minor concrete of the quality suitable for use in the work is obtained.

90-10.02 MATERIALS

• Minor concrete shall conform to the following requirements:

90-10.02A Cementitious Material

• Cementitious material shall conform to the provisions in Section 90-1.01, "Description."

90-10.02B Aggregate

- Aggregate shall be clean and free from deleterious coatings, clay balls, roots, and other extraneous materials.
- The Contractor shall submit to the Engineer for approval, a grading of the combined aggregate proposed for use in the minor concrete. After acceptance of the grading, aggregate furnished for minor concrete shall conform to that grading, unless a change is authorized in writing by the Engineer.
- The Engineer may require the Contractor to furnish periodic test reports of the aggregate grading furnished. The maximum size of aggregate used shall be at the option of the Contractor, but in no case shall the maximum size be larger than 37.5 mm or smaller than 19 mm.
- The Engineer may waive, in writing, the gradation requirements in this Section 90-10.02B, if, in the Engineer's opinion, the furnishing of the gradation is not necessary for the type or amount of concrete work to be constructed.

90-10.02C Water

• Water used for washing, mixing, and curing shall be free from oil, salts, and other impurities that would discolor or etch the surface or have an adverse affect on the quality of the concrete.

90-10.02D Admixtures

• The use of admixtures shall conform to the provisions in Section 90-4, "Admixtures."

90-10.03 PRODUCTION

- Cementitious material, water, aggregate, and admixtures shall be stored, proportioned, mixed, transported, and discharged in conformance with recognized standards of good practice that will result in concrete that is thoroughly and uniformly mixed, that is suitable for the use intended, and that conforms to requirements specified herein. Recognized standards of good practice are outlined in various industry publications such as are issued by American Concrete Institute, AASHTO, or the Department.
- The cementitious material content of minor concrete shall conform to the provisions in Section 90-1.01, "Description."
- The amount of water used shall result in a consistency of concrete conforming to the provisions in Section 90-6.06, "Amount of Water and Penetration." Additional mixing water shall not be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer.
- Discharge of ready-mixed concrete from the transporting vehicle shall be made while the concrete is still plastic and before stiffening occurs. An elapsed time of 1.5 hours (one hour in non-agitating hauling equipment), or more than 250 revolutions of the drum or blades, after the introduction of the cementitious material to the aggregates, or a temperature of concrete of more than 32°C will be considered conditions contributing to the quick stiffening of concrete. The Contractor shall take whatever action is necessary to eliminate quick stiffening, except that the addition of water will not be permitted.
 - The required mixing time in stationary mixers shall be not less than 50 seconds or more than 5 minutes.
- The minimum required revolutions at mixing speed for transit-mixed concrete shall be not less than that recommended by the mixer manufacturer, and shall be increased, if necessary, to produce thoroughly and uniformly mixed concrete.
- Each load of ready-mixed concrete shall be accompanied by a weighmaster certificate that shall be delivered to the Engineer at the discharge location of the concrete, unless otherwise directed by the Engineer. The weighmaster certificate shall be clearly marked with the date and time of day when the load left the batching plant and, if hauled in truck mixers or agitators, the time the mixing cycle started.
- A Certificate of Compliance conforming to the provisions in Section 6–1.07, "Certificates of Compliance," shall be furnished to the Engineer, prior to placing minor concrete from a source not previously used on the contract, stating that minor concrete to be furnished meets contract requirements, including minimum cementitious material content specified.

90-10.04 CURING MINOR CONCRETE

Curing minor concrete shall conform to the provisions in Section 90-7, "Curing Concrete."

90-10.05 PROTECTING MINOR CONCRETE

• Protecting minor concrete shall conform to the provisions in Section 90-8, "Protecting Concrete," except the concrete shall be maintained at a temperature of not less than 4°C for 72 hours after placing.

90-10.06 MEASUREMENT AND PAYMENT

• Minor concrete will be measured and paid for in conformance with the provisions specified in the various sections of these specifications covering concrete construction when minor concrete is specified in the specifications, shown on the plans, or indicated by contract item in the Engineer's Estimate.

90-11 MEASUREMENT AND PAYMENT

90-11.01 MEASUREMENT

- Portland cement concrete will be measured in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.
- When it is provided that concrete will be measured at the mixer, the volume in cubic meters shall be computed as the total mass of the batch in kilograms divided by the density of the concrete in kilograms per cubic meter. The total mass of the batch shall be calculated as the sum of all materials, including water, entering the batch. The density of the concrete will be determined in conformance with the requirements in California Test 518.

90-11.02 PAYMENT

- Portland cement concrete will be paid for in conformance with the provisions specified in the various sections of these specifications covering construction requiring concrete.
- Full compensation for furnishing and incorporating admixtures required by these specifications or the special provisions will be considered as included in the contract prices paid for the concrete involved and no additional compensation will be allowed therefor.
- Should the Engineer order the Contractor to incorporate any admixtures in the concrete when their use is not required by these specifications or the special provisions, furnishing the admixtures and adding them to the concrete will be paid for as extra work as provided in Section 4-1.03D, "Extra Work."
- Should the Contractor use admixtures in conformance with the provisions in Section 90-4.05, "Optional Use of Chemical Admixtures," or Section 90-4.07, "Optional Use of Air-entraining Admixtures," or should the Contractor request and obtain permission to use other admixtures for the Contractor's benefit, the Contractor shall furnish those admixtures and incorporate them into the concrete at the Contractor's expense and no additional compensation will be allowed therefor.

SECTION 12. (BLANK)

SECTION 13. RAILROAD RELATIONS AND INSURANCE REQUIREMENTS SECTION 13-1. RELATIONS WITH RAILROAD COMPANY

13-1.01 GENERAL.- The term "Railroad" shall be understood to mean the Union Pacific Railroad Company.

It is expected that the Railroad will cooperate with the Contractor to the end that the work may be handled in an efficient manner. However, except for the additional compensation provided for hereinafter for delays in completion of specific unit of work to be performed by the Railroad, and except as provided in Public Contracts Code Section 7102, the Contractor shall have no claim for damages, extension of time, or extra compensation in the event his work is held up by any of the work to be performed by the Railroad.

The Contractor must understand the Contractor's right to enter Railroads property is subject to the absolute right of Railroad to cause the Contractor's work on Railroad's property to cease if, in the opinion of Railroad, Contractor's activities create a hazard to Railroad's property, employees, and/or operations.

The Contractor will be required to sign and submit to the Railroad the Contractor's Endorsement, in the form attached hereto.

• RAILROAD REQUIREMENTS. The contractor shall notify, Manager Industry and Public Projects, 10031 Foothills Boulevard, Roseville, CA 92316 Telephone (916) 789-6352 and the Engineer, in writing, at least ten (10) working days before performing any work on, or adjacent to the property or tracks of the Railroad.

The Contractor shall cooperate with the Railroad where work is over or under the tracks, or within the limits of Railroad property, in order to expedite the work and to avoid interference with the operation of railroad equipment.

The Contractor shall comply with the rules and regulations of Railroad or the instructions of its representatives in relation to the proper manner of protecting the tracks and property of Railroad and the traffic moving on such tracks, as well as the wires, signals and other property of Railroad, its tenants or licensees, at and in the vicinity of the work during the period of construction.

The Contractor shall perform his work in such manner and at such times as shall not endanger or interfere with the safe operation of the tracks and property of Railroad and traffic moving on such tracks, as well as wires, signals and other property of Railroad, its tenants or licensees, at or in the vicinity of the work.

The Contractor shall take protective measures necessary to keep railroad facilities, including track ballast, free of sand or debris resulting from his operations. Any damage to railroad facilities resulting from Contractor's operations will be repaired or replaced by Railroad and the cost of such repairs or replacement shall be deducted from the contractor's progress and final pay estimates.

The Contractor shall contact the Railroad's "Call Before You Dig" at least 48 hours prior to commencing work, at 1-800-336-9193 (a 24 hour number) to determine location of fiber optics. If a telecommunications system is buried anywhere on or near railroad property, the Contractor will co-ordinate with the Railroad and the Telecommunication Company(ies) to arrange for relocation or other protection of the system prior to beginning any work on or near Railroad Property.

The Contractor shall not pile or store any materials nor park any equipment closer than 25'- 0" to the centerline of the nearest track, unless directed by Railroad's representative.

The Contractor shall also abide by the following temporary clearances during the course of construction:

12'-0" horizontally from centerline of track

21'-0" vertically above top of rail

The temporary vertical construction clearance above provided will not be permitted until authorized by the Public Utilities Commission. It is anticipated that authorization will be received not later than fifteen days after the approval of the contract by the Attorney General. In the event authorization is not received by the time specified, and, if in the opinion of the Engineer, the Contractor's operations are delayed or interfered with by reason of authorization not being received by the said time, the State will compensate the Contractor for such delay to the extent provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications and not otherwise.

Walkways with railing shall be constructed by Contractor over open excavation areas when in close proximity of tracks, and railings shall not be closer than 8'-6" horizontally from centerline of the nearest track, if tangent, or 9'-6" if curved.

Any infringement on the above temporary construction clearances due to the Contractor's operations shall be submitted to the Railroad by way of Engineer, and shall not be undertaken until approved by the Railroad, and until the Engineer has obtained any necessary authorization from any governmental body or bodies having jurisdiction thereover. No extension of time or extra compensation will be allowed in the event the Contractor's work is delayed pending Railroad approval and governmental authorization.

When the temporary vertical clearance is less than 22'-6" above top of rail, Railroad shall have the option of installing tell-tales or other protective devices Railroad deems necessary for protection of Railroad trainmen or rail traffic.

Four sets of plans, in 11" x 17" format, and two sets of calculations showing details of construction affecting the Railroad's tracks and property not included in the contract plans, including but not limited to shoring and falsework, shall be submitted to the Engineer for review prior to submittal to Railroad for final approval. Falsework shall comply with UPRR guidelines. Demolition of existing structures shall comply with UPRR guidelines. Shoring shall be designed in accordance with UPRR's shoring requirement of Drawing No. 106613 and guidelines for shoring and falsework, latest edition, issued by the Railroad's Office of Chief Engineer. Shoring and falsework plans and calculations shall be prepared and signed by a registered professional engineer. This work shall not be undertaken until such time as the Railroad has given such approval, review by Railroad may take up to six (6) weeks after receipt of all necessary information.

The Contractor shall notify the Engineer in writing, at least 25 calendar days but not more than 40 days in advance of the starting date of installing temporary work with less than permanent clearance at each structure site. The Contractor will not be permitted to proceed with work across railroad tracks unless this requirement has been met. No extension of time or extra compensation will be allowed in the event that the Contractor's work is delayed because of his failure to comply with the requirements in this paragraph.

Private crossings at grade over tracks of Railroad for the purpose of hauling earth, rock, paving or other materials will not be permitted. If the Contractor, for the purpose of constructing highway-railway grade separation structures, including construction ramps thereto, desires to move equipment or materials across Railroad's tracks, Contractor must first obtain permission from Railroad. Should Railroad approved the crossing, Contractor may be required to execute a private crossing agreement. By this agreement, the Contractor would be required to bear the cost of the crossing surface, together with any warning devices that might be required. Contractor shall furnish his own employees as flagmen to control movements of vehicles on the private roadway and shall take all measures necessary to prevent the use of such roadway by unauthorized persons and vehicles.

No blasting will be permitted by Contractor unless approved by the Railroad.

The Contractor shall, upon completion of the work covered by this contract to be performed by Contractor upon the premises or over or beneath the tracks of Railroad, promptly remove from the premises of Railroad all of Contractor's tools, implements and other materials, whether brought upon said premises by said Contractor or any subcontractor, employee or agent of Contractor or of any subcontractor, and cause said premises to be left in a clean and presentable condition.

All under track pipeline installations shall be constructed in accordance with Railroad's current standards which may be obtained from Railroad. The general guidelines are as follows:

Edges of jacking or boring pit excavations shall be kept a minimum of 20 feet from the centerline of the nearest track. If the pipe to be installed under the track is four (4) inches in diameter or less, the top of the pipe shall be at least 42 inches below base of rail. If the pipe diameter is greater than four (4) inches in diameter, it must be encased and the top of the steel pipe casing shall be at least 66 inches below base of rail. Installation of any pipe or conduit under Railroad's tracks is to be done by dry bore and jack method. No hydraulic jacking or boring will be permitted. Care is to be exercised so as not to damage any underground facilities of Railroad.

13-1.03 PROTECTION OF RAILROAD FACILITIES

- (1). Upon advance notification of not less than ten (10) working days by Contractor, Railroad representatives, conductors, flagmen or watchmen will be provided by Railroad to protect its facilities, property and movements of its trains or engines. Said notice shall be made to , Manager Industry and Public Projects of Railroad at (916) 789-6352. At the time of such notification, Contractor shall provide Railroad with a schedule of dates that flagging services will be needed , as well as times, if outside normal working hours. Any subsequent deviation from said schedule shall also require ten (10) working days advance notice from the first affected date. In general, Railroad will furnish such personnel or other protective devices:
 - (a) When any part of any equipment is standing or being operated within 25 feet, measured horizontally, from centerline of any track on which trains may operate, or when any erection or construction activities are in progress within such limits, regardless of elevation above or below track.
 - (b) For any excavation below elevation of track subgrade if, in the opinion of Railroad's representative, track or other Railroad facilities may be subject to settlement or movement.
 - (c) During any clearing, grubbing, grading or blasting in proximity to Railroad which, in the opinion of Railroad's representative, may endanger Railroad facilities or operations.
 - (d) During any of Contractor's operations when, in the opinion of Railroad's representatives, Railroad facilities, including, but not limited to, tracks, buildings, signals, wire lines or pipe lines, may be endangered.
- The cost of flagging and inspection provided by Railroad during the period of constructing that portion of the project located on or near Railroad property, as deemed necessary for the protection of Railroad's facilities and trains, will be borne by the State for a period of 80 working days beginning on the date work commences on or near property of Railroad. The Contractor shall pay to the State liquidated damages in the sum of \$500 per day for each day in excess of the above 80 working days the Contractor works on or near Railroad property, and which requires flagging protection of Railroad's facilities and trains.
- 13-1.04 WORK BY RAILROAD. Railroad will furnish or cause to be furnished as necessary due to construction, labor materials, tools and equipment to perform certain works including relocation of telephone, telegraphy and signal lines and appurtenances and will perform any other work in connection therewith.

The work by Railroad will be performed by its own forces and is not a part of the work under this contract.

(a) The Railroad will perform preliminary engineering inspection and flagging as specified in Section 13-1.03 "Protection of Railroad Facilities".

13-1.05 DELAYS DUE TO WORK BY RAILROAD. No delays due to work by Railroad are anticipated.

If delays due to work by the Railroad occur, and the Contractor sustains loss which, in the opinion of the Engineer, could not have been avoided by the judicious handling of forces, equipment and plant, the amount of said loss shall be determined as provided in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

If a delay due to work by Railroad occurs, an extension of time determined pursuant to the provisions in Section 8-1.07, "Liquidated Damages," of the Standard Specifications will be granted.

13-1.05 LEGAL RELATIONS.- The provisions of this section, "Relations with Railroad Company" and the provisions of the following section, "Railroad Protective Insurance," of these special provisions shall inure directly to the benefit of Railroad

SECTION 13-2. RAILROAD PROTECTIVE INSURANCE

The term "Railroad" shall be understood to mean the Union Pacific Railroad Company.

In addition to any other form of insurance or bonds required under the terms of the contract and specifications, the Contractor will be required to carry insurance of the kinds and in the amounts hereinafter specified.

Such insurance shall be approved by the Railroad before any work is performed on Railroad's property and shall be carried until all work required to be performed on or adjacent to the Railroad's property under the terms of the contract is satisfactorily completed as determined by the Engineer, and thereafter until all tools, equipment and materials have been removed from Railroad's property and such property is left in a clean and presentable condition.

The insurance herein required shall be obtained by the Contractor, who shall furnish the Railroad with completed certificates, in the form attached hereto, signed by the insurance company or its authorized agent or representative, reflecting the existence of each of the policies required by 1 and 2 below including coverage for X, C and U and completed operations hazards, and the original policy of insurance (or a certified duplicate original policy) required by 3 below, to:

Union Pacific Railroad Company Insurance Group 1416 Dodge Street, Room 820 Omaha, NE 68179

Certificate of insurance shall guarantee that the policy under 1 and 2 will not be amended, altered, modified or canceled insofar as the coverage contemplated hereunder is concerned, without at least thirty (30) days notice mailed by registered mail to the Railroad.

Full compensation for all premiums which the Contractor is required to pay on all the insurance described hereinafter shall be considered as included in the prices paid for the various items of work to be performed under the contract, and no additional allowance will be made therefor or for additional premiums which may be required by extensions of the policies of insurance.

The approximate ratio of the estimated cost of the work over or under or within 50 feet of Railroad's tracks to the total estimated cost is 0.001. Approximate daily train traffic is 0 passenger trains and 20 freight trains.

1. Contractor's Public Liability and Property Damage Liability Insurance

The Contractor shall, with respect to the operations he performs within or adjacent to Railroad's property, carry regular Contractor's Public Liability and Property Damage Liability Insurance providing for the same limits as specified for Railroad's Protective Public Liability and Property Damage Liability insurance to be furnished for and in behalf of Railroad as hereinafter provided.

If any part of the work within or adjacent to Railroad's property is subcontracted, the Contractor in addition to carrying the above insurance shall provide the above insurance on behalf of the subcontractors to cover their operations.

2. Contractor's Protective Public Liability and Property Damage Liability Insurance.

The Contractor shall, with respect to the operations performed for him by subcontractors who do work within or adjacent to Railroad's property, carry in his own behalf regular Contractor's Protective Public Liability and Property Damage Liability Insurance providing for the same limits as specified for Railroad's Protective Public Liability and Property Damage Liability Insurance to be furnished for and on behalf of Railroad as hereinafter provided.


3. Railroad's Protective Public Liability and Property Damage Liability Insurance

The Contractor shall, with respect to the operations he performs within or adjacent to Railroad's property or that of any of his subcontractors who do work within or adjacent to Railroad's property perform, have issued and furnished in favor of Railroad, Policy or policies of insurance in the Railroad Protective Liability Form as hereinafter specified.

Railroad Protective Liability Form

(Name of Insurance Company)

DECLARATIONS



Item 4. Name and Address of Contractor:

Item 5. Name and Address of Governmental Authority for whom the work by the Contractor is being performed: State of California, acting by and through its Department of Transportation, P.O. Box 942874, Sacramento, California 94274-0001

nem 6. De		TRUCTION ON	ripuon oi work:		
					
	Premium Bases	Rates pe Coverage A	er \$100 of Cost Coverage's B & C		ce Premiums Coverage's B & C
	Contract Cost	\$	\$	\$	\$
	Rental Cost	\$	\$	\$	\$
	Countersigne	ed	, 20 by		
	S				
	tle			(Name of Insu	rance Company)
POLICY	insured, nan premium and	ned in the declaration	ons made a part hereof he statements in the dec	, in consideration	company, agrees with the on of the payment of the py the named insured and
			INSURING AGREEN	MENTS	
	I. Coveraș	ge ABodily Injury	Liability.		
	to pay a resulting arising connecti designat of the G	is damages because g therefrom, hereing out of acts or omision with the work ated job site by the Covernmental Autho	of bodily injury, sickness after called "bodily injustions at the designated described in Item 6 of contractor or any employ	ss, or disease, in ury," either (1) I job site which the declaration wee of the Contra of the Declarati	become legally obligated cluding death at any time sustained by any person a are related to or are in s, or (2) sustained at the actor, or by any employee ons, or by any designated missions.

Coverage B--Property Damage Liability.

To pay on behalf of the insured all sums which the insured shall become legally obligated to pay as damages because of physical injury to or destruction of property, including loss of use of any property due to such injury or destruction, hereinafter called "property damage," arising out of acts or omissions at the designated job site which are related to or are in connection with the work described in Item 6 of the declarations.

Coverage C--Physical Damage to Property.

To pay for direct and accidental loss of or damage to rolling stock and their contents, mechanical construction equipment, or motive power equipment, hereinafter called "loss," arising out of acts or omissions at the designated job site which are related to or are in connection with the work described in Item 6 of the declarations; provided such property is owned by the named insured or is leased or entrusted to the named insured under a lease or trust agreement.

II. Definitions.

- (a) **Insured.--**The unqualified word "insured" includes the named insured and also includes any executive officer, director or stockholder thereof while acting within the scope of his duties as such.
- (b) **Contractor.--**The word "contractor" means the Contractor designated in Item 4 of the declarations and includes all subcontractors of said Contractor but shall not include the named insured.
- (c) Designated employee of the insured.--The words "designated employee of the insured" mean:
 - (1) any supervisory employee of the insured at the job site,
 - (2) any employee of the insured while operating, attached to or engaged on work trains or other railroad equipment at the jobsite which are assigned exclusively to the Contractor, or
 - (3) any employee of the insured not within (1) or (2) who is specifically loaned or assigned to the work of the Contractor for prevention of accidents or protection of property, the cost of whose services is borne specifically by the Contractor or by governmental authority.
- (d) Contract.--The word "contract" means any contract or agreement to carry a person or property for a consideration or any lease, trust or interchange contract or agreement respecting motive power, rolling stock or mechanical construction equipment.

III. Defense, Settlement, Supplementary Payments.

With respect to such insurance as is afforded by this policy under Coverage's A and B, the company shall:

- (a) defend any suit against the insured alleging such bodily injury or property damage and seeking damages which are payable under the terms of this policy, even if any of the allegations of the suit are groundless, false or fraudulent; but the company may make such investigation and settlement of any claim or suit as it deems expedient;
- (b) pay, in addition to the applicable limits of liability:
 - (1) all expenses incurred by the company, all costs taxed against the insured in any such suit and all interest on the entire amount of any judgment therein which accrues after entry of the judgment and before the company has paid or tendered or deposited in court that part of the judgment which does not exceed the limit of the company's liability thereon;
 - (2) Premiums on appeal bonds required in any such suit, premiums on bonds to release attachments for an amount not in excess of the applicable limit of liability of this policy, but without obligation to apply for or furnish any such bonds;

- (3) expenses incurred by the insured for such immediate medical and surgical relief to others as shall be imperative at the time of the occurrence;
- (4) all reasonable expenses, other than loss of earnings, incurred by the insured at the company's request.

IV. Policy Period, Territory.

This policy applies only to occurrences and losses during the policy period and within the United States of America, its territories or possessions, or Canada.

EXCLUSIONS

This policy does not apply:

- (a) to liability assumed by the insured under any contract or agreement except a contract as defined herein;
- (b) to bodily injury or property damage caused intentionally by or at the direction of the insured;
- (c) to bodily injury, property damage or loss which occurs after notification to the named insured of the acceptance of the work by the governmental authority, other than bodily injury, property damage or loss resulting from the existence or removal of tools, uninstalled equipment and abandoned or unused materials;
- (d) under Coverage's A(1), B and C, to bodily injury, property damage or loss, the sole proximate cause of which is an act or omission of any insured other than acts or omissions of any designated employee of any insured;
- (e) under Coverage A, to any obligation for which the insured or any carrier as his insurer may be held liable under any workmen's compensation, unemployment compensation or disability benefits law, or under any similar law; provided that the Federal Employers' Liability Act, U.S. Code (1946), Title 45, Sections 51-60, as amended, shall for the purposes of this insurance be deemed not to be any similar law;
- (f) under Coverage B, to injury to or destruction of property (1) owned by the named insured or (2) leased or entrusted to the named insured under a lease or trust agreement.

- (g) 1. Under any liability coverage, to injury, sickness, disease, death or destruction
 - (a) with respect to which an insured under the policy is also an insured under a nuclear energy liability policy issued by Nuclear Energy Liability Insurance Association, Mutual Atomic Energy Liability Underwriters or Nuclear Insurance Association of Canada, or would be an insured under any such policy but for its termination upon exhaustion of its limit of liability; or
 - (b) resulting from the hazardous properties of nuclear material and with respect to which (1) any person or organization is required to maintain financial protection pursuant to the Atomic Energy Act of 1954, or any law amendatory thereof, or (2) the insured is, or had this policy not been issued would be, entitled to indemnity from the United States of America, or any agency thereof, under any agreement entered into by the United States of America, or any agency thereof, with any person or organization.
 - 2. Under any medical payments coverage, or under any Supplementary Payments provision relating to immediate medical or surgical relief, to expenses incurred with respect to bodily injury, sickness, disease or death resulting from the hazardous properties of nuclear material and arising out of the operation of a nuclear facility by any person or organization.
 - 3. Under any liability coverage, to injury, sickness, disease, death or destruction resulting from the hazardous properties of nuclear material, if
 - (a) the nuclear material (1) is at any nuclear facility owned by, or operated by or on behalf of, an insured or (2) has been discharged or dispersed therefrom;
 - (b) the nuclear material is contained in spent fuel or waste at any time possessed, handled, used, processed, stored, transported or disposed of by or on behalf of an insured; or
 - (c) the injury, sickness, disease, death or destruction arises out of the furnishing by an insured of services, materials, parts or equipment in connection with the planning, construction, maintenance, operation or use of any nuclear facility, but if such facility is located within the United States of America, its territories or possessions or Canada, this exclusion (c) applies only to injury to or destruction of property at such nuclear facility.

4. As used in this exclusion:

"hazardous properties" include radioactive, toxic or explosive properties;

"nuclear material" means source material, special nuclear material or byproduct material;

"source material", "special nuclear material", and "byproduct material" have the meanings given them in the Atomic Energy Act of 1954 or in any law amendatory thereof;

"spent fuel" means any fuel element or fuel component, solid or liquid, which has been used or exposed to radiation in a nuclear reactor;

"waste" means any waste material (1) containing byproduct material and (2) resulting from the operation by any person or organization of any nuclear facility included within the definition of nuclear facility under paragraph (a) or (b) thereof;

"nuclear facility" means

(a) any nuclear reactor,

- (b) any equipment or device designed or used for (1) separating the isotopes of uranium or plutonium, (2) processing or utilizing spent fuel, or (3) handling, processing or packaging waste,
- (c) any equipment or device used for the processing, fabricating or alloying of special nuclear material if at any time the total amount of such material in the custody of the insured at the premises where such equipment or device is located consists of or contains more than 25 grams of plutonium or uranium 233 or any combination thereof, or more than 250 grams of uranium 235,
- (d) any structure, basin, excavation, premises or place prepared or used for the storage or disposal of waste, and includes the site on which any of the foregoing is located, all operations conducted on such site and all premises used for such operations; "nuclear reactor" means any apparatus designed or used to sustain nuclear fission in a self-supporting chain reaction or to contain a critical mass of fissionable material; with respect to injury to or destruction of property, the word "injury" or "destruction" includes all forms of radioactive contamination of property.
- (h) under Coverage C, to loss due to nuclear reaction, nuclear radiation or radioactive contamination, or to any act or condition incident to any of the foregoing.

CONDITIONS

(The conditions, except conditions 3, 4, 5, 7, 8, 9, 10, 11 and 12, apply to all coverage's. Conditions 3, 4, 5, 7, 8, 9, 10, 11 and 12, apply only to the coverage noted thereunder.)

1. Premium.--The premium bases and rates for the hazards described in the declarations are stated therein. Premium bases and rates for hazards not so described are those applicable in accordance with the manuals in use by the company.

The term "contract cost" means the total cost of all work described in Item 6 of the declarations.

The term "rental cost" means the total cost to the Contractor for rental of work trains or other railroad equipment, including the remuneration of, all employees of the insured while operating, attached to or engaged thereon. The advance premium stated in the declarations is an estimated premium only. Upon termination of this policy the earned premium shall be computed in accordance with the company's rules, rates, rating plans, premiums and minimum premiums applicable to this insurance. If the earned premium thus computed exceeds the estimated advance premium paid, the company shall look to the Contractor specified in the declarations for any such excess; if less, the company shall return to the said Contractor the unearned portion paid.

In no event shall payment of premium be an obligation of the named insured.

2. Inspection.--The named insured shall make available to the company records of information relating to the subject matter of this insurance.

The company shall be permitted to inspect all operations in connection with the work described in Item 6 of the declarations.

- 3. Limits of Liability, Coverage A.--The limit of bodily injury liability stated in the declarations as applicable to "each person" is the limit of the company's liability for all damages, including damages for care and loss of services, arising out of bodily injury sustained by one person as the result of any one occurrence; the limit of such liability stated in the declarations as applicable to "each occurrence" is, subject to the above provision respecting each person, the total limit of the company's liability for all such damage arising out of bodily injury sustained by two or more persons as the result of any one occurrence.
- **4. Limits of Liability, Coverage's B and C.**—The limit of liability under Coverages B and C stated in the declarations as applicable to "each occurrence" is the total limit of the company's liability for all damages and all loss under Coverage B and C combined arising out of physical injury to, destruction or loss of all property of one or more persons or organizations, including the

loss of use of any property due to such injury or destruction under Coverage B, as the result of any one occurrence.

Subject to the above provision respecting "each occurrence," the limit of liability under Coverage's B and C stated in the declarations as "aggregate" is the total limit of the company's liability for all damages and all loss under Coverage's B and C combined arising out of physical injury to, destruction or loss of property, including the loss of use of any property due to such injury or destruction under Coverage B.

Under Coverage C, the limit of the company's liability for loss shall not exceed the actual cash value of the property, or if the loss is of a part thereof the actual cash value of such part, at time of loss, nor what it would then cost to repair or replace the property or such part thereof with other of like kind and quality.

- **5. Severalty of Interests, Coverage's A and B.--** The term "the insured" is used severally and not collectively, but the inclusion herein of more than one insured shall not operate to increase the limits of the company's liability.
- **6. Notice.--**In the event of an occurrence or loss, written notice containing particulars sufficient to identify the insured and also reasonably obtainable information with respect to the time, place and circumstances thereof, and the names and addresses of the injured and of available witnesses, shall be given by or for the insured to the company or any of its authorized agents as soon as practicable. If claim is made or suit is brought against the insured, he shall immediately forward to the company every demand, notice, summons or other process received by him or his representative.
- 7. Assistance and Cooperation of the Insured, Coverage's A and B.--The insured shall cooperate with the company and, upon the company's request, attend hearings and trials and assist in making settlements, securing and giving evidence, obtaining the attendance of witnesses and in the conduct of suits. The insured shall not, except at his own cost, voluntarily make any payment, assume any obligation or incur any expense other than for such immediate medical and surgical relief to others as shall be imperative at the time of accident.
- **8.** Action Against Company, Coverages A and B.--No action shall lie against the company unless, as a condition precedent thereto, the insured shall have fully complied with all the terms of this policy, nor until the amount of the insured's obligation to pay shall have been finally determined either by judgment against the insured after actual trial or by written agreement of the insured, the claimant and the company.

Any person or organization or the legal representative thereof who has secured such judgment or written agreement shall thereafter be entitled to recover under this policy to the extent of the insurance afforded by this policy. No person or organization shall have any right under this policy to join the company as a party to any action against the insured to determine the insured's liability. Bankruptcy or insolvency of the insured or of the insured's estate shall not relieve the company of any of its obligations hereunder.

Coverage C.--No action shall lie against the company unless, as a condition precedent thereto, there shall have been full compliance with all the terms of this policy nor until 30 days after proof of loss is filed and the amount of loss is determined as provided in this policy.

9. Insured's Duties in Event of Loss, Coverage C.--In the event of loss the insured shall:

- (a) protect the property, whether or not the loss is covered by this policy, and any further loss due to the insured's failure to protect shall not be recoverable under this policy; reasonable expenses incurred in affording such protection shall be deemed incurred at the company's request;
- (b) file with the company, as soon as practicable after loss, his sworn proof of loss in such form and including such information as the company may reasonably require and shall, upon the company's request, exhibit the damaged property.

10. Appraisal, Coverage C.--If the insured and the company fail to agree as to the amount of loss, either may, within 60 days after the proof of loss is filed, demand an appraisal of the loss. In such event the insured and the company shall each select a competent appraiser, and the appraisers shall select a competent and disinterested umpire. The appraisers shall state separately the actual cash value and the amount of loss and failing to agree shall submit their differences to the umpire. An award in writing of any two shall deter-mine the amount of loss. The insured and the company shall each pay his chosen appraiser and shall bear equally the and umpire.

The company shall not be held to have waived any of its rights by any actrelating to appraisal.

- **11. Payment of Loss, Coverage C.--**The company may pay for the loss in money but there shall be no abandonment of the damaged property to the company.
- 12. No Benefit to Bailee, Coverage C.-- The insurance afforded by this policy shall not inure directly or indirectly to the benefit of any carrier or bailee, other than the named insured, liable for loss to the property.
- 13. Subrogation.--In the event of any payment under this policy, the company shall be subrogated to all the insured's rights of recovery therefor against any person or organization and the insured shall execute and deliver instruments and papers and do whatever else is necessary to secure such rights. The insured shall do nothing after loss to prejudice such rights.
 - **14. Application of Insurance.**--The insurance afforded by this policy is primary insurance.
- **15. Three Year Policy.**--A policy period of three years is comprised of three consecutive annual periods. Computation and adjustment of earned premium shall be made at the end of each annual period. Aggregate limits of liability as stated in this policy shall apply separately to each annual period.
- **16.** Changes.--Notice to any agent or knowledge possessed by any agent or by any other person shall not effect a waiver or a change in any part of this policy or stop the company from asserting any right under the terms of this policy; nor shall the terms of this policy be waived or changed, except by endorsement issued to form a part of this policy.
- **17. Assignment.-**-Assignment of interest under this policy shall not bind the company until its consent is endorsed hereon.
- 18. Cancellation.--This policy may be canceled by the named insured by mailing to the company written notice stating when thereafter the cancellation shall be effective. This policy may be canceled by the company by mailing to the named insured, Contractor and governmental authority at the respective addresses shown in this policy written notice stating when not less than 30 days thereafter such cancellation shall be effective. The mailing of notice as aforesaid shall be sufficient proof of notice. The effective date and hour of cancellation stated in the notice shall become the end of the policy period. Delivery of such written notice either by the named insured or by the company shall be equivalent to mailing.

If the named insured cancels, earned premium shall be computed in accordance with the customary short rate table and procedure. If the company cancels, earned premium shall be computed pro rata. Premium adjustment may be made either at the time cancellation is effected or as soon as practicable after cancellation becomes effective, but payment or tender of unearned premium is not a condition of cancellation.

in the declarations as are made by him are his a issued in reliance upon the truth of such rep	icy the named insured agrees that such statements agreements and representations, that this policy is presentations and that this policy embodies all company or any of its agents relating to this
In witness whereof, the	_ Insurance Company has caused this policy to be
signed by its president and a secretary at	, and countersigned on the declaration page
by a duly authorized agent of the company.	
(Facsimile of Signature)	(Facsimile of Signature)
Secretary	President

CERTIFICATE OF INSURANCE Exhibit "C"

		E	XIIIDIL C		
Thi	is is to certify to:		M.P. 273.0	D FILE NO.: 0, Valley Subdivision r., Gray Rocks, CA.	
(1)	Railroad Agreements Branch, Engineering Services California Department of Tran 1801 30th Street, Sacramento,	sportation			
(2)	and to the following Railroad	Company			
dar	t such insurance as is afforded nage liability is in full force and ured with respect to liability in nection with the contract or wo	l effect as of the date for damages arising	of this certificate and cover	rs the following contractor as a	named
1.	Named Insured and Address				
this	is is to certify that policies of in s time. Notwithstanding any re- s certificate may be issued or m ms, exclusions and conditions of	quirement, term or co ay pertain, the insura	ondition of any contract or	other document with respect to	which
2.	Description of Work				
	Contract No	•			
В	Coverage's ontractor's odily Injury Liability and operty Damage Liability	Policy Expiration Date	Limits of Liability Each Occurrence	Aggregate	
Uı	mbrella or Excess Liability				
All	of the coverages include covera	nge for the completed	l operations hazard, and X, (C and U exposures.	
	Ü		Company by Coverage	•	
Co	verage's	Company		Number	
	dily Injury Liability	Company	roncy	Number	
	pperty Damage Liability				
	abrella or Excess Liability				
4.	The policy or policies descr days after written notice therecertificate.			odified or cancelled until thir oad named as certificate holder	
Cei	rtificate Date:				

For _____

(Insurance Company)	
	State of California
By	Department of Transportation
(Authorized Agent or Representative)	DH-0S-A104(8-10-99)

CONTRACTOR'S ENDORSEMENT

to comply with and be bound by all the terms and provisions of this agreement relating to the work to be performed and the insurance requirements set forth in Section 13 of the Contract Special Provisions. B. Before the Contractor commences any work, the Contractor will provide the Railroad with (1) a binder of insurance for the Railroad Protective Liability Insurance described in Section 13.2 of the Contract Special Provisions, and the original policy (or a certified duplicate original policy), and (2) a certificate issued by its insurance carrier providing the other insurance coverage required pursuant to Section 13.2 of the Contract Special Provisions in a policy or policies which contain the following type endorsement: UNION PACIFIC RAILROAD COMPANY is named as an additional insured with
insurance for the Railroad Protective Liability Insurance described in Section 13.2 of the Contract Special Provisions, and the original policy (or a certified duplicate original policy), and (2) a certificate issued by its insurance carrier providing the other insurance coverage required pursuant to Section 13.2 of the Contract Special Provisions in a policy or policies which contain the following type endorsement:
UNION PACIFIC RAILROAD COMPANY is named as an additional insured with
respect to all liabilities arising out of Insured's performance of work on behalf of the State.
C. This endorsement shall be completed and directed to:
Mr. James H. Smith Manager Industry & Public Projects 10031 Foothills Boulevard, Roseville, CA 95747 (9169) 789-6352
CONTRACTOR (print name on above line)
col. The college interpretation and the college interpretation
By: